

JOURNAL OF THE INSTITUTION OF CIVIL ENGINEERS.

No. 8. 1936-37.
OCTOBER 1937.

INSTITUTION LECTURE TO STUDENTS, 1936-37.¹

"Modern Methods of Structural Design."

By Professor JOHN FLEETWOOD BAKER, M.A., D.Sc.,
Assoc. M. Inst. C.E.

INDIVIDUAL experience and particular conditions play so important a part in the complete process of design that it would be unprofitable, even if it were possible here, to attempt a detailed consideration of all that design means. The scope of this Lecture will be strictly limited to that part concerned with the strength of the structure.

Even in this comparatively narrow field, the designer's task of producing a structure of adequate strength is complex. So complex is it that assumptions must be made, not only to make good deficiencies in the knowledge of conditions but with the avowed object of simplifying the strength-calculations. Whatever advances in knowledge may be made, it is unlikely that this state of affairs will change radically; those of you engaged in design know that involved methods of calculation are usually impracticable. Simplification can, however, be bought at too great a price. There is, in some branches of structural engineering, a tendency for assumptions to be chosen because they make some simple calculation possible, even though they are so sweeping that the true behaviour of the structure is disguised. Under these conditions, while it may be possible, with the safeguard of large load-factors, to produce stable structures, any evolution of the method of construction is impossible. Although regrettable, this is not surprising. The designer is not averse to adopting improved methods when they are found, but he cannot,

¹ This Lecture was delivered at a meeting of the Association of London Students, and was repeated before the Local Associations at Belfast, Birmingham, Bristol, Cardiff, Glasgow, Manchester, Newcastle, and Sheffield.—
ACTING SEC. INST. C.E.

except when dealing with a major structure, such as a Sydney Harbour bridge, afford to devote his time to the search. Other investigators, though giving a great deal of attention to the development of new methods of stress-analysis, have done relatively little to produce new methods of design. Developments in stress-analysis do not influence design directly, since they do no more than make easier the determination of the stress-distribution in a structure when the sections of the members have been chosen, and it is only in the more important cases that the labour of making a tentative design and modifying it by subsequent analysis is offset, economically, by the greater efficiency of the final result. That the production of design-methods has lagged behind stress-analysis is shown by the fact that, apart from the beam resting on simple supports, the only form of structure that can be designed directly by methods common in practice, with any confidence that the maximum stresses in the members produced by the assumed loading will be a close approximation to the permissible stresses chosen, is the simple truss having pin-joints. Even there, owing to the behaviour of bars subjected to compressive loads and to the somewhat archaic formulas still commonly used for the permissible end-loads on such bars, it is probable that the maximum stress in a strut will not be a close approximation to the value intended by the designer. Although the simple truss is a common form, it is rarely built with effective pin-joints. More often in practice, by the use of riveting to gusset-plates, the joint is practically rigid, preventing appreciable relative rotation of the ends of the members joined and thus introducing bending restraints when load is applied. These restraints develop bending stresses in the members, and in all but the lightest trusses it is necessary to see that they are not excessive. Since the magnitudes of these secondary bending stresses can only be gauged when the proportions of the members are known, this is a case where tentative design based on a simplifying assumption is used. It is, therefore, also one which is more readily affected by advances in stress-analysis, and it may be worth while to draw attention to a new approach to the problem which has been made possible by the recent work of Hardy Cross, Professor of Structural Engineering in the University of Illinois. His original Paper ¹ should be studied by all students for two reasons. It sets out a novel principle, having already far-reaching effects on the designer's attitude towards those problems of stress-analysis arising in rigidly-jointed structures which the use of reinforced concrete and of welded steelwork have brought to the fore. It does so in a refreshingly concise and simple form not usual

¹ H. Cross, "Analysis of Continuous Frames by Distributing Fixed-End Moments," Trans. Am. Soc. C.E., Vol. 96 (1932), p. 1.

in technical papers and extremely difficult to emulate successfully. As the Cross or moment-distribution method may not be familiar to all of you it will be well here, before considering the effect of the bending stress on the strength of a truss, to give an example of the determination of this stress by the new method. It should, however, first be noted that, whilst the rigidity of joints may in some cases have an appreciable effect on the deflexions of a truss, it is usual to be satisfied with a first approximation and to assume that the deflexions of the joints of the actual truss are the same as those of the frame with pinned joints in place of rigid joints. These deflexions are easily calculated, and the problem of secondary-stress determination is, therefore, that of finding the bending stresses in a rigidly jointed truss when the joints are forced to take up known deflexions.

In the classic slope-deflexion method which will be familiar to you all, the deflected structure is first considered to be pin-jointed, with the result that the angles between the bars change. The moments which must be applied to the members to force their ends back into the relative angular positions set by the rigid joints are then determined by forming and solving as many simultaneous equations as there are joints in the frame. In the Cross method, on the other hand, the joints are kept rigid throughout. They are first forced to take up the pre-determined deflexions, but any rotation of the joints is prevented. The resulting end moments can be written down without trouble but they are not, of course, the final values giving rise to the secondary stresses, since it is necessary to apply external couples at each joint to prevent rotation. These external couples must be removed; each joint is released in turn while the others are kept fixed. A joint, on the removal of the external couple, rotates until it reaches an equilibrium position, and in doing so modifies the moments in the members connected to it. These modifications can be found without difficulty, and the process of releasing joints is continued until the changes in the end moments become small enough to be neglected.


The method will be more readily understood by reference to an example. The secondary bending stresses produced in the cantilever frame shown in *Fig. 1* * when a load of 20,000 lbs. is hung from R will be determined. All the members of the frame have the same cross-section and are connected together through gusset-plates which prevent any change in angle between the ends of the members. When the load is applied the structure deflects, joints Q and R moving down the same distance, 0.038 inch, and joint R moving to the left 0.010 inch, deflexions which can be found with ease by means

* Reproduced by permission of the University Press, Cambridge.

of a Williot diagram if the assumption of pin-joints, already referred to, is made. The condition of the rigidly-jointed structure can be gauged to some extent from the behaviour of the model, built of spring steel and attached at P and S to a back-board, illustrated in *Figs. 2*. It is shown unloaded in *Figs. 2 (a)* and in its final deflected form under load in *Figs. 2 (d)*, where the bending induced in the members is apparent.¹

The model can be used conveniently to show the procedure in the Cross method of determining the secondary bending stresses. As I have said, in the first step when the joints are moved into their pre-determined deflected positions all rotation is prevented. This step can be carried out on the model by moving joints Q and R through

Fig. 1.



Young's modulus = 30×10^6 lbs. per square inch.


Relevant moment of inertia of member (I_{xx}) = 10 inch⁴ units.

Cross-sectional area of member = 4 square inches.


the distances already calculated and inserting stops between the gusset-plates and the back-board so that the joints retain their original angular positions. The state of the model at this stage is shown in *Figs. 2 (b)*, and it is clear from the positions of the pointers Q' and R', which are rigidly attached to the gusset-plates, that whilst deflexion of the joints has been allowed, rotation has been prevented. Each member is, therefore, behaving as an encastré beam and, due to the relative deflexion of the ends, fixing moments of magnitude $\frac{6EI\delta}{L^2}$ are induced at the ends, E denoting Young's

¹ In order to make the demonstration clear, exaggerated deflexions of the model, *Figs. 2*, were obtained by making the ends of the diagonal at P and the strut at S free to slide longitudinally.

Figs. 2.




(a)



(b)




(c)




(d)

DEFORMATION OF CANTILEVER FRAME.


Figs. 9.




(a)



(b)



(c)



(d)

FRAME WITH LOADS ARRANGED TO PRODUCE DOUBLE- AND SINGLE-CURVATURE BENDING.

make the calculation simple the external couples are not all removed at the same time. First release Q, which, in the model, means removing the stops inserted between it and the back-board, keeping the other joints fixed. Q rotates into a new equilibrium position, as can be seen from *Figs. 2 (c)*, and in so doing modifies the end moments on the members. The modification can be calculated with ease since the removal of an external couple of $-24,140$ lbs.-inches induces the same moments in the members as the application of a couple $+24,140$ lbs.-inches. In the frame under consideration the stiffness (the moment of inertia divided by the length) of each of the members meeting at Q is the same, so that the moments developed at the ends Q of the members by the rotation of Q will be of the same magnitude, one half of $+24,140$, or $+12,070$ lbs.-inches [line (b), columns (3) and (4), Table I], since the moment induced is in proportion to the stiffness of the member. The rotation of Q also modifies the moments at the far ends of these members QP and QR, producing additional moments there of $+6,035$ lbs.-inches [line (b), cols. (2) and (8)]. This is so because the moment, induced at the fixed end of a beam by a moment M at the other end, causing rotation only, is $\frac{1}{2}M$. Since joint R has not been released the moments at the ends of the other members remain unchanged [line (b), cols. (1), (5), (6) and (7)]. Joint Q is now in equilibrium. It is fixed once more in its new position, by the insertion of stops, so that it cannot rotate. The next joint R is now released. The external moment acting on this joint is the algebraic sum of all those so far set down, in cols. (6), (7) and (8), and is $-26,640$. On release the joint rotates into its new equilibrium position, with the result that this moment is divided between the members in proportion to their stiffnesses [line (c), cols. (6), (7) and (8)] and moments of half these magnitudes are induced at the far ends of the members [line (c), cols. (1), (4) and (5)]. Joint R is once more fixed. When we consider the joint Q again we find that an external couple has again been applied to it through the stops to prevent it rotating, since a moment $+4,928$ was carried over as a result of the rotation of R. When the joint is released, therefore, it once more rotates and modifies the moments further and so the process is continued. For practical purposes, since the modifications produced by subsequent releases are clearly small, the calculation need be carried no further than this and the bending moment at the end of each member is found by adding up the moments in the respective columns. Thus, at the end Q of PQ the moment is -9534 lbs.-inches. From these end moments the secondary bending stresses are calculated.

It is usual, when checking to see that the structure is not overstressed, to add the maximum secondary end bending stress arising

from the end moments calculated in this way to the primary or axial stress in each member determined from a consideration of the pin-jointed truss, and to see that this total end stress does not exceed that permissible for the material. This permissible stress is, in the case of a compression member, usually taken to be some multiple (for instance $1\frac{1}{3}$ times) of the safe axial load per unit area on a pin-ended strut, that is, on a strut having no end moments applied. The members of a rigidly-jointed truss are, however, subjected to axial load and to end moments also. To disguise this fact when deducing the permissible stress frequently means that the best use is not made of the material. It is probable that the majority of compression-members in a truss are bent in double curvature (for example, member RS, *Figs. 2 (d)*), the end moments having the same sense, and as will be seen later the maximum end stress which can be allowed in such a member is considerably greater than the safe axial load on the pin-ended strut. On the other hand, it is possible to find compression members in trusses bent in single curvature by the secondary moments, the moment at one end tending to cause a clockwise rotation and that at the other a counter-clockwise rotation, and there the permissible end stress is less than that usually adopted.

When a member AB of length L is subjected to an axial compressive force P and end moments M_A and M_B , the bending moment at any section, distance x from one end, is given by the expression


$$M_x = (M_A + M') \frac{\sin \alpha (L - x)}{\sin \alpha L} + (M_B + M') \frac{\sin \alpha x}{\sin \alpha L} - M'$$

where $\alpha = \sqrt{\frac{P}{EI}}$, and M' is a constant introduced to make allowance for the imperfections in a practical member, which we know, from the examination of test-results, can be conveniently represented by a small initial curvature of the axis.

From this equation the maximum stress in the member can be determined, and although the expression is too cumbersome for direct use in design it is not a difficult matter to translate it into the form of curves giving for any value of axial load per unit area and any ratio of the end bending moments M_B and M_A the maximum end bending stress f_A which can be induced with safety at the end of the member. Such a family of curves, based on a total maximum stress in the member of 8 tons per square inch, is shown in *Fig. 3* for an axial load per unit area (p) of 4 tons per square inch. Each curve refers to a different ratio of end bending moments, and you will see that when the member is bent in double curvature by end moments of equal magnitude $\left(\frac{M_B}{M_A} = \frac{f_B}{f_A} = -1.0\right)$, the case covered

by the right-hand curve, a secondary end bending stress of 4 tons per square inch would be permissible in any member having a slenderness-ratio (of length to least radius of gyration, L/r) of less than 128; that is to say, the total stress at the end of the member could be the full 8 tons per square inch, a very much greater value than that given by the usual method. The reason is, of course, that in any compression-member having a slenderness-ratio less than 128 subjected to an axial load per unit area of 4 tons per square inch and to equal double-curvature moments, the maximum bending stress will be found to occur at the end. For values of slenderness-ratio greater than 128 the maximum bending stress is found at some intermediate section, and since the total maximum stress made up

Fig. 3.



of axial load per unit area (4 tons per square inch) plus maximum bending stress is limited to 8 tons per square inch, the end bending stress must be less than 4 tons per square inch.

For the case of pure single-curvature bending, represented by the left-hand curve, when the member is bent by equal end moments of opposite sense ($\frac{M_B}{M_A} = \frac{f_B}{f_A} = 1.0$), the permissible secondary stress is very much smaller, being no more than 1 ton per square inch when the slenderness-ratio is 128 and only 3.7 tons per square inch for a slenderness-ratio of as low as 30.


Although attention has been drawn to these facts in the past, they do not appear to have been incorporated in any design method. The reason in all probability is that, quite apart from the natural objection which a designer would have to the use of a number of families of curves in place of his simple strut formula, they can only be used when the most rigorous stress-conditions for each member are known.

These conditions may not be brought about by that arrangement of load which produces the maximum axial load in the member, since, as the curves show, the total stress at any section depends not only on the axial load and on the maximum end bending stress but also on the ratio of the end bending stresses. A great deal of preparatory work would therefore have to be carried out to determine worst conditions in any particular type of truss before design could be started, and as it would be unsound to base a new method on theoretical argument alone, without the support of experimental data collected on actual trusses, the complete investigation called for would be a heavy piece of work. Such an investigation has been carried through recently for another type of structure, the steel building-frame, and a short description of it will show how more exact design methods can be developed. The investigation to which I refer is that made by the Steel Structures Research Committee between the years 1929 and 1936, a full account of which is contained in the Reports of that Committee published by H.M. Stationery Office in 1931, 1934 and 1936. Although directed primarily to the steel frame, a large part of this investigation dealt with problems common to reinforced-concrete structures. It must not be thought, therefore, that an important type of structure is being entirely neglected in this Lecture, or that all is well with reinforced-concrete design while much has had to be learnt about steel.

While the end bending effects which we have already discussed are of secondary importance in many trusses, there are certain types of structures, including building-frames, which depend upon them for their stability. A review of the methods of designing steel building-frames, which consist in the main of rows of vertical stanchions to which are connected lines of horizontal beams, has shown, however, that it is usual to assume, when considering the effect of vertical loads, that the beams are connected to the stanchions by perfect hinges which supply no bending restraints; in effect the stress-analysis is confined to what may be termed the primary system. This assumption makes the design of the beams a simple matter and has much to recommend it in spite of its extravagance. Its effect on stanchion-design is not so satisfactory, as those of you know who have been engaged on this type of structure. Although on the face of it the choice of the requisite stanchion-section is simplified thereby, the nature of the resulting stress-distribution is so distorted as to make a rational choice impossible.

When the effect of lateral or wind loads is considered it is easy to see that the assumption of hinged joints would result in the deduction of high bending stresses in the stanchions, since each stanchion would behave as a cantilever beam, of length equal to the height of the


building, subjected to a share of the wind loads. The designer, knowing that these excessive stresses do not exist, assumes, when considering lateral loads, that the joints between the members are completely rigid. Thus the assumptions made in designing a frame are diametrically opposite and depend on the type of loading under consideration.



A comprehensive series of tests recently made for the Steel Structures Research Committee on a number of existing buildings has shown that the assumption of rigid joints is much more nearly justified than that of pin-joints, whatever the loading. This can be seen from *Fig. 4*, which shows the observed bending moments in part of a single-bay frame of a London hotel-building due to the

application of a concentrated load to the centre of a beam. You will notice first the large restraining moment at the right-hand end of the beam which reduces the maximum stress in that member below the value it would have when simply supported and subjected to the same load. The magnitude of this restraining moment was 470,000 lbs.-inches due to the 10·1-ton load on the beam, and it induced in the stanchion-lengths above and below the beam moments of 120,000 and 350,000 lbs.-inches, values much greater than those

Figs. 5.



which would be assumed in normal design. It is worth pointing out here that the distance from the centre-line of the stanchion at which a reaction of 5·05 tons, half the applied load, would have to act to produce these moments is approximately 42 inches. The connexion responsible for this "equivalent eccentricity" consisted of a bottom stool, a 4-inch by 4-inch by $\frac{1}{2}$ -inch top flange-cleat 8 inches long, and two 4-inch by 4-inch by $\frac{1}{2}$ -inch web-cleats 10 inches long to a 14-inch deep beam.


The distribution of bending moment in the stanchions can also be seen, and it is well illustrated in *Figs. 5*, which shows the observed bending stresses in three lengths of a single-bay frame, made up of 8-inch by 4-inch by 18-lb. joists throughout, due to the application of

a central load of 2 tons to the bottom beam. The connexions consisted of the usual type of bottom and top flange-cleats made up of $3\frac{1}{2}$ -inch by 3-inch by $\frac{5}{16}$ -inch angle 4 inches long, secured with $\frac{1}{2}$ -inch diameter bolts to the webs of the stanchions. The observed bending stresses which are shown by the full line were appreciable, the maximum value being 6,075 lbs. per square inch, and you will see by comparing these stresses with those calculated on the assumption of rigid joints, shown by the hatched line, that, although the observed stresses were rather less than those calculated, the form of the observed diagram was the same as that for the rigid-joint case. It is interesting to note that appreciable bending stresses were developed in the top stanchion-length and that since no sway, or horizontal deflexion of the beams, took place the bending of each stanchion-length was in double curvature. This distribution of stanchion-stress is typical of that found in the other buildings tested, and it was not modified in form when the steel frame was clothed with floors, walls and stanchion-casing, as can be seen from *Fig. 6*, which shows the bending moments for three lengths of a stanchion in a London office-building due to a distributed load applied to one-half of the floor at level D when the building was complete with external walls and brickwork stanchion-casing. Here, again, the bending is in double curvature, and the appreciable bending moment in the bottom length remote from the load is again apparent.

As I have said, the bending stresses induced in the stanchions were found to be much greater than those assumed in design to-day, which are taken to be due to the application of a moment equal to the reaction at the end of the loaded beam multiplied by the eccentricity of the reaction, that is the distance of the point of support of the end of the beam from the centre-line of the stanchion. The difference can be gauged from the fact that in the bare framework of the hotel-building the eccentricity at which the reaction from one beam framing into the web of a stanchion would have had to act to produce the bending stresses observed was 44.6 inches, whereas the distance taken in design to-day might have been as low as $\frac{1}{4}$ inch and would certainly not have been more than $2\frac{1}{4}$ inches. The restraining moment developed at the end of the beam in this particular case reduced the maximum stress in that member by 25 per cent. of the value it would have had in the similar simply-supported beam, the condition assumed in design to-day.

The placing of floors and fire-resisting casing, an essential part of a large class of steel-frame buildings, whilst it does not modify the form of the stress-distribution in the steelwork, apart from tending to eliminate the stresses due to sway, has the effect of increasing the rigidity of the connexions and therefore, other things being

Fig. 6.



unchanged, the moments transmitted through those connexions. In one part of the office-building which was tested this increase was found to be as much as 3 times.

The observations showed quite conclusively, therefore, that all the standard types of bolted and riveted beam-to-stanchion connexions


(and the same can in all probability be said of most welded connexions) are capable of transmitting large moments, with the result that appreciable restraining moments are developed at the ends of a loaded beam and that the corresponding moments developed in the stanchions are many times greater than those usually taken into account. This means that the stress-calculations made in design to-day give an inaccurate representation of the distribution of stress.

While this misrepresentation is more serious in the case of stanchions, it will be well at this point to deal shortly with beam-design, which is relatively straightforward. We have seen that in the actual buildings beam-to-stanchion connexions restrain the ends of the beams and so tend to reduce the maximum bending stresses in these members. The magnitude of this reduction for any applied load depends, of course, on the type of connexion and on the flexibility of the stanchion to which the connexion is made. When it was realized that the flexibility of the stanchion compared with that of the connexion had a relatively small influence on the maximum beam moment it was possible, by assuming a lower limit for the rigidity of the stanchion and by conducting a comprehensive series of tests on standard connexions, to draw up Tables and curves showing what minimum restraining moment could be depended upon in any beam fitted with a known connexion, no matter what the rigidity of the stanchion so long as it was above the lower limit. The curves and Table appropriate to a riveted flange-cleat connexion having a top cleat 6 inches by 4 inches by $\frac{1}{2}$ inch are shown in *Fig. 7*. These data were prepared by Professor Cyril Batho, of Birmingham University, as a result of tests carried out by him. The restraining moment M can be found from them for any length of beam fitted with this connexion when D , the depth of the beam, and the loading as defined by M_F , the mean of the fixed-end or encastré moments, are known. With this information the design of the beam is as straightforward as that usual to-day. The maximum flexural stress in the member is easily calculated, being that which would occur were the ends freely hinged minus M , the restraining moment supplied by the connexion and found from the curves or Table.

It is when the condition of a stanchion is considered that the unsatisfactory nature of the present design-method is fully realized. Those of you who are familiar with the London County Council Code of Practice, or with the British Standard Specification No. 449 for the use of structural steel in buildings, know that the permissible stresses in stanchions tabulated there are deduced from the case of a pin-ended strut but that the designer, anxious to obtain some credit for the continuity of the stanchion through many floors, is allowed to consider the length of the member, not as the floor-to-floor height,

but as some smaller effective length. The only excuse for this reduction is the fact that the floor-beams framing into the stanchion provide some restraint. This postulates a connexion of some rigidity between the beam and the stanchion, and yet the bending moments,

Fig. 7.




$\frac{M_F}{2D}$: tons.	Length of beam : feet.				
	5	10	20	30	40
6	2.8	3.4	4.1	4.5	4.7
8	3.0	3.8	4.8	5.3	5.6
10	3.1	4.1	5.1	5.8	6.1
15	3.3	4.5	5.7	6.25	6.25
20	3.4	4.7	6.0	6.25	6.25
50 —	3.6	5.0	6.25	6.25	6.25

coming into the ends of the stanchion-length from the beams, are calculated on the assumption of hinged joints. There is, in fact, a serious confusion of thought when dealing with compression-members.

It is not here alone that confusion is evident. As serious a matter is the fact that no real attempt is made to-day, even within the

imperfect limits of the usual assumptions, to assess the strength of the structure in relation to the purpose it has to fulfil. Every designer will claim that his object is to produce a structure of adequate strength and stability, that is, one to stand up to any loads which can legitimately be applied to it. To do this it is usual for him, in making strength-calculations, to consider all floors to be completely loaded to their full intensity. Are the conditions produced the most rigorous for all members? This should be the first question the designer asks himself, and he might answer it by studying *Figs. 8*. It shows, in the left-hand top corner, *Figs. 8 (a)*, a symmetrical frame having all floors loaded. Consider the centre-length of stanchion AB. It will be subjected to an axial compressive force arising from the loads applied to the floors above. As the member is not perfect there will be a tendency for it to bend under this axial load, a tendency which will be resisted at the ends to some extent by the beams and connexions framing into the stanchion at A and B, so that the bending moment is of the form shown hatched in the diagram. This restraint, provided by the beams, and the resulting form of the bending-moment diagram, gave rise to the artificial and contradictory assumption of the existing Code of Practice relating to effective pillar-length, which I have just mentioned. However, returning to the bending-moment diagram, it will be seen that the maximum stress in AB is the sum of the axial compressive load per unit area and the maximum compressive stress due to the bending of the member. Now let us consider once again the actual bending stresses observed in the buildings tested, illustrations of which are given in *Figs. 4, 5 and 6*. It will be remembered that when load was applied to the beam on one side of a stanchion appreciable bending stresses were developed in the stanchion-lengths both above and below. If, therefore, load is removed from the beam to the right of B the bending-moment diagram for AB will be of the form shown in *Figs. 8 (b)*, and the maximum bending stress will be greater than when all floors were loaded. The axial compressive load per unit area is, however, unchanged since no load has been removed from the floors above, so that the maximum stress in the stanchion-length is greater and the second arrangement of loading is more rigorous than the first. This arrangement may not produce the worst stress-conditions for the stanchion-length since if load is removed from the floor to the right of A a further increase of bending stress will occur, *Figs. 8 (c)*, and the decrease in axial end load may not compensate for this increase, leaving the maximum total stress still greater. It may be noted also that the bending stresses are further increased if load is removed from the next floor above on the other side of the stanchion, *Figs. 8 (d)*. In these last three arrangements of load the

Figs. 8.

bending moments applied by the beams to the ends of the stanchion-length bend it in double curvature.

Another and most important condition has to be considered in which the stanchion-length bends in single curvature. An arrangement of load which brings this about is shown in *Figs. 8 (e)*, load

being removed from the floors at A and B on opposite sides of the stanchion so that, due to the bowing of the member, the maximum stress will occur at, or near, the centre of length. As in the case of double-curvature bending the removal of a further load from the floors above, *Figs. 8 (f)*, will increase the bending stresses, while decreasing the axial stress, and it is possible that one or other of these arrangements which bring about single-curvature bending will produce the worst stress-conditions in the stanchion. It is impossible to say from inspection whether double- or single-curvature bending will produce the maximum stress, but it is certain that one or other will give a greater value than the symmetrical arrangement of load hitherto used. Every engineer will agree that it is much more reasonable to base the design on the worst condition possible than to consider some particular case, not the worst, and then to extrapolate, as it were, by the use of a large safety-factor in the hope of covering the worst. If the more reasonable way is taken the design of a stanchion resolves itself into two steps, (1) a determination of the end reactions applied to the member by those arrangements of load which produce the worst conditions in the member under both double- and single-curvature bending, and (2) an estimate of the maximum stresses developed by those reactions which will enable the suitability of the member to be judged.

Since under ordinary commercial conditions the design of a building-structure has to be produced in a comparatively short time it would not be helpful to leave the matter here. The first step in the production of a method of design must therefore be the collection of data which will enable the worst end-reactions to be estimated with ease. The magnitudes of these reactions are affected by the proportions of the members making up the frame and by the characteristics of the connexions joining the members. The tests on existing buildings, to which I have referred, showed that the introduction of floors and stanchion casing increased the rigidity of the connexions very considerably. Since the moments at the ends of a stanchion-length increase as the rigidity of the connexions increases, it was clear that for the normal type of clothed steel frame it would be necessary to assume, when dealing with stanchions, that the joints in the frame were perfectly rigid. Even with this assumption, however, any exact determination of the worst reactions could only be made if the proportions of all the members in the frame were known. As anything in the nature of a tentative design of the whole structure is out of the question, all the proportions cannot be known, so that the data to be provided must be such that an upper-limit value of the moment can be estimated from the meagre knowledge of the frame already possessed by the designer. As I have

indicated, the designer can determine his beam-sections before approaching the stanchions, but since the maximum moment developed in the stanchion, unlike that in the beam, is considerably influenced by the relation between the beam- and stanchion-stiffnesses, it is essential, if an economical estimate of the reactions is to be made, for the designer to choose a stanchion-section, as he does now in the existing method of design, and then to find whether his choice is satisfactory.

The calculations which had to be made before the data giving the most rigorous reactions could be set down were lengthy and no complete account of them can be given here, but some idea of the method used can be grasped from a consideration of one or two very simple cases.

Perhaps I should remind you that these end reactions arise from loading on the beams. The load is of two kinds: dead, due to the weight of the floor itself, and live, or superimposed, due to the weight of furniture and occupants. The first, that is the dead load, is found on every beam and cannot be altered, while the second can be arranged in many possible ways.

The experimental investigation had shown that accurate estimates of the moments in the structures could be made by means of the simple slope-deflexion method of analysis or by the Cross method, which is based on the same assumptions, so that it was possible to calculate the moments at the upper and lower ends of any stanchion-length. For instance, those in the fourth storey of a single-bay six-storey frame having a ratio of beam- to stanchion-stiffness of unity are given in Table II. They are arranged so that the moment

TABLE II.—MOMENTS IN INTERMEDIATE STANCHION-LENGTH:
SINGLE-BAY FRAME.

	Beam 1 loaded.	Beam 2 loaded.	Beam 3 loaded.	Beam 4 loaded.	Beam 5 loaded.	Beam 6 loaded.
M_{34}	$= 0.02M_F$	$+ 0.08M_F$	$- 0.39M_F$	$- 0.13M_F$	$+ 0.03M_F$	$- 0.01M_F$
M_{43}	$+ 0.01M_F$	$- 0.03M_F$	$+ 0.13M_F$	$+ 0.39M_F$	$- 0.08M_F$	$+ 0.03M_F$

produced by the application of load to any beam can be picked out, and they are in terms of M_F , the fixed end or encastré moment,

which has the value $\frac{wL^2}{12}$ for a uniformly-distributed load of intensity

w per unit length on the beam. It will be seen from the Table that when the third floor is loaded the end moment M_{34} developed at the lower end of the stanchion-length is $- 0.39 M_F$, while when the second is loaded it is $+ 0.08 M_F$. At the upper end the corresponding

moments M_{43} are $+0.13 M_F$ and $-0.03 M_F$. Our object is to find expressions for the worst possible moments that can occur in this stanchion-length. The worst moments are made up of two parts, one due to the dead load and the other to the most unfavourable combination of live loads. That due to dead load is found by adding algebraically all the moments, and has the value at the upper end (M_{43}) $+0.45 M_F^D$, where M_F^D is the fixed end moment due to dead load on a beam, while that due to live load is $+0.56 M_F^L$ found by adding the moments due to live load on beams 1, 3, 4 and 6, which are all of positive sign. As this is a single-bay frame, all stanchion-lengths must bend in double curvature, and these dead- and live-load moments give all the information required for this stanchion-length.

The nature of the bending to which the stanchion-length is subjected may be more easily appreciated from *Figs. 9* (facing p. 301), which show a six-storey two-bay frame, built of spring steel, carrying various arrangements of load. The frame is shown unloaded in *Figs. 9 (a)*. A and B are pointers rigidly attached to joints 4 and 3. The bending of the stanchion-length of the single-bay frame subjected to loads on all floors is illustrated in *Figs. 9 (b)*, where it can be seen, from the deflected form of the stanchion-length and even more clearly from the positions of the pointers which show that rotation of both joints has been clockwise, that bending is in double curvature.

In an internal stanchion the conditions are a little more complicated. This can be seen from Table III, which gives the end

TABLE III.—MOMENTS IN INTERMEDIATE LENGTH, INTERNAL STANCHION: TWO-BAY FRAME.

Bay No. 1.						
	Beam 1 loaded.	Beam 2 loaded.	Beam 3 loaded.	Beam 4 loaded.	Beam 5 loaded.	Beam 6 loaded.
M_{34}	$+0.02 M_F$	$-0.08 M_F$	$+0.39 M_F$	$+0.13 M_F$	$-0.03 M_F$	$+0.01 M_F$
M_{43}	$-0.01 M_F$	$+0.03 M_F$	$-0.13 M_F$	$-0.39 M_F$	$+0.08 M_F$	$-0.03 M_F$

Bay No. 2.						
	Beam 1 loaded.	Beam 2 loaded.	Beam 3 loaded.	Beam 4 loaded.	Beam 5 loaded.	Beam 6 loaded.
M_{34}	$-0.02 M_F$	$+0.08 M_F$	$-0.39 M_F$	$-0.13 M_F$	$+0.03 M_F$	$-0.01 M_F$
M_{43}	$+0.01 M_F$	$-0.03 M_F$	$+0.13 M_F$	$+0.39 M_F$	$-0.08 M_F$	$+0.03 M_F$

moments in the corresponding internal stanchion-length of a two-bay frame due to load on each beam of each bay. Here again the moments due to dead loading are found by adding all the moments. M_{43} has the value $-0.45 (M_{F_1}^D - M_{F_2}^D)$ where $M_{F_1}^D$ and $M_{F_2}^D$ are the fixed-end moments due to dead load on the beams in the first and second bay respectively (their magnitudes are not necessarily the same). When the second and fifth beams of bay No. 1 are loaded, together with the first, third, fourth and sixth of bay No. 2, all giving positive values of M_{43} as can be seen from the Table, the end moments have their maximum live-load values ($M_{43} = 0.11M_{F_1}^L + 0.56M_{F_2}^L$) and the bending is in double curvature as can be seen from *Figs. 9 (c)*. If, now, beams 1, 3 and 5 of bay No. 1 are loaded together with 2, 4 and 6 of bay No. 2, the moment M_{43} has the value $(-0.06M_{F_1}^L + 0.39M_{F_2}^L)$. This is smaller than the previous

TABLE IV.—TOTAL BENDING MOMENT DUE TO DEAD LOAD.

$\frac{K_{BR} + K_{BL}}{K_U + K_L}$	Bottom length : total moment $(M_{F_1}^D - M_{F_2}^D)$	Intermediate length : total moment $(M_{F_1}^D - M_{F_2}^D)$	Topmost length : total moment $(M_{F_1}^D - M_{F_2}^D)$
0.0	0.86	1.00	1.00
0.2	0.78	0.95	0.92
0.6	0.67	0.84	0.79
1.0	0.59	0.75	0.70
2.0	0.45	0.60	0.55
4.0	0.31	0.43	0.40
8.0	0.19	0.27	0.26

value but, as can be seen from *Figs. 9 (d)*, bending is in single curvature so that it may give rise to a higher stanchion-stress than the greater double-curvature moment. The two cases must be considered, each, of course, in conjunction with the dead-load moments. For all internal stanchions these three sets of moments, due to the dead load and to the arrangements of live load producing bending in double and in single curvature, must be evaluated.

It would be asking too much of the designer to calculate these moments in every case; in fact he would be unable to do so, as the full details of his frame are not yet known to him. Fortunately, it was found possible to collect safe values of the moments in any frame depending only on the limited data already possessed by the designer. This information, for dead load, is shown in Table IV. The first column contains the ratio of the sum of the stiffnesses K_{BR} and K_{BL} , of the beams to right and left of the stanchion, to

the sum of the stiffnesses K_U and K_L of the stanchion-lengths above and below the beams. The beams and upper stanchion-length are already designed, and a tentative choice will have been made of the lower length, so that the designer knows the value of this ratio. He can then read the total moment coming into the stanchion at the floor-level from the appropriate column in the Table according to whether a bottom, intermediate, or topmost stanchion-length is under consideration. The total moment being known, the moments in the upper and lower lengths are found by dividing the total between them in the ratio of their stiffnesses. The tests on existing buildings showed that this is not strictly justified, but it gives the best approximation possible. Table V gives the information for live-load moments; it is more complicated, since in intermediate and topmost lengths both double- and single-curvature moments must be included as we cannot yet judge which will be critical.

The reactions at the ends of the stanchion-length made up of axial load and end moments are now known, and the designer must test to see whether his choice of a stanchion-section is satisfactory. He must see that the maximum stress developed by these reactions does not exceed the permissible value. For this the families of curves similar to *Fig. 3* (p. 304) could be used, giving as they do the end bending stress which can safely be applied in conjunction with any axial load. You will remember, however, that the ratio of end bending stresses had also to be known, and to determine this the designer would have to consider tentative sections for two stanchion-lengths at a time. That is to say, in designing the length 43 a section for this length would be chosen so enabling the moment M_{43} to be calculated, but before the adequacy of this section could be tested M_{34} must be known and this means that a tentative choice of the length 32 would have to be made also. This might well be irksome, and it was therefore considered worth while to consider in detail only the moment at the upper end of the stanchion-length, which is under normal conditions the greater, and to assign a limiting value to the moment at the lower end such that safety is ensured, although inevitably at the cost of some economy. In this way only one ratio of end moments, and therefore only one curve from each family, is used. When the arrangement of load produces bending in single curvature a decrease in the bending moment at the lower end of the stanchion-length decreases the maximum stress in the stanchion. In this case safety will be ensured by assuming that the ratio f_B/f_A of the end bending stresses is unity, that is, by taking the moment at the lower end as equal to that at the upper. When the loads are such as to produce bending in double curvature a decrease in the magnitude of the moment at the lower end of the stanchion-


TABLE V.—TOTAL BENDING MOMENT DUE TO LIVE LOAD.

$\frac{K_{BR} + K_{BL}}{K_U + K_L}$	Bottom length.		Intermediate length.		Topmost length.	
	Double curvature.		Double curvature.		Double curvature.	
0.0	$1.15M_{F_1}^L + 0.29M_{F_2}^L$	$1.36M_{F_1}^L + 0.34M_{F_2}^L$	$1.00M_{F_1}^L - 0.00M_{F_2}^L$	$1.00M_{F_1}^L + 0.00M_{F_2}^L$	$1.00M_{F_1}^L - 0.00M_{F_2}^L$	$1.00M_{F_1}^L - 0.00M_{F_2}^L$
0.2	$1.02M_{F_1}^L + 0.23M_{F_2}^L$	$1.23M_{F_1}^L + 0.28M_{F_2}^L$	$0.89M_{F_1}^L - 0.06M_{F_2}^L$	$0.92M_{F_1}^L + 0.01M_{F_2}^L$	$0.89M_{F_1}^L - 0.03M_{F_2}^L$	$0.89M_{F_1}^L - 0.03M_{F_2}^L$
0.6	$0.83M_{F_1}^L + 0.16M_{F_2}^L$	$1.04M_{F_1}^L + 0.20M_{F_2}^L$	$0.73M_{F_1}^L - 0.11M_{F_2}^L$	$0.81M_{F_1}^L + 0.01M_{F_2}^L$	$0.73M_{F_1}^L - 0.06M_{F_2}^L$	$0.73M_{F_1}^L - 0.06M_{F_2}^L$
1.0	$0.71M_{F_1}^L + 0.12M_{F_2}^L$	$0.90M_{F_1}^L + 0.15M_{F_2}^L$	$0.63M_{F_1}^L - 0.13M_{F_2}^L$	$0.72M_{F_1}^L + 0.02M_{F_2}^L$	$0.63M_{F_1}^L - 0.08M_{F_2}^L$	$0.63M_{F_1}^L - 0.08M_{F_2}^L$
2.0	$0.52M_{F_1}^L + 0.06M_{F_2}^L$	$0.69M_{F_1}^L + 0.09M_{F_2}^L$	$0.47M_{F_1}^L - 0.13M_{F_2}^L$	$0.57M_{F_1}^L + 0.01M_{F_2}^L$	$0.46M_{F_1}^L - 0.09M_{F_2}^L$	$0.46M_{F_1}^L - 0.09M_{F_2}^L$
4.0	$0.34M_{F_1}^L + 0.03M_{F_2}^L$	$0.47M_{F_1}^L + 0.04M_{F_2}^L$	$0.31M_{F_1}^L - 0.11M_{F_2}^L$	$0.41M_{F_1}^L + 0.01M_{F_2}^L$	$0.31M_{F_1}^L - 0.09M_{F_2}^L$	$0.31M_{F_1}^L - 0.09M_{F_2}^L$
8.0	$0.20M_{F_1}^L + 0.01M_{F_2}^L$	$0.29M_{F_1}^L + 0.01M_{F_2}^L$	$0.19M_{F_1}^L - 0.08M_{F_2}^L$	$0.26M_{F_1}^L + 0.01M_{F_2}^L$	$0.19M_{F_1}^L - 0.07M_{F_2}^L$	$0.19M_{F_1}^L - 0.07M_{F_2}^L$


length may increase the maximum stress in the stanchion. For safety in this case the ratio f_B/f_A must be based on a consideration of the conditions which make the ratio of the magnitudes of the moments at the lower and upper ends of the stanchion-length the minimum. This minimum is found in the topmost length of an external stanchion when one topmost beam only is loaded and when the ratio of beam- to stanchion-stiffness $\left(\frac{K_B}{K_L}\right)$ approaches zero. The ratio of the moments at the lower and upper end then has the value

Figs. 10.

(a)



(b)



0.268, and this must be taken as the ratio f_B/f_A . The relevant information can now be embodied in only two sets of curves as shown in Figs. 10, the upper referring to single-curvature bending and the lower to double-curvature bending. They are, incidentally, based on a load-factor of 2; that is to say, they are so constructed that all the loads giving rise to the stresses could be doubled without raising the maximum stress in the member beyond the yield-stress of the material, taken to be 18 tons per square inch for mild steel.


The design-procedure can now be summarized. Suppose an inter-

mediate stanchion-length is to be designed. A provisional section is chosen for it. The lengths above and all beams will have already been designed so that the ratio of the stiffnesses can be calculated. Concentrating attention first on the loaded beams at the upper end framing into the web of the stanchion, the end moments due to dead load and also to that live load producing double-curvature bending are found from the appropriate Tables, and the maximum flexural stress at the end of the stanchion-length produced by these moments combined is set down. To this is added the similar bending stress arising from the loading of beams framing into the flanges, to give the total maximum end bending stress. The next step is to see that the provisional stanchion-section can safely bear this stress together with the axial load per unit area imposed by the reactions at the ends of the beams above. The slenderness-ratio of the stanchion-length is calculated and the lower family of curves, *Figs. 10 (b)*, is brought into use. Each curve gives the relation between permissible end bending stress and slenderness-ratio for a particular value of axial load per unit area. If the axial load is, for example, 4 tons per square inch, attention is concentrated on the appropriate curve marked 4 and it is found that for the known slenderness-ratio, for instance 80, the permissible end bending stress, read from the vertical axis, is 4.6 tons per square inch. If this is greater than the actual total maximum end bending stress already calculated the section chosen for the stanchion will be adequate. It will be adequate to carry the dead load and the live load arranged so as to produce double-curvature bending; it may, however, be inadequate when the live load produces single-curvature bending. A similar calculation must be carried through, substituting for the double-curvature live-load moments those end moments which can be read from the appropriate Table (Table V) which are developed when the live load is so arranged that single-curvature bending is produced. When the resulting total maximum end bending stress has been calculated the appropriate curve from the upper family is used to test the adequacy of the stanchion-section.

Those of you familiar with the usual method of design will see that no fundamental change has been made, but the real magnitudes of the bending moments in the stanchion have been recognized, and by adopting rational strut-curves the consideration of unreal effective lengths has been avoided. There is one difference, however, which is of importance to the designer in his office. Owing to the necessity for considering both double- and single-curvature bending two independent tests of the adequacy of the stanchion-section have to be made in the new method. A number of engineers gave the method a trial in their offices and they were of the opinion

that as a result the time taken in proportioning a stanchion was prohibitive. Further simplification was therefore essential, so that, while the basis of the method was not undermined, one test only would be required for the stanchion section. This was made possible by producing one family of strut-curves made up of the critical portions of those already shown in *Figs. 10*. You will see from Table V that for a symmetrical frame the bending moment in double curvature is never less than 1.7 times the single-curvature moment. If, therefore, when considering single-curvature bending the magnitude of the live-load end bending moment is taken to be that of the double-curvature moment instead of the real single-curvature moment, and the test of adequacy is made on a family of curves similar to the upper family (that is, to the single curvature set (*Figs. 10*)) but having the ordinates increased 1.7 times, then safety will be ensured although some economy will be sacrificed. One calculation only of maximum end bending stress has in this way to be made, namely that for double-curvature bending, and if a composite family of curves is formed from the original double-curvature set and the new single-curvature set by taking that portion of each which gives the lower value of the permissible end bending stress, the work entailed in proportioning a stanchion is reduced by one-half. The composite curves are shown in *Fig. 11*,

Fig. 11.



and although I have only given you the argument for their adoption in the case of a symmetrical frame they are safe whatever the arrangement of the members.

This is a bare outline of the method of design from which you can appreciate its basis, but I have said nothing of what you will find on applying it.

The designer inevitably thinks of two questions: "Does it mean more work in the design office?" and "Does it result in any saving of material?" The first is easy to answer. Since there is little

doubt that the steps in the existing method were chosen mainly on account of their simplicity, it is inevitable that any more rational method must be more complicated. But let me suggest that you will not be in a position to judge the amount of work involved until you have had some experience of the method. The position is not as bad as the first perusal of the clauses of the Recommendations for Design¹ as published lead one to believe. The small amount of extra work is offset to some extent for the conscientious designer, who worries about these things, by the comfort in the thought that he is not asked to draw on his imagination to cover such points as the "effective lengths" of the stanchions.

The question of the weight of the structure is not so easily answered, bound up as it is with such factors as the intensity of superimposed load and the working stress. I have drawn your attention several times to the lack of truth in the picture of the stress-distribution given by the existing design-method. But let me remind you that the method as applied in Great Britain has resulted, as far as I know, in no building failure in more than 30 years. It must, therefore, include an adequate safety-margin supplied by a fictitious value for the superimposed load in the case of certain, though not all, occupancies, by the factor which makes the permissible stress a fraction of the yield-stress of the material and by others, such as those arising from the presence of clothing, which are still more or less obscure.

Although necessary, in part to cover ignorance when the existing method and Code are used, the factors should be modified for the new method, based as it is not only on a stress-distribution nearer the truth but on an arrangement of loads more trying to the structure.

Even so, it is clear that when using factors approximately the same as those embodied in the existing code the new method gives a saving on beams since account is taken of end restraint. The saving is considerable—for instance in carrying 1 ton per foot over a span of 16 feet a 12-inch by 5-inch by 32-lb. beam can be used instead of a 12-inch by 6-inch by 44-lb. beam.

Where stanchions are concerned, the emphasis in the new method is so different from that in the old that it is impossible to make a clear comparison. There will be a tendency for the distribution of weight in a continuous stanchion to change, the lower lengths becoming lighter and the upper lengths heavier. This is due to the recognition given to bending stresses, and this recognition means that where much the same factors are used the new method will call for heavier stanchion-lengths in some cases, though by no means in all. But the same factor should not be used. Not one of the

¹ "Steel Structures Research. Recommendations for Design." H.M. Stationery Office, 1936.

innumerable stanchions designed by the haphazard method of to-day has caused any structural failure. If, therefore, the factor to be used with the new method is based on that actually existing in some of the more sorely tried columns now standing, then by adopting this more rational method throughout great economy must result, and framed structures will be free to evolve in a way impossible to-day.

CORRESPONDENCE
ON PAPERS PUBLISHED IN
NOVEMBER 1936 JOURNAL.

Paper No. 5045.¹

“The Restoration of the Breach in the Right Guide Bank
of the Hardinge Bridge.”

By BERTRAM LIONEL HARVEY, O.B.E., B.Sc., M. Inst. C.E.,
M.I.E. (Ind.).

Correspondence.

Sir ROBERT GALES observed that the Author suggested that the breach in the right guide bank which occurred on the 26th September, 1933, had had its origin at or just below water-level, and that it had been caused by a very strong suction on the face of the boulder protection, produced by “specially fast-moving eddies”; that suction caused silty sand, of which the bank was composed, to be drawn out until the boulder protection fell down and exposed the core of the bank to the action of the flood-water.

The slope of the bank was 1 in 2 and the sand was covered with a 1-inch layer of good stiff clay topped by 3 inches of quarry-refuse, the whole consolidated and held down by the weight of a 3-foot 1-inch covering of pitching-stone. Sir Robert had held an inquiry at the site in December, 1933, into the cause of the breach, and had pursued further inquiries in January, 1934, and although the need for some covering of the sand, to prevent its being sucked out or even “running” out between the pitching-stones, had been realized from the inception of “bund-and-apron” construction, no suggestion of that cause of failure had been made at the time of the inquiries.

The breach had started between chainage 19 and chainage 22 of the guide bank. The original amount of stone pitching sufficient for a scour-depth of 100 feet below low-water level had been supplemented by an addition of 400 cubic feet per foot run of guide bank, laid in water at the toe of the apron, from chainage 15 to chainage 30. That seemed to prove that the slip had not been caused by deepening due to scour along the toe, and suspicion fell on the abrupt termination of the additional pitching at chainage 15. It seemed possible that

¹ Journal Inst. C.E., vol. 4 (1936-37), p. 21 (November, 1936).

Sir Robert
Gales.

an eddy had been formed by that abrupt change of section and that the resultant scour might have worked back to the point of origin of the breach. There was no evidence or suggestion of deepening of the channel by scour along the toe, neither was there any evidence of eddy-scour having occurred, and no definite conclusion was reached.

A slip had occurred on the 11th January, 1934, at chainage 26.50 at the isolated head of the right guide bank, which showed as an exposure of the sand core of the bank above water-level. There was no question of scour at the toe or of eddy-action, as the river at that time had been only 6 feet above low-water level and the current had been slow. The slip was attributed to instability of the material of the natural bank of the river, and it was suggested that this might have been the determining factor in the breach of the guide bank. No definite conclusion had, however, been reached as to the cause of the breach. It remained for the Author, whose experience of slips and their control was extensive, to suggest the true cause, namely, that it was the result of local exposure of the sand core at about water-level, which he ascribed to fast-moving eddies.

Sir Robert thought that an explanation satisfying both of the cases described above lay in wave-wash. In the case of the breach there was no need to go further than the Author's description of the waves that had rushed into the breach at intervals of about 2 minutes accompanied by an afflux of about 2 feet in the embayment, and the small slip in the head of the guide bank was fully accounted for by the wash from the daily steamer-traffic which would pass that spot.

Slips due to scour at the toe of a guide bank occurred with a falling river, because the straight-running flood-water withdrawing into curving channels deepened them and the sand core of the guide banks was softened by seepage from the saturated banks. The breach of the 26th September had occurred with a rapidly-rising river, but that no longer presented a difficulty. At the time the sandbank extended across the river from the left bank towards the head of the right guide bank. As the river fell rapidly the current slowing in the shallower water, had led to a rapid deposit of sand and silt and upward growth of the sandbank; but when the freshet had come down, accompanied by a still more rapid rise, it had found the restricted channel opposite the guide-bank head, resulting in heading up and formation of the surface-waves which had persisted until the channel had been re-opened to sufficient capacity. There was no longer any doubt that those waves, by the suction they produced in passing along the face of the guide bank, had been able to draw out the covering of quarry-refuse and clay so as to allow the pitching stone to drop and to expose the sand core, which had been swept away.

by succeeding waves. As soon as the waves stopped, the embay-
ment had ceased to progress towards the main line at the back of the
bridge-abutment, and if the river had then begun to fall, the breach,
which at that time had had no great depth where the slope-stone
met the pitching stone of the apron, could have been repaired without
much difficulty. The river, however, continued to rise, but it was
not until the 2nd October, 6 days after the guide bank had been
breached, that the water (which had been flowing into the embay-
ment over the undisturbed stone apron at the back of the guide-
bank head), by eroding the river bank at the edge of the apron, had
begun to flow through the embayment and out by the breach in
a volume which had threatened disaster. On the 5th October the
river had commenced to fall, and on the 7th October it had fallen
no less than 14 inches, bringing a rush of water at high velocities
back into the main channel, of which the new channel at the back of
the guide bank head became a part; a slight accident had thus led
to a disaster. When the sand core of the guide bank had first been
exposed, the damage could have been repaired in a few hours, and
the breach as it existed up to the 2nd October could have been
repaired in a few months, but, deepened and extended by the flowing
through it of an arm of the main river, the breach had taken 2 years
and had cost about £750,000 to repair.

Although there was no want of knowledge about the severity of
the conditions to which the covering of the sand core was exposed
at a guide bank in the lower Ganges, the design of a satisfactory
covering had yet to be made. In the first bund-and-apron guide
banks the reserve pitching stone was stacked on the slope of the bank,
whence it went down and forward to supplement the apron stone
where that proved to be insufficient. At the Curzon bridge over the
Ganges at Allahabad it was formulated that the slope-stone should
be treated as permanent, although it was considered that it should
remain a flexible protection. The sand-core covering used there
was 3 inches of quarry-refuse kept in place by loose stone pitch-
ing. The slope had never moved and the covering had proved
satisfactory.

For the Hardinge bridge, assuming that the depth of scour for
which the apron was to be designed was now known, it would be
necessary to allow an additional strip of apron at the foot of the
slope in order to ensure that there should be no movement of the
slope-stone. If that could be depended upon, the safety of the
sand core could be secured by a single layer of cut-and-fitted stone,
as was found sufficient on the Suez canal to protect the banks from
the heavy wave-wash of ships passing through it. However, even
with the additional strip of apron at the foot of the slope, it seemed

Sir Robert
Gales.

necessary to provide a flexible covering for the guide banks of the lower Ganges; he suggested that the covering should consist of : 3-inch underlay of burnt brick on flat followed by 6 inches of broken stone ballast, and that the pitching stone should be hand-set and bedded down into the stone ballast to the extent that that could be done without the cost of cutting or breaking the pitching stone. The bricks were to provide a continuous cover for the sand, the stone ballast or other material was to protect the brick cover, the covering of stone was, by its weight, to keep the stone ballast in place, and it was to be hand-set to reduce the cavities through which the wave entered which produced the suction on withdrawal. Concentration of rainfall which would form gutters down the face was to be prevented by a clay banquette along the edge of the bank, which would ensure that all rain falling on the top of the bank would drain towards the inner slope.

The cost of the construction suggested above would have to be considered. The additional strip of apron to ensure as far as possible the permanence of the slope would add to the cost of the guide bank but it would in fact form a much-needed margin of safety in the event of unexpected conditions showing the apron stone to be insufficient in quantity. The covering of good clay, often recommended, would be very expensive; the so-called clays in the delta were silt-deposits which, once dried, disintegrated in water. The famous Sara clay on the preservation of which the safety of the Hardinge bridge depended, was such a deposit, containing traces of wild rice; it had a small band of indurated material, but none of that would be available. A good clay was to be found in the Borind some 50 miles up the river, and a true clay, formed by decomposition of basalt, was available at Phudkipur, 134 miles up the river where there were stone quarries. Either of those clays would cost as much as quarry refuse. Quarry-refuse would be difficult to obtain in the quantities required, and would probably have to be manufactured by crushing that led to broken stone ballast, and the size of the top 3 inches should be big enough to bridge the spaces between the pitching stones. There would be no saving in pitching stone, as nothing less than 3 feet 6 inches of pitching stone would be sufficient.

There were other considerations in connexion with the protection of the face slopes of the guide banks of the lower Ganges. Owing to the vast amount of excavation which it would usually be necessary to do in about half a working season in order to lay the apron at low-water level, the floor-level of that part of the apron nearest the slope of the guide bank would in most cases be found to be at about half-flood level, and it was only for the upper half of the slope that it was possible to protect the sand with the covering described.

above. Below half-flood level the only protection possible when the Sir Robert Gales.
apron had gone down into place was the increased cover of pitching stone provided, which had hitherto been insufficient. The upper half of the slope was exposed to flood wave-wash and moving eddies, and therefore needed the greater protective covering, but the lower half was exposed to steamer-wash, which partially accounted for the slip described above in the head of the right guide bank. The safeguards that had been devised against that kind of slip were the reserve strip of apron already suggested, and a considerable increase in the thickness of the inner belt of the apron.

Mr. C. C. INGLIS, of Poona, stated that model experiments had Mr. Inglis.
been in progress at Khadakvasla hydrodynamic research station, Poona, since the beginning of 1935 in connexion with safeguarding the Hardinge bridge. The main experiments had been planned

- (a) to find out how scour occurred around a pier, the factors which affected the scour, and the best method for protecting the piers ;
- (b) to determine the angle of repose of various kinds of pitching in various conditions of flow ;
- (c) to observe how an apron (laid horizontally at low-water level) launched to form a pitched slope under various flow-conditions ;
- (d) to determine the exact conditions which led to the breach, and the best way to prevent a repetition.

A model of 25 miles of the river, to a horizontal scale of 1 to 500 had also been constructed, and was run with discharges of up to 20 cusecs, eleven series of experiments having been carried out to determine the effect of various control-designs as compared with the conditions in 1933. Subsequently the model had been enlarged to comprise a length of 60 miles of the river. He did not propose to describe those experiments, but merely to utilize the results to answer points raised in the Paper.

In *Fig. 2* (p. 26 §) the Author compared conditions in 1933 with average conditions over a period of years. That gave a wrong impression, because in most years there were rises and falls. On p. 31 § he stated that " it appears as if the main force of the river, swollen by the floods in Upper India, had concentrated above the bridge in the form of almost a tidal wave or waves with a steep hydraulic gradient, which lasted over a period of about 12 hours." Such a state of affairs was physically impossible, and an examination of the data did not indicate that there had been any phenomenal

Mr. Inglis.

conditions, although the flood had undoubtedly been a heavy one and the quick drop had put a severe test on the stability of the pitching. It was found, however, from model experiments that the conditions were favourable to a slip and that the breach was to be expected even with normal discharges in the river.

On p. 27 § the Author stated that "investigations as to the cause of the breach have been exhaustive and, although various reasonable and probable theories have been suggested, the actual and definite cause of what happened on the 26th September, 1933, . . . will probably remain an unsolved problem." Every feature described in the Paper had been reproduced closely in the large model of the river and a model designed to determine the exact way in which the breach occurred had reproduced the breach accurately. It had, in fact, been found possible to cause a breach at different parts of the guide bank by a suitable adjustment of the conditions.

When Mr. Inglis had first visited the bridge, there seemed to be a general opinion that the breach had been due to the large-radius slow-moving eddy, which revolved slowly in the vicinity of the breach, the idea being that the velocity of the eddy increased with depth, causing a hole to form near the toe of the pitching, and the Author referred to "strong eddy suction." Neither of those explanations was correct or even physically possible; the true explanation—as viewed through a glass sheet let into the side-slope of a model of the right guide bank—was that below the slowly-revolving surface eddy there was a region of instability at mid-depth, where the flow was sometimes in one direction and sometimes in another; but the only severe action was at the bed, at the toe of the pitching, and there the flow was straight and turbulent, coming in surges, some stronger than others, at the rate of from one to three per second in the model. Sometimes sand was picked up in little gusts like dust on a road. Stones were carried away in the surges, and although a stone might remain unmoved for several seconds, it might then be carried away in a powerful surge. Experiments with a model of a pier had shown that silt was scooped out around the pier by diving curved flow and that stones thrown into the "cups" so formed usually remained there, gradually sinking into the bed as scour progressed. Hence although no stone might be visible around the pier, it was merely because it was covered by a layer of silt. Stone thrown or laid outside the "cup" was washed downstream and served no useful purpose; it might even form a local obstruction and be a source of danger.

The Author on p. 25 § gave the reasons for the construction of the

Damukdia guide bank. Mr. Inglis wished to make it clear that the action taken was what "common sense" would indicate to be the safest course, and hence it was easy to understand why that operation was followed in an emergency. The action taken, however, ignored the first principles of river-control—namely, that opposing the direct force of flow caused relatively harmless kinetic energy to be changed into highly-destructive turbulent eddy-flow of an unstable kind, accompanied by surging, and that the only way to control flow was by "coaxing" the river to swing in a large, natural curve, around a fixed guide bank. Constructing the Damukdia guide bank ignored the first principle directly, and also prevented the right guide bank functioning in the way it was designed—namely, as a Bell bund. Had the right guide bank been constructed of the correct length in the first instance, it seemed fairly certain that the local engineers would have let well alone, but owing to its being much too short their anxiety was easily understood. So long as the river flowed from Sara to form a loop around the right guide bank, the bank was of ample length; it would only be of insufficient length if attack came from the right, upstream, instead of from Sara on the left, as at present, and there was no possibility of attack from the right bank. That followed from the reasoning of Bell and others; but the exact effect had been examined in the model, which showed that had the Damukdia guide bank not been constructed, the loop of the embayment would not have extended below the end of the guide bank, nor eaten more than 2,400 feet into the right bank. Some conclusions, drawn from the experiments, which had a direct bearing on questions raised in the Paper were:

(i) A guide bank tended to pull a river around its nose, but there was a limit to the embayment caused thereby.

(ii) Flow tended to "hug" guide banks and to leave them with reluctance.

(iii) Scour of 206 feet had been recorded near Sara. That was considerably deeper than pier-foundations. Pitching around piers retarded action but did not prevent it. The proper place to protect piers was, therefore, upstream—by the correct design of the guide banks.

(iv) After a "falling apron" had launched, so as to form a pitched slope, action would begin only at the toe, not on the slope, and when the whole of the stone of the falling apron had been launched, further scour at the toe would lead to stone being denuded from the original slope above water-level, leaving part of the bank exposed below water-level. The area of slip would increase rapidly unless localized by the method described by the Author—namely, "... to pitch boulders speedily over a length of about 15 feet beyond

Mr. Inglis.

the slip, at both ends, at water level," while simultaneously covering the exposed area of the slip by throwing boulders from above.

(v) The retired guide bank at Sara had caused an abrupt change in direction of flow, which induced diving flow, leading to a scour 206 feet deep at high flood. That had had the effect of directing unstable surging flow towards Damukdia on the opposite bank. When the Damukdia guide bank was constructed to oppose the latter flow, it prevented free embayment by natural scour, which would have dissipated a large amount of energy and would have smoothed out instability of flow. It had also increased instability and surging, and so had intensified the attack which caused the breach.

(vi) The basic principles of Bell and Spring were sound, but they required revision and amplification in the light of recent knowledge. Work of that kind could not, however, be reduced to rule-of-thumb methods, and every case required special consideration. Bearing in mind that a mistake in design might necessitate the expenditure of hundreds of thousands of pounds, it was obvious that designs should be prepared by construction-engineers and river-training specialists working in collaboration. Some years ago, model-experiments were looked upon with suspicion, but undue reliance was now frequently placed on them. Both attitudes were unsound; a river model did not yield geometrically-similar results to the prototype, and so the design of models and the interpretation of results presented problems of great complexity and difficulty. It was, in fact, necessary to construct different models to determine the effect of different factors, and then to combine the various results in a large river-model (with a minimum discharge of 7 cusecs), from which accurate results could be obtained.

Mr. Leitch.

Mr. W. O. LEITCH observed that a liberal amount of rubble had been laid in the moles, but a large proportion of it appeared to be "one-man-rock" which, should movement occur, seemed hardly heavy enough to prevent the stones from being rolled away by the current, instead of then sinking down and possibly filling the first small scour-hole.

The permanent protection of the bridge was not the main subject of the Paper, but as a considerable time had elapsed, perhaps the Author could say what was about to be done to deal with such deep scours as 120 feet, which, having occurred once, might occur again, and which would seem to make it necessary to tackle the very expensive problem of training the river for a greater distance above the bridge, so as to steady the current down to and past the bridge.

Mr. Radice.

Mr. W. A. RADICE, of Calcutta, observed that important decisions affecting the safety of the bridge had had to be made quickly, and

he wished to express his admiration of the soundness of judgement Mr. Radice displayed by those responsible.

When he had visited the restoration works in 1934 the mole was practically completed and the stone dykes of the backwater-bund were just appearing above the water. He had then expressed to the Author the fear that, as the river rose in flood, and perhaps even more so as it subsided, the changes in river-levels might cause the water in the lagoon between the mole and the backwater bund to act as a lung, and to breathe out pulsations which, impinging on the main current flowing past the mouth of the lagoon, might cause swirls dangerous to the safety of the outer downstream face of the mole. He would be interested to know whether any such tendency had developed during the rise and fall of the river in 1934, because if no inconvenience or danger were caused by the presence of the lagoon, the fact might have an influence on the existing practice of design of guide banks, and might lead to a revision of theories on river-training and the need for unbroken continuity of the protective works.

During that visit he had also noticed that the space between the back of the mole and the earthworks of the right-bank approach to the bridge itself formed a deep enclosed hollow. The Author had informed him at the time that the question of providing means to flood that hollow to correspond with the river-level outside, so as to equalize the pressures on each face of the mole, was under consideration. It would be of interest to know what the decision had been, and its effect on the behaviour of the mole during the ensuing flood, especially with regard to seepage through the mole itself and the disposal of rain-water accumulations in the hollow.

The AUTHOR, in reply, observed that he was very grateful to Sir The Author, Robert Gales for the very thorough and detailed remarks he had made, and for agreeing that the original slip might have been caused by the local exposure of the sand core at about water-level. The Author continued in charge of the Hardinge bridge for the remainder of the flood season, following the completion of the Paper, and the slips that occurred during that period had strengthened his conviction that slips, if left uncared for, would invariably turn into breaches. Mr. Inglis, on the other hand, stated that from the observations on his model-experiments he had found the cause of the breach to be due to other reasons—in fact, by a suitable adjustment of conditions in the model it had been found possible to produce breaches at different parts of the guide bank. The Author had had the good fortune to witness the earlier series of experiments which Mr. Inglis had carried out in his laboratory, but during those experiments it had seemed to the Author that a breach, by any

The Author.

other method than undermining the toe, was impossible as the guide banks were constructed of a solid clay material, very nearly of the consistency of concrete. He was, however, glad to learn that apparently subsequent to his visits, the model had been altered to reproduce closely every feature of the guide bank in the prototype and that Mr. Inglis had been able to come to the conclusion he had stated. Nevertheless, the Author maintained that a slip, if left unattended, would develop into very much larger proportions and would grow until it became a breach; it was also a possibility that a breach could occur by undermining at the toe of a fully-fallen apron. The additional strip of apron at the foot of the slope suggested by Sir Robert Gales would be a good feeder for slips or breaches which commenced lower down, but if slips commenced, as so very many did, above low-water level, or, worse still, at about high-flood level, the extra strip of apron would not function in the way that was intended.

With regard to the Damukdia bund, it was unfortunate that at the time it had been designed and constructed the railway had not had the advantage of the knowledge which Mr. Inglis had obtained from his model, as then a large amount of money and anxiety would have been saved. It was, however, built after the considered opinion of very many engineers had been taken and was now, the Author understood, being extended.

The model experiments carried out by Mr. Inglis had, in the Author's opinion, given, and would continue to give, most valuable information, with special reference to specific details, such as the pitching of piers, the launching of aprons, the maximum scour in a certain channel, and other such localized subjects which were badly in need of investigation. The Author, however, felt that, over an extended length of 50 miles of an alluvial river, where so many factors entered into the picture and where the alteration of even one factor would perhaps cause innumerable changes downstream, the investigation of the behaviour of a river like the Ganges, by means of a model, was not perhaps the best method; he felt that experience, together with frequent inspection and observation, combined with common sense and an application of general hydraulic principles, could supply the knowledge necessary for designing and maintaining training works of large rivers, aided perhaps, in matters of detail, by the knowledge acquired from the results of model experiments.

Mr. Leitch's remarks were interesting because the Author understood that work was now being carried out to protect the river-bed from scouring to even greater depths than it already did in the vicinity of the guide banks, and thereby to avoid those banks being exposed to the action shown through the glass side on Mr. Inglis'

model. That was being done by continuing the fallen apron far out The Author. into the stream in the form of a carpeting or apron from 3 to 4 feet thick in extension of the fallen apron. The work was both slow and difficult, but it was successful if it were done carefully through floating grids, and by the method described on p. 38 §. "One-man-rock" had been confirmed by the model-experiments to be a satisfactory size of pitching stone. If the rocks were cubical and irregular they were not very easily detached from a mass and rolled away, except in exceptional circumstances, or where the silt below them had been scoured.

Mr. Radice's questions and remarks were particularly interesting because they referred to phenomena that Mr. Radice had discussed as probabilities at the time that the work was in hand, and because the troubles which Mr. Radice had anticipated had actually occurred. In the case of the impounded water behind the mole the trouble had come very early in the flood, in July in fact. The pumping arrangements for the equalization of water-level between the inside of the mole and the river had not been completed by that date, and the seepage he referred to had occurred, causing great damage to the earth bank of the mole and necessitating emergency pitching on its slope with bags of earth and the surplus stock of undersized boulders. Realizing, after that had occurred, that it might occur again at higher levels later, the same protection had been carried up to above high-flood level. When the pumping arrangements had been completed, and were in operation night and day whenever necessary, a maximum difference of 6 inches in the relative levels had been maintained through the flood and late into the fall of the river.

The other trouble that Mr. Radice had feared had also occurred, with very nearly disastrous results. The main stream, flowing past the sheltered water in the lagoon, had set up a very unpleasant large slow-moving eddy. Slips had occurred, probably due to that eddy, both at the river end of the back-water bund and just around the corner, on the river side, from the end of the mole. It seemed, therefore, that the unbroken continuity of guide banks, at bridge abutments, would have to remain the correct design for protective works.

Paper No. 5034.¹

“Newry Ship-Canal Improvement Scheme.”

By ROBERT FERGUSON, B.A., B.E., M. Inst. C.E.

Correspondence.

Mr. Marsh.

Mr. C. M. MARSH observed that the conditions on the Newry canal had many parallels in the Weaver Navigation in Cheshire. Both systems were combinations of docks and a ship-canal, but while at Newry the docks were at the upper end of the ship-canal, on the Weaver the docks were situated at Weston Point on the Mersey and the canal acted as a feeder running inland to the chemical works at Northwich (13 miles) and to the salt-works at Winsford (20 miles), and was available for coasters with fixed masts and funnels for a distance of 16 miles.

The figures given on p. 55 § as the maximum dimensions of boats likely to use the Newry canal were almost identical with the limits at Weston Point docks (namely, 240 feet length by $15\frac{1}{2}$ feet draught by 37 feet beam); as the Author was providing for vessels of 1,000 tons gross with those dimensions, it might be of interest to record that at Weston Point the largest steamer docked during the last 10 years had a gross tonnage of 1,436, and that during that period as many as fifty-two vessels of over 1,000 tons gross, carrying on an average 1,400 tons, had been docked.

The narrowest places on the old canal at Newry were stated to have had a waterway area of 600 square feet. That was a similar figure to that for the narrowest places on the Weaver Navigation, and gave a waterway-to-craft ratio of 3 to 1 for typical loaded Weaver craft. That ratio was found to produce serious bank-erosion, and wherever possible steps were being taken to increase the area of the waterway. The selection of 3 to 1 on the Newry canal was therefore of interest, as was the adopted profile with underwater slopes of 1 in $1\frac{1}{2}$, which would appear to be unusually steep unless the strata through which the Newry canal passed were exceptionally favourable. Examination of recent cross-sections on the Weaver showed normal slopes under-water of 1 in $2\frac{1}{2}$, whilst a slope as steep as 1 in 2 was only occasionally found. The typical cross-section was saucer-shaped with slopes steepest at mid-depth and flattening out towards the surface and towards the bed of the canal.

No mention appeared to be made in the Paper of the speed of

¹ Journal Inst. C.E., vol. 4 (1936-37), p. 51 (November, 1936).

§ Page numbers so marked refer to the Paper.—ACTING SEC. INST. C.E.

vessels navigating the Newry canal, or whether it was anticipated Mr. Marsh, that vessels of large dimensions would pass each other in the canal. The bed-width of about 50 feet would indicate that passing was not intended, at any rate with steamers of 28 feet beam; in view of the relatively short length of the canal it would be a simple matter to avoid that without serious delay to vessels. If that were so, a more stable profile would seem to have been possible by easing the side slopes, with a reduction in the bed-width, the surface width being apparently the limiting factor.

The Author's remarks as to the longevity of timber that was completely immersed could be confirmed by numerous examples on the Weaver. During the recent construction of a flood-water sluice, a disused lock, constructed in the 18th century, was pumped out. The floor of the lock was formed of timber baulks, rough dressed, about 12 inches square, spaced 4 feet apart with the intervening spaces filled with hand-packed rubble. Those timbers were without exception in perfect condition. The standard method of bank-protection, which had been used on the Weaver for 50 years wherever there was shallow water alongside the bank, was by overlapping pitch-pine planks. The present condition of the oldest planking was therefore of interest: the upper parts above water level were badly decayed, whilst the portions entirely immersed and those in the ground were in perfect condition. The present method of treating that planking was to drive the timber sheeting so that the tops were only just above water-level: they were provided with a mild-steel flat waling anchored to back piles at 7-foot 6-inch centres and were entirely encased in a concrete capping extending about 3 inches below water-level. The spacing of the back piles and tie-rods was worth noting in view of the Author's spacing of 30 feet between centres. A spacing of 15 feet between centres had been originally selected on the Weaver, but bulging of the planking had occurred; intermediate rods and piles were added and for about the last 40 years a spacing of 7 feet 6 inches had been used with complete satisfaction. The cost of the present form, complete with concrete cap, tie-rods and back piles, together with a moderate amount of filling and bank sloping, averaged 45s. per linear yard, which compared with the 38s. 6d. per linear yard given in the Paper.

The details of the construction of the outer gates at Victoria lock were of considerable interest and value. The most radical change made was the replacement by steel buoyancy-gates of the timber gates which had had a life of 80 years. It would be of interest to know whether the provision of timber gates—greenheart frames with pitch-pine facing—had been considered, and to have the reasons for the selection of steel gates. Did the Author anticipate that

Mr. Marsh.

the steel gates would have a life of 80 years ? Mr. Marsh regretted the absence of information as to the steps taken for obtaining accurate templates for dressing the heelposts and clapping-sills of the new gates to suit the old masonry, and as to the difficulties experienced in fitting the new gates. In view of the time during which the canal was out of commission, it would seem probable that it had been found necessary to remove the old gates prior to the final dressing of the timbers of the new gates. Could the Author confirm that point, and had any information been gathered from the course of the work which would have enabled the time to be reduced ?

The Author.

The AUTHOR, in reply, noted with interest the similarity between the dimensions of the entrance lock at the Weston Point docks of the Weaver Navigation and those proposed at Newry for the accommodation of vessels of 1,000 tons gross. The fact that a number of vessels up to 1,400 tons gross had docked at Weston Point did not preclude, however, the possibility of one of the dimensions of a vessel of 1,000 tons gross from reaching the limits of any one of the three dimensions of the lock. In order that a vessel of 1,000 tons gross might be chartered without special reference to its length, beam, or draft, it was necessary to provide for the contingency of such a vessel being somewhat abnormal in one of its dimensions.

The material through which the canal had been cut, although varying in character was generally favourable, and in the vicinity of McShane's bridge, where the greatest widening had been effected, it consisted of hard gravel which was extremely difficult to excavate. Originally, the banks had been pitched to a depth of about 3 feet below the water-level of the canal and the underwater slopes below that depth had been unprotected. The top portion of the bank had been formed of imported material which, even when pitched, did not stand up to the wave-action and required constant repairs, but the lower underwater portion, although standing unprotected at a slope of 1 in $1\frac{1}{2}$, had been stable for almost a century. Artificial waterways with unprotected slopes, although usually constructed to a trapezoidal cross-section, generally reverted to the saucer-shaped section of a natural channel, due no doubt to the elbow between the bed and the slope being filled with material eroded from the bank.

The distance between Albert basin and Victoria lock was about $3\frac{1}{2}$ miles and vessels were required to take at least 1 hour in travelling that distance. A lie-by was provided in Ogle's Bay (*Fig. 1*, p. 52 §) to enable a vessel catching the tide to pass an incoming vessel, but normally the sailing-arrangements made by the harbour-master avoided that necessity. The bed-width had been made as wide as possible, consistent with the stability of the underwater slopes, with

the object of increasing the sectional area of the waterway and not The Author, for the purpose of enabling vessels to pass.

The method of bank-protection adopted at Newry differed from that on the Weaver, as king-piles, the rubble septum, and the masonry wash-wall had not been provided on the Weaver. Accordingly, the spacing of the tie-bars on the Weaver ought to be much closer than was necessary at Newry.

The replacement by steel buoyancy-gates of the timber outer gates at Victoria lock was more economical in initial cost than the replacement in greenheart, necessitated the canal being closed for a shorter period of time, and obviated the underwater renewal of the existing cast-iron roller-path which was very much worn. Moreover, it followed the precedent that had been established in 1923, when the inner gates were replaced with steel buoyancy-gates. The Author did not possess the prophetic powers that were necessary to anticipate with any degree of accuracy the life of steel lock-gates, but he considered that the comparative ease with which steel buoyancy-gates could be floated out for major repairs and re-stepped conferred an advantage on that type of gate over the ponderous timber gates which could not be handled without the use of heavy lifting-tackle. In a small port like Newry that type of plant was not available and it was necessary in the dismantling of the old gates to cut the ribs into sections for easy removal. The operation of dismantling the old gates had occupied a considerable portion of the time that the canal was out of commission, and further delay had been caused by the rapid accumulation of mud which seriously hampered the diver in getting into proper position the template for the clapping-sills and socket casting. There had been no difficulty in dressing the heelposts to the radius of the hollow quoins, but the clapping-sills could not be dressed until the templates of the masonry sill had been obtained, and that was not possible until the old gates had been entirely removed. If there had been no mud-problem and if heavier lifting tackle had been available at the site the time taken in installing the new gates would have been reduced appreciably. No difficulty had been experienced in the actual stepping of the gates.

The operation of taking a template of the masonry sills presented no special feature. The diver screeded the face of the sill and projected the line on to the underside of the wood template, which was then cut out so that the edge of the template could be scribed to the face of the sill. As the cast-iron nosing had corroded, and in some places the masonry had been grooved by the action of the hauling chains, it was not possible to obtain a perfectly water-tight fit.

Paper 5062.¹

"Simple Experimental Solutions of Certain Structural Design Problems."

By Professor ALFRED JOHN SUTTON PIPPARD, M.B.E.,
D.Sc., M. Inst. C.E.,
and STANLEY ROBERT SPARKES, M.Sc.

Correspondence.

Dr. Nichols.

Dr. H. J. NICHOLS, of Bombay, considered that the method dealt with in the Paper was one which might be of some value in dealing with a small structure which relied for stability on the stiffness of its members against bending. As the size of the structure increased, the percentage error became of greater importance, and the necessity for accuracy became greater. In the structure dealt with in the Paper, however, the calculations themselves were not excessively long, and could be relied on to predict with fair accuracy—certainly within the limits of the tolerances of the British Standard Specification for Structural Steel—the stresses to be expected.

It could not be overlooked, however, that even in flat two-hinged arches the arch-shortening effect could be considerable and should be taken into account, and that that effect depended on the cross sectional area of the rib. When the moment of inertia of a typical built-up steel member was represented in a model by a member rectangular in section, as was inevitable in models cut from sheet material, the sectional area of the model-member was always greater than its scale value. The low experimental value given on p. 92 § for the roof-portal for the new Central Depot (Westminster) exemplified the effects of that difference in area. On the other hand, in the case of the Lengué arch, in which the model-members were also rectangular in section and proportional to the sectional area of the full-size members, those members were bound to have been considerably deficient as regards their scale lateral stiffness.

The only real solution was to recognize the fact that each structural member was possessed of two separate fundamental properties, its lateral stiffness against bending and its stiffness against longitudinal strain, and to provide accordingly for those properties in models. That adjustment could be made comparatively simply by introducing into each model-member, proportioned for lateral stiffness, a device to reduce its longitudinal stiffness to the correct scale value. That device could be similar in principle to (although very much smaller and stiffer than) that described in Dr. Nichols's own Paper on "Pre-

¹ Journal Inst. C.E., vol. 4 (1936-37), p. 79 (November, 1936).

§ Page numbers so marked refer to the Paper.—ACTING SEC. INST. C.E.

stressing Bridge Girders." ¹ That device, it might be mentioned, Dr. Nichols, need not affect the transverse stiffness of the member in question.

The method of model-investigation was one which had unfortunately been considerably neglected in Great Britain in the past, and its developments held out prospects of a more ready acceptance among British engineers of new forms of construction.

The AUTHORS, in reply, agreed substantially with the comments ^{The Authors.} made by Dr. Nichols, but observed that his criticism applied equally to most other suggested methods of experimental stress-analysis. Unless the elastic properties of the structure were reproduced in exact proportion errors were bound to occur and their importance would vary with different types of structure. In many cases simplified models of the kind used by the Authors would introduce errors so small as to be negligible, and probably less than those caused by assumptions made in arithmetical stress-analysis. In the calculation for the roof-portal for the Central Depot, for example, the structure had been divided into a number of short lengths each of which was assumed to be of constant cross-section; the difference of 3.7 per cent. quoted in the Paper was therefore the difference between two approximate solutions. An exact solution would be so laborious as to be impracticable.

The value of the Authors' method depended upon its simplicity and the ease with which results sufficiently accurate for many purposes could be obtained. A distinction had to be made between an elaborate experimental investigation such as that described by Dr. Nichols in his Paper ¹ and a simple preliminary estimate or check calculation, which was the object of the Authors of the present Paper. In many types of structure the ingenious device due to Dr. Nichols would be advisable or even essential, but to introduce it in every case would make experimental analysis sufficiently formidable to deter most designers.

Paper No. 5028.²

"Repeated Stresses on Structural Elements."

By Professor FREDERICK CHARLES LEA, O.B.E., D.Sc. (Eng.),
M. Inst. C.E.

Correspondence.

Mr. H. B. GATES, of Perth, Western Australia, referring to the Mr. Gates, figures given in Table V (p. 109 §) in which it appeared that the safe

¹ Journal Inst. C.E., vol. 5 (1936-37), p. 91 (February, 1937).

² Journal Inst. C.E., vol. 4 (1936-37), p. 93 (November, 1936).

§ Page numbers so marked refer to the Paper.—ACTING SEC. INST. C.E.

Mr. Gates.

range of stress in joint type "O" was only about 8 to 9 tons per square inch at the limit, wished to point out that the bearing stresses used were too high. For a working tensile stress of 8 tons the bearing stress usually recommended was not more than 10 tons, whereas that employed in the specimen was 13.33 tons. Undoubtedly a high bearing stress complicated the stresses around the rivet-hole, thus giving a false idea of the tensile strength of the plate. He had always suspected that 10 tons was too high, and that the bearing stress ought not to exceed 8 tons.

Again, the transference of stress through a riveted joint was a complicated matter, and did not receive sufficient study from the average designer. The effect of an added cover-plate was to produce a discontinuity of section, similar to a notch. There was a sudden transference of stress at the first and last rows of rivets, whilst an intermediate row, if used, took only a small proportion. Those considerations led him to believe that the diamond form of cover was unsound, as there was a definite concentration of stress carried by a single rivet at the point. That conclusion was borne out by the curves in *Fig. 13* (p. 111 §) where joint "P" was seen to be by far the best. Similar reasoning applied to welded cover-plates. The general conclusion was that there should be no stinting in the number of rivets, or, alternatively, in the weld-metal.

Dr. Nichols.

Dr. H. J. NICHOLS, of Bombay, wished to express his admiration for the way in which the Author had carried out the series of tests described in the Paper, but he was doubtful as to the extent to which the manner of loading the test-specimens represented actual loading conditions in a member of, for example, a bridge structure.

It was stated on p. 95 § that the repeated-stress experiments had been carried out in a Haigh machine, but information was not given as to the cyclic speed. Presumably the tests had been run at a comparatively high rate of repetition, and had proceeded continuously until failure had occurred. Such loading conditions were however, very different from those obtaining in any practical structure. A typical loading in, for example, a member of a railway-bridge truss might be represented by twenty repetitions of stress rising to a maximum and dying away again, followed by, say, one hour of complete rest for recovery under a moderate mean load, after which the twenty repetitions would be repeated, and so on. In Mr. Nichols's opinion a test carried out on the above lines would show vastly different results from those obtained by a continuous vibration. To carry out such a test would require a great deal of time and a thoroughly realistic test would evidently have to last as long as the life of a steel bridge, or perhaps 60 years; nevertheless, useful

Comparative data might be obtained in a reasonably short time by Dr. Nichols, repeating tests which ended after about 4,000 repetitions when run continuously, and substituting intermittent loading as outlined above.

It was obvious also that all loadings of a bridge in service were not capacity loadings. A maximum load might occur once per month or once per year, whilst average working loads were little more than 10 per cent. of capacity. It would be of interest if the Author could give his opinion as to what effect, if any, occasional high stresses were likely to have on the ultimate endurance of a member subject to repetitions of stress just below the fatigue-limit. Could the Author also state whether, in the case of continuous repetition tests, there was any connexion between the percentage elongation of a specimen and the number of repetitions it would stand before failure, and if so, could he suggest a practical formula to reduce safe working stresses in terms of the reduced percentage elongation?

The AUTHOR, in reply, agreed that it was quite true that in repeated-stress testing, the conditions could not be the same as under the actual conditions of working, but the same could be said of any scheme of testing with which he was familiar. The questions raised by Dr. Nichols, however, as to the cyclical speed and the effect of periods of rest between the applications of cycles were of great importance. Wöhler's original experiments had been carried out at slow speeds as compared with much recent work, but for wrought iron and mild steels it seemed to be well established that within a very wide range the periodicity of the cycles did not affect the range very considerably at ordinary temperatures. At very high frequencies, as shown by Jenkin at 30,000 cycles per second, the range was higher than at, say, 30 cycles per second, but between 3 and 80 cycles per second it had not been demonstrated that there was any appreciable difference in the fatigue-range. In the Haigh machine used in the tests, the number of cycles per minute was 2,000. The Author had carried out tests from 320 to 5,000 cycles per minute, but he had not been able to establish a marked difference in the fatigue-range.

At temperatures above 300° C., which were not of great interest to the bridge engineer but were of great interest theoretically, the cyclical rate was of very great importance, and it would appear that when the static stress that might be applied indefinitely without conditions of creep approximated to the maximum stress at which fracture took place quickly, then the cyclical rate had little effect on the fatigue-range. It was very doubtful also whether periods of rest had any great effect; for example, in carrying out tests on materials, it had often happened that during some of the tests of the series, the machines had been stopped for long or short periods,

The Author.

but when fracture had occurred, points on the plotted curves corresponding to those delayed tests fell on the curve obtained from the tests run continuously. As Mr. Nichols suggested, all loadings on a bridge did not produce the maximum stresses. The effect of repeated loads below certain ranges did not appear to have any effect in producing fatigue in mild steels, and it appeared, therefore, that only those loadings producing stresses beyond the fatigue-ranges determined experimentally were of real importance. In that connexion, the shape of the plotted curves was of importance.

The point raised by Dr. Nichols as to the "effect, if any, occasional high stresses were likely to have on the ultimate endurance of a member subject to repetitions of stress just below the fatigue limit," was of very great importance. The occasional high stress might be sufficient either once or when repeated a few times, to start a crack, and as at such cracks concentrations of stresses would occur the cracks might continue at much lower stresses. The Author, in a recent Paper,¹ had shown that under corrosive conditions, for example, corrosive penetrations might occur which would finally lead to fracture at comparatively low stresses. He had not been able to show that stresses below the fatigue-range changed the percentage of elongation of mild steel. He had, however, been able to show that certain austenitic steels might be considerably hardened by the stress-cycles, but that that hardening accompanied by the increase of the tensile strength and a diminution of the percentage elongation might take place without any sign of failure under fatigue. Further, mild steels might be hardened by cycles which produced plastic deformation.

Mr. H. B. Gates pointed out, quite rightly, that the bearing stresses on the rivets on the specimens that failed at 8 or 9 tons per square inch was 13.33 tons per square inch. It should, however, be noticed that the ratio 13.33 to 9 was less than 10/6, which would probably be the design-ratio. Nevertheless, the Author was inclined to agree that the bearing stresses in that case might have contributed to the low fatigue-range. As Mr. Gates observed, the transference of stresses through riveted joints was a complicated matter and the Author hoped that much more experimental work would be undertaken.

It might be of interest to point out that in a Paper shortly to be published, it would be shown that failure at holes in flanges of rolled-steel joists, with rivets in them, took place at ranges of stress of about five-eighths of those at which the flange without holes failed.

¹ "The Effect of Discontinuities and Surface Conditions on Failure under Repeated Stress." *Engineering*, vol. cxliv (1937), pp. 87 and 140.

CORRESPONDENCE
ON PAPERS PUBLISHED IN
DECEMBER 1936 JOURNAL.

Paper 5060.¹

“Ship-Canals Utilized for Drainage.”

By LUDOLPH REINIER WENTHOLT, D. Tech. Sc., M. Inst. C.E.

Correspondence.

Mr. R. G. CLARK agreed with the Author that, generally speaking, Mr. Clark, the interests of navigation and land-drainage operating in one inland waterway did not always coincide. In high peak-flood periods, low water-levels were necessary in the reservoir to pump land-drainage into without stoppage or interruption. On the other hand, navigation required all the water obtainable, as it was easier for ship-propulsion and steerage.

Conditions in Holland and England differed considerably, and barges with a capacity of up to 2,000 tons were used in Holland, as compared with those of about 30 tons capacity used in England. Again, the difference in tidal range in England and Holland was great; he believed that the tidal range in Rotterdam was about 6 feet, whilst on the seaward side of the Zuider Zee embankment the range was probably only about 2 feet.

He agreed with the Author that the size of the craft should have a minimum ratio of 7 to 1 to the wetted perimeter of the canal or waterway; in other words, the larger the craft the larger should be the canal-capacity. That was also helpful to land-drainage, as it provided a larger reservoir to accommodate the surplus flood-water from the adjacent land. The ratio of the canal-capacity to the area drained in Holland was notable.

He agreed with the Author that the critical velocity in inland waterways was governed by the material in the bed and in the sides of the canals. He had met with hard gravel, clay, and fine sand within a distance of 10 miles, and it was the velocity that eroded the fine sand that controlled the velocity of the canal. It would be of interest if the Author could show in a diagram the hydraulic curves from end to end of the canal during sluicing under flood conditions at Ymuiden. With neap tides and adverse winds the sluicing-range and time-factor would add interest to the Paper.

¹ Journal Inst. C.E., vol. 4 (1936-37), p. 221 (December, 1936).

Mr. Clark.

What was the effect of wash from the self-propelled craft? He had noticed in northern France that the wave following large craft was sometimes not so large as the wave following smaller craft, but the question of speed was a factor to be taken into consideration. It might be that the wave after a vessel passed caused more damage to the canal-sides than the velocity due to sluicing the excess water. Alternatively, the combination of both might cause the maximum damage. He would be interested to learn the results of the Author's experience.

Mr. Gardner.

Mr. A. C. GARDNER pointed out that in a country like Holland drainage considerations had of necessity to take first place, and so long as navigation interests were not hampered by the restricted size of vessels both purposes could be equally served. When, however, as in the case of the North Sea canal, provision had to be made for vessels with a draught of 9 metres, it was at once apparent that the problem to be faced by the engineers became one of the first magnitude, involving as it did questions other than those of actual construction (important though the latter were). The Author stressed the importance of the most suitable water-level in a canal to suit both conditions, drainage requiring a low water-level and navigation requiring a high one. The problem was further increased by the large quantities of water brought into the canal in rainy seasons, amounting to over 7,500,000 cubic metres per day, and further by the limited output of the pumping plant at the eastern end of the canal, and by the tidal conditions controlling sluicing-operations at its outlet into the North Sea at Ymuiden.

The Author stated that, as the result of reconstruction-works in hand, the cross-sectional area of the canal was being increased from 800 to 1,440 square metres, an increase of 80 per cent., but that he did not anticipate that the maximum velocity of flow would be greater than at present. It appeared that with the greatly increased carrying capacity of the canal the velocity would be materially reduced. The mean velocity of 0.5 metre per second did not seem to be very high for a canal of the size mentioned, where the ratio of the perimeter of the largest vessel using it to the perimeter of the canal itself was as low as 1 to 7. There were many navigation-canals where that ratio was much higher, and where the mean velocity was also greater. In the case of many canalized rivers such conditions might be regarded as extremely favourable. To cite only the case of the river Clyde, a tidal velocity of more than twice the figure referred to above was quite common, whilst the perimeter ratio was higher over considerable portions of the length of the navigation. In the extreme case of the *Queen Mary*, when the vessel was leaving the shipyard the critical ratio was about 1 to 4.

That was naturally exceptional, but in many cases the ratio would be about 1 to 5 or 1 to 6. Would the Author give the ratio f/F in respect of the three canals referred to on p. 225 § ?

The question of maximum permissible velocity was also a matter upon which he would like further information. He agreed that the velocity ought not to be so great as to render navigation of ordinary vessels difficult, and that it should be below the known critical velocity at which the material composing the banks of the canal could be transported.

The points considered above would appear to be the main considerations, and it was not clear why traction-costs per horsepower-hour, which in their turn depended on the kind of power used and on variable fuel-prices, entered into the question of canal-design, unless the canal-proprietors were themselves the owners of the transport and were vitally concerned with the question of economical transportation. Perhaps the Author would be good enough to answer that question.

The Author stated that by enlarging the cross-section of the Twente canal over a length of 20 kilometres to one-and-a-half times that required for navigation, it had been possible not only to avoid the costly construction of a number of culverts under the canal, but at the same time to increase the value of adjacent lands by an amount equal to 75 per cent. of the total cost of the works. That being so, why was the straightforward expedient of enlarging the cross-section of other canals not more commonly resorted to, seeing that the permissible velocity increased with the increase of the ratio F/f and that the amount of drainage-water which could be discharged through a canal increased rapidly with any increase in its cross-sectional area ?

In the design for the inflow structure for the Bolksbeek the decision to place the settling-basin above the weir was undoubtedly wise, as was also the decision to place the weir at an angle to the canal, whilst the placing of the sill and floor out of level in order to secure the least disturbing inflow to the canal was a very ingenious method. It would be of interest to know if that method had been adopted elsewhere, or whether it had originated in the experiments to which the Author referred. What normal method of protection was adopted on the dykes in open stretches of the canal ?

The conditions governing the requirements of the spillway near Zutphen appeared to have been well considered in relation to the varying seasonal drainage-discharges and to the probable river-levels in the Yssel, whilst the experiments in the hydraulic laboratory

Mr. Gardner. at Delft also appeared to have contributed useful information towards the detailed features of the design. Concrete seemed to have entered very largely into the construction-works described. To what extent, if any, were the spillway-face, sills, and culverts protected by stone facing of any kind?

Mr. Peel. Mr. CECIL PEEL observed that many navigable waterways were tidal or non-tidal rivers which had been deepened and trained, and which therefore had certain currents along them, whilst even in canals considerable movement of the water was caused by the passage of vessels. All rivers had tributaries, and if they were canalized or deepened the problem of the entry of drainage-water would arise in its relation to navigation. Again, it was seldom possible to construct a canal, which necessarily had to cross a great many natural watercourses, without having to use it for drainage purposes.

Generally the water which flowed along a river or entered a canal from drainage-channels contained silt which was frequently deposited in the waterway, and could become a hindrance to navigation. A constant velocity which neither scoured nor allowed deposition represented the ideal, which was never attained in practice, in those types of channels. Usually the deposition was confined to a definite position in the channel, and a somewhat greater depth could be maintained there so as to have a reserve for silting. Large canals were usually constructed, and rivers deepened, to a trapezoidal cross-section, but it would seem that that was not a very favourable section from the consideration of silt-equilibrium. Natural earth-slopes, river-beds, and banks were never straight lines in cross-section.

It had been shown¹ that the natural shape of the cross-section of a straight channel through alluvium which was in silt-equilibrium was a semi-ellipse, and while that was seldom exactly the case in practice in a large natural channel, yet the section was always curvilinear.

Examination of the cross-sections of rivers and canals after they had been left undisturbed for some time, except by the action of currents and the passage of vessels, invariably disclosed a deposition of silt in the bottom angular corners of the trapezium, and frequently near the middle of the channel. In plan these were never absolutely regular, since a straight channel was not a natural one and the water tended to form a winding channel of greater depth between the shoals of silt. The reason for that typical

¹ G. Lacey, "Stable Channels in Alluvium." Minutes of Proceedings Inst. C.E., vol. 229 (1929-30, Part 1), p. 259.

position appeared to lie in the existence of transverse currents in Mr. Peel's channel.

It had been shown¹ that in a straight channel along which water was flowing, the level was slightly higher in the middle than at the sides, and that caused the water to have a helical motion. It tended to flow downwards in the middle, outwards across the bottom towards the sides, up the sides, and inwards across the surface towards the middle again. In a channel having sharp angles between the bottom and sides that flow caused eddies in the angles, and those caused the deposition of silt, which might either be suspended in the water or derived from erosion of the bottom and sides. Again, the lateral flow was less in the middle of the bed and there slacker water and deposition occurred. Thus the channel tended to form a curvilinear or semi-elliptical shape, and once formed there was a more uniform general flow, resulting in silt-equilibrium.

In constructing and maintaining channels, therefore, it was possible that some benefit might result from making the section curvilinear at the bottom instead of entirely level, the sloping sides forming tangents to the curve. That would quite possibly effect a reduction in the absolute amount of silting, which would be more uniform across the bed. Moreover, the silt would be deposited in a channel which was deeper in the middle than was actually required for navigation, and so would interfere less with it. The cost of forming the channel to that shape in the first instance might be considerable, but more excavation would be required, but in a canal or river which required heavy maintenance dredging the extra cost would not be so relatively large, and if economy in maintenance resulted, the extra cost might be worth while. The curvilinear section would be easy to form with machines of the land-dredger and drag-line types working across a canal, but with a floating dredger it would have to be formed in steps which would be transformed into a curvilinear shape by the action of the water.

Another advantage that that form of channel would possess was that, on occasion and by using special care in towing, somewhat deeper-draughted vessels could use the channel than would otherwise be possible. Again, there would be a greater depth in the middle to allow for the "squatting" of vessels when under way. That would amount to 6 inches or more in the case of a ship of 26 feet draught navigating in a canal 28 or 30 feet deep, with a ratio of sectional areas of about $4\frac{1}{2}$. "Squatting" was due to the displacement of water from ahead to the stern of the ship due to its forward

A. H. Gibson, "Hydraulics and its Applications." Fourth Edition, London, 1930, p. 331.

Mr. Peel.

motion. That caused a current of water relative to the sides and bottom of the canal, the kinetic energy of which was derived partly from a lowering of the water-level along the greater part of the ship's length, and partly from the bow-wave.

The use of hydraulic models in the design of the various works described in the Paper was very interesting. The use of those models was nearly always justified in such cases as their cost was usually small compared with the savings to be effected, and possibly very costly mistakes might be avoided by their use.

No purely theoretical treatment of even the simplest of hydraulic problems could be at all complete in the present state of knowledge, and indeed quite erroneous calculations could easily be made. The laws of similarity as applied to hydraulics were becoming better known, and it was possible to construct models which gave correct results within the limits of the particular problems for which they had been designed.

Some years ago a model of the upper Mersey estuary had been constructed and its régime had been compared with that of its prototype. That estuary possessed very marked features and quite large changes took place relatively quickly, so that it provided an excellent example for comparison. Unfortunately the ratio of vertical and horizontal scales which had been chosen had not been as correct as it should have been, and subsequent research had disclosed the correct scales. After the model had been operated it was decided at the time what scales would probably have given more exact results, and it was interesting to note that they were the same that research had since shown would have been correct. Nevertheless, the correspondence between the model and the estuary had been remarkable and as the main features had been faithfully reproduced in a general way. With regard to the purely dynamic features of tidal-levels, currents, and relative times of high and low water at various parts of the estuary, the correspondence was almost exact.

In another model the object had been to determine the probable extent of scouring at the outfalls of a large storm-water pumping station. In that case three pumps at times discharged up to 900 cusecs each through bellmouthed outlets of 51 inches maximum diameter. The outlets were fitted with balanced flaps at their ends and were contained in recesses 9 feet 6 inches high and 7 feet wide in a vertical quay-wall. The ground in front of the wall sloped along the wall, being about 3 feet below the sill of the recess in the shallowest case and about 12 feet below in the deepest case. The axes of the pipes were 3 feet 1½ inches above the sills of the recesses; L.W.O.S.T. was 3 feet below, and H.W.O.S.T. 10 feet above, the sills, the maximum tide-level being 4 feet above H.W.O.S.T. When the water in

model discharged at L.W.O.S.T. the scour was very considerable. Mr. Peel. the tidal level was raised the scour became much less, and when it was raised to that of the axes of the pipes the scour ceased. Fortunately that was the lowest tidal level at which the pumps would be used in practice. Higher tidal levels were tried, and it was found that when the water-level was a little above the H.W.O.S.T. the scour recommenced slightly. That appeared to be due to the fact that up to about H.W.O.S.T. a large amount of kinetic energy was lost in wave disturbance, but that above that level that disturbance ceased and the water seemed to strike downwards more directly towards the ground. The model really showed that any scour that might take place in practice would not be serious and could be tolerated, and such had been the case during some 5 years' operation. It was only by experiments with correctly designed models that these peculiar effects could be discovered, and accurate hydraulic measurements made. In the model of the pumping-station, which included the complete system of culverts, passages, multi-flap valve, &c., the head-losses at different points for various flows were measured.

With regard to the tests on turbulence-basins and their downstream sills, and the scour in downstream channels, research had been carried out both in France and Germany upon that problem, using models as well as actual structures. Two systems had been evolved. In France, it was claimed, greatly reduced such scour and obviated the necessity for extensive aprons. In France the toothed sill had been adopted. That consisted of alternate higher and lower teeth, rectangular in section across the stream and triangular along it. The higher teeth generally had vertical upstream faces and sloping downstream ones, and the lower teeth had faces sloping in both directions. The gaps between the higher teeth allowed some of the water to flow into the eddies formed by the higher teeth and so reduced their turbulence and scouring effects. In Germany the grillage system had been used in which timber baulks were laid with spaces between them along the bed of the channel and slightly above it. Those baulks sloped upwards slightly in a downstream direction, and a slight gap was left between the end of the concrete apron and the baulks. The effect was that an eddy was formed and a reverse current set up underneath the grillage, and that carried in material and so filled up the space and prevented scouring beneath the apron. The Author experimented with those devices in his model tests? No, what kind of surface had he given to the model-walls and what material had he used in the models to test the scouring?

The AUTHOR, in reply to the Discussion and Correspondence, The Author. pointed out that in the Netherlands there were some large rivers,

The Author.


the Rhine and its branches and the Meuse, the last-mentioned having been canalized. The Paper did not, however, deal with the Meuse and some smaller rivers, which, notwithstanding their canalization, had kept their character of rivers; it only referred to real canals independent of the question whether they had been in former times natural waterways or not. The canals dealt with in the Paper were not under the influence of the tide, because of the fact that the waterways which had formerly been in open communication with the sea had, with the exception of the large rivers and the estuaries, been closed many centuries ago at their lower end by means of dams in order to prevent the high tides and the salt water from entering into those canals. The dams were provided with sluices. Engineers in the Netherlands had, therefore, little or no trouble in connexion with silt carried by tidal water into the canals. Moreover, the small rivers and brooks, which brought their water into the canals, generally speaking had a catchment-area with a sandy soil, so that their water contained little silt. On the other hand, those rivers and brooks transported, especially during flood-conditions, a great quantity of sand. To prevent that sand from entering into the canals, the inlets were provided with settling basins. As there was little or no silt in the water and care was taken that the sand did not enter into the canals, dredging in the canals in the Netherlands was of small importance. In consequence the fact mentioned by Mr. Peel, that a trapezoidal cross-section of a channel was not a very favourable section from the consideration of silt-equilibrium, was not of predominant importance under the conditions which were met with in the Netherlands.

The erosion of the side slopes due to wave-action might be of great importance. It depended on the material of which the side slopes consisted, on the dimensions and the shape of the vessels, and above all, on their speed. The speed was therefore always limited. The speed-limit was generally from 12 to 18 kilometres per hour for small vessels on large canals, and from 6 to 7.5 kilometres per hour for relatively large barges on the smaller canals. It had been shown in practice that the erosion only occurred between from 0.5 to 1 metre below and and 0.5 metre above the water-level; the slopes of the canals were therefore generally provided either with a protection of stone or mattress-work from 0.5 metre above normal high-water level to 1 metre below normal low-water level or with a construction of steel or wood sheeting of such dimensions that it kept its position even if the slope had been eroded down to 1 metre below the water-level. The normal method of protection of the banks of the Twente canal was shown in *Fig. 9*. At places where boats were often brought alongside the bank the influence of the

propellers was very bad; at such places the protection had to meet much more severe conditions. The concrete blocks were hexagonal. They had a height of 15 centimetres, and the length of the sides was 12.5 centimetres. The concrete was of a composition of 1 part cement to 6 parts of sand and gravel. The blocks were made in special presses.

The engineers and ships' captains in the Netherlands generally preferred a section with an entirely level bottom to a curvilinear section, especially for canals with much navigation. A canal with level bottom had the advantage that vessels might pass with more clearance between them and between the vessel and the slopes than was the case with a canal with a curvilinear section of the same

Fig. 9.




BANK-PROTECTION ON THE TWENTHE CANAL.

rea. The normal section of the Twenthe canal and that of the new Amsterdam-Rhine canal (now under construction) were shown in Figs. 10, p. 354.

The section would naturally not be constant; a deposition of sand from the higher parts of the slopes would be found in the bottom angular corners of the trapezium, but Dutch engineers did not think that a reason why that cross-section, which was in their opinion the best, should not be adopted. Moreover, the alteration of section thus produced was of no great importance. Theoretically, an advantage of a curvilinear form of canal was that vessels of somewhat deeper draught could use the canal than would otherwise be possible. That advantage was not important in the Netherlands, since the draught of the vessels was generally determined by the

The Author.

depth of the lock-sills, and moreover because the depth of the channel was seldom less than 0.5 metre more than the draught of the vessels for which the canal was designed.



There were two reasons why the ratio of the perimeter of the largest vessel using a canal to the perimeter of the canal was perhaps somewhat higher in the Netherlands than in many other countries. In the first place there was little hard material in the bottom, and

the second place the contractors in Holland specialized in dredging, The Author. and Holland had a great fleet of dredgers. A larger cross-section therefore cost less in Holland than was the case in countries with other conditions. Moreover, there was an important traffic in the Netherlands with rather small steam- and motor-vessels in regular service, for which a rather high speed was very important; hence it followed that the cross-section was determined not by the dimensions of the very large, slow-going barges, but by the speed which was allowed for the smaller steam- and motor-vessels. Nevertheless there were many canals, especially the smaller ones, for which the ratio of cross-sections f/F was not very favourable.

He quite agreed with Mr. Gardner that a maximum velocity of 5 metre per second was not high for a canal of the size of the North Sea canal, where the ratio of the wetted perimeter of the largest vessel using it to the wetted perimeter of the canal itself was as low as 1 to 7. The ratio f/F for the canal from Assen to Meppel was about 1:4.2, for the canal from Zwolle to Almelo it was about 1:2.2, and for the South Willems canal it was about 1:4.

Mr. Gardner asked why traction-costs per horse-power-hour, which in their turn depended on the kind of power used, and on variable fuel-prices, entered into the question of canal-design, unless the canal-proprietors were themselves the owners of the transport and were vitally concerned with the question of economical transportation. As a matter of fact, inland navigation had almost always to compete with rail and/or road transport, and the canal-proprietors were therefore always concerned with the costs of transportation. If those were low because the cross-section of the canal was large, they were able to fix higher duties than when the canal had a small section. With the same duties there would be more navigation on a large canal than on a small one. Mr. Wilson was interested in the assumption of a tug-pull of 1 kilogram per net ton, and asked how that pull was estimated. In Holland, and also in Germany, the opinion was that that pull was reasonable, and calculations were therefore made on the assumption of that pull.

In most cases it was practically impossible to widen canals in the Netherlands, because there were roads alongside them, and often houses were situated quite near to the canal. Apart from that it was generally very expensive to widen a canal, as enlarging entailed renewal of the bank-protection, lengthening of the bridges and culverts, raising of dikes and roads, and so on. In the case of the Venen canal the cross-section had not been enlarged when the canal was finished, but from the start its cross-section was one-and-a-half times that required for navigation. The ratio of the canal-capacity to the area drained in Holland was not as notable as Mr.

The Author.

Clark seemed to think. It was not the same for the different parts of the Netherlands, but generally speaking it did not amount to more than 4 per cent.

He quite agreed with what had been said by the President and others about the value of model-tests. Models generally cost only a very small percentage of the actual cost of the works. The trials made in connexion with the weir of the Bolksbeek had cost 1,800 guilders (£200), and those in connexion with the spillway at Zutphen had cost 3,600 guilders (£400), less than 4 per cent. and 2 per cent. of the costs of the works respectively. He appreciated the words of Mr. Borer concerning Mr. Thijsse and his laboratory; Mr. Thijsse and himself had worked together in very close co-operation. Generally speaking the models were being used to ascertain the relative merits of various designs, and not to make the design itself. In many cases, however, the designs were altered as a result of the laboratory-tests.

The placing of the sill of the weir of the Bolksbeek out of level in order to secure the least disturbing inflow to the canal had, as far as Mr. Thijsse and he knew, not been adopted elsewhere. That method had originated in the experiments, referred to in the Paper. An apron-length of 8 metres was sufficient because the water was falling vertically and the discharge was divided over a rather large distance, so that the maximum discharge per metre of sill was only $1\frac{2}{3}$ cubic metre per second. The great height of the sill was necessary to get the flow well divided and well directed. A hydraulic jump did not take place. Nevertheless the water flowing over the sill necessitated the provision of mattress-work on a scale similar to that anticipated in the laboratory. The toothed sill mentioned by Mr. Peel had not been invented in France, but by Professor Rehbock of Karlsruhe. The other construction (the grillage system) referred to was of Austrian origin. With both systems research had been carried out at the laboratory at Delft, but they had not been thought suitable for the Twente canal. The surfaces of the model-wall were of paraffin-wax, of cement-plaster or of painted wood. They were made as smooth, in proportion to the scale, as the actual works. Pumice sand had been used in the laboratory as a material in the models to test the scouring action.

Paper No. 5048.¹

"Efficiency Tests of Large Modern Pelton Wheels."

By ERIC NORMAN WEBB, D.S.O., M.C., M. Inst. C.E.

Correspondence.

Mr. HENRY HEADLAND, of Arapuni, New Zealand, observed that Mr. Headland. any novel and interesting features had been incorporated in the design of the machines,² particularly in the way of foolproof protection; from the details given in the Paper those devices had been used to advantage in making testing-conditions ideal. The hydraulic conditions existing at Shanan for the machines under consideration gave a specific speed of 5.12, which was ideal for the type of turbine installed (namely, a single-jet Pelton wheel with a ratio of pitch diameter to jet diameter of 10. A check of the leading dimensions of the machines showed that they complied with normal standard practice, and it was satisfactory to know that the accepted rules of design could be followed safely for machines of large output. In machines of the type under consideration two items contributed mainly to the value of the final overall efficiency; namely, the design of the buckets and the nozzle. In view of the high values of efficiency obtained at all loads it would be useful if the Author would give a little more information concerning the design of those particular items.

For an efficient machine the jet should not be so large that it interfered with the back of the buckets, and the buckets themselves should be so designed that the jet was gradually deflected by the bucket-curves through an angle of 180 degrees, and then freely discharged without striking the wheel. The surface of the bucket should be perfectly smooth and of minimum area to reduce friction-loss. Those requirements were to a certain extent conflicting, and a sketch showing the leading dimensions of the buckets, including the width of out-cut and the values of the various angles, would be a useful addition to the Paper. From the data given in the Paper it was estimated that the lip of the buckets should be undercut at an angle of 73 degrees if impact of buckets on the jet were to be avoided. If a calculation were made for the number of buckets required to develop the specified output it could readily be seen that the machines had been designed for maximum efficiency apart from


¹ Journal Inst. C.E., vol. 5 (1936-37), p. 259 (December, 1936).

² Additional information was published in *The Engineer*, vol. cliii (1932), p. 48.

Mr. Headland, other considerations. The minimum number of buckets required was fifteen, so that there were actually about 50 per cent. more than were actually required. Experience showed that within limits the efficiency of a given wheel increased with the number of buckets, and apparently that was the reason for casting two buckets on to one lug so that all the buckets could be accommodated on the disc.

It was stated in the introduction to the Paper that a special stainless steel was used for the buckets, presumably in anticipation of trouble with corrosion at the backs of the buckets; after 2 years' operation experience should have proved whether stainless steel had been effective in overcoming that trouble. In one case, ordinary cast bronze, steel, nickel steel and stainless steel had all proved so unsatisfactory under a head of 800 feet that the efficiency of the machine had obviously been affected. An analysis of the special steel used for the

Fig. 12.




Shanan buckets would probably show that it contained about 14 per cent. chromium, 0.2 per cent. nickel, and 0.35 per cent. manganese with a Brinell hardness of approximately 200, and heat-treatment at 800° C.

Limitations of space had probably prevented the Author from giving full particulars of the equipment used, and it was assumed that the current-meters were the Texas type Mark V, a cross-section of which was shown in *Fig. 12*. A short description of the construction and operation of the instrument might be of service to those who were not familiar with the apparatus.

The instrument consisted essentially of a two- or three-bladed propeller, in the hub of which was mounted a pair of oil-immersed ball bearings, the entrance of water to the chamber being prevented by a frictionless packing-ring. In the ball-races an axle was fitted which transmitted the rotation of the propeller through a bush with a single or double thread and thence to a toothed wheel,

ch one or two pins were arranged, so that by combination of the Mr. Headland. head and pins signals could be obtained every 5, 10, or 20 revolutions required. The toothed wheel and pins operated a lever which tried a contact arm and contact, all of which were housed in a mber in the main body of the instrument. The contact and ative terminal provided for the opening and closing of a 4-volt al-circuit, which was completed through the meter supporting-Instruments of that type were usually calibrated in still water, were particularly accurate; as pointed out by the Author, ecities could be obtained accurately to within 0.001 metre per nd. Apart from errors due to oblique currents, which would be

Fig. 13.



ferred to later, the only inaccuracy which was liable to occur in practice was that due to the viscosity of the oil used, which might rise to errors of up to 1 per cent. in the rate of rotation, the error increasing with the viscosity and decreasing with the speed of rotation, as shown in Fig. 13.

For velocities in excess of 1 foot per second the screw-type meter registered accurately near the walls of a pipe, but to get within 2.5 inches of the wall either a 4-inch propeller was used, or the standard screw propeller was suitably shrouded, which would probably give rise to a slight error in the registration. A change of shape of the propeller by deformation during operation might affect the rating, and although no mention of that point was made in the

Mr. Headland. Paper, errors due to that cause could be detected by checking the shape of the screw against a plaster cast.

The Author had used two instruments in carrying out the tests although a large number would have resulted in a saving of time and greater precision, because the results would have been less dependent on the existence of a steady flow. On the other hand, however, that would have involved the use of more adequate equipment, including an electric chronograph for recording time and current-meter signals on a chart. It was assumed that the Author had used a telephone or buzzer together with a stop-watch, and the speed of rotation would not exceed 7 revolutions per second: a maximum velocity that was probably satisfactory with contact signal at every 10 or 20 revolutions, although the liability of personal error was not eliminated. The method of supporting the instruments during tests did not seem very satisfactory, and it would perhaps have been somewhat better to have used some rigid form of traversing gear with stream-lined rods, because high lateral stresses on light circular rods due to water flow might cause vibration of the mounting, which would result in the meter giving readings less than the actual flow.

The minimum number of measuring points for a pipe having an internal area of A square feet was given by the relation $n = 4.3\sqrt{A}$ which for the case under consideration gave 19, so that 21 points as provided, should be adequate. Judging from the polar diagram subsequently obtained it was possible that more accurate results would have been obtained if additional measurements had been taken towards the outside of the pipe where the greatest variations in flow and maximum velocity existed, instead of utilizing an equal distribution of measuring points along the diagonal axes of the pipe.

The magnitude and nature of the error in approximating the total flow on the assumption that the velocities varied regularly as concentric circles was useful to know when making a rapid field-check on turbine-efficiency. In connexion with the other two analytic methods of arriving at the areas of the polar figures, it should be pointed out that, while those approximations agreed, they usually gave a somewhat higher result than the measurement of the actual area of the figures with a planimeter, in which case it might be possible that the values of Q obtained with the Ott meter might agree more closely with those expected from the curve forecasting the jet diameter d and the formula $Q = 0.97(\pi d^2/4)\sqrt{2gH_c}$ (p. 271). The known calibration of the jet based on experience and modern

ts had served as a very useful guide to the accuracy of the Ott Mr. Headland. meter gaugings, and such a substantial check was unfortunately not usually available in efficiency-tests on other types of turbines.

A comparison of the results of the tests between the machines with clean and lime-encrusted buckets showed a possible loss of efficiency of up to 1 per cent., and illustrated how important it was to maintain the buckets in good condition.

The flow of water in the pipes as illustrated by the polar diagrams for No. 1 and No. 4 machines were such that the efficiency figures obtained might be expected to be optimistic. As pointed out by the Author, the conditions were similar to those obtained in the Arapuni turbine-tests (p. 280 §). In the latter case it was probable that the disturbance produced at the intake, which was practically at right angles to the flow in the headrace, together with the subsequent downward bend in the penstock, continued down the full length of the pipe. Such a disturbance might persist for more than thirty diameters, which in the case of the 12-foot diameter Arapuni penstocks would give a length of 360 feet, the approximate overall length being 450 feet. The location of the measuring instruments would, however, bring them into the zone of the disturbance produced at the intake. At Shanan, the Author stated that the diameter of the pipe was sufficiently small to provide retardation to any rotational movement which would eventually be damped out in a sufficiently long stretch of straight pipe, but the bifurcation, as well as the vertical and horizontal bends, together with the Johnson and butterfly valves in the pipe, would also bring the current-meters into the region where the disturbance produced by those items still existed.


As noted in paragraph (c) of the conclusions (p. 279 §), the existence of spiral flow would have an appreciable effect on the value of the velocity obtained, for, since the instruments were calibrated in still water, oblique or turbulent flow introduced certain errors which reduced the reliability of current-meter measurements. If the turbulence were not too pronounced the use of two instruments with different registration coefficients might be used as an index to the amount of correction to be applied to the more accurate of the two meters.

The Author had not indicated whether a two-bladed conical screw or the three-bladed cylindrical screw had been used during the tests. Whilst the former was self-cleaning, an advantage with lime-bearing water at Shanan, it gave less accurate results where oblique currents were involved. The shape of the screw, however, was not the most

Mr. Headland. important feature, and where steady oblique currents were known to exist it was advisable to allow the axis of the meter to swing in line with the flow and to make an accurate observation of the angle of obliquity rather than to operate the meter crosswise to the current; the latter method resulted in the propeller being struck at an oblique angle by streamlines whose velocity varied rapidly in magnitude and direction, and also involved a non-uniform distribution of the velocity-elements over the plane of the blades. In consequence current-meters definitely under-registered the forward components of oblique lateral and vertical currents, which were to a certain extent influenced by interference of the meter-supports.

In *Fig. 14* the range of possible error at the maximum velocity

Fig. 14.




in the pipe was shown plotted against the angle of obliquity, while in *Fig. 15* those curves were shown with the cosine of the angle as ordinates. They were straight lines, indicating that the meter integrated correctly all cosine-components, independently of variations in the obliquity.

The unreliability of pitot-tube measurements under flow-conditions experienced in large pipes was now well recognized, but recently an instrument known as the "pitot-sphere" had been developed which was claimed freedom from errors due to obliquity and turbulence. The measurement consisted of a comparison of the pressure distribution at five points on the surface of a 12-millimetre diameter sphere, from which the direction of flow, velocity, and static pressure could be calculated. The method had been used for pipes up to 6 millimetres in diameter, with satisfactory results compared with other methods of measurement. The instrument had the advantage

being simple to operate and inexpensive, and there seemed to be Mr. Headland's reason why it should not be used with pipes of larger diameter.

Fig. 15.



The AUTHOR, in reply, observed that it was hardly practicable or The Author. permissible to go into details of the bucket design, concerning which c. Headland's comments were generally correct. Buckets of stainless steel had been adopted to obtain (a) great resistance to the usual wearing and corroding influences, and therefore sustained high efficiency over long periods, and (b) increased resistance to any incipient cavitation or cognate effects. After 4 years' operation on commercial load, it had been reported that the bucket-tips and lifting edges were as sharp as when installed, and that only the slightest signs of wear of any kind had been discernible anywhere, whilst the original polish had remained undiminished.

The current-meters at Shanahan had been of the two-bladed conical-propeller type. It was believed that the rod carrying the propellers was amply stiff to prevent any vibration at the velocities measured; certainly no vibration of the rod could be detected by usual physical means. It was doubtful whether any increase in the number of measuring points within the area already covered would have affected the results. Additional points in the outermost annulus and next the skin, however, were most desirable, and would be valuable for checking the somewhat arbitrary value of the velocity accepted for the flow next the skin. The only practicable means for detecting that would appear to be the pitot-tube in one of its later and more reliable forms. The tendency to spiral flow at the metering station could not have been other than slight, and the angularity correspondingly small. Without some other equally reliable form of check-measurement, it was not possible to estimate what effect

The Author. such angularity as actually existed might have had on the accuracy of the velocity measurement. A reliable pitot-tube velocity-meter would be a great boon, and there seemed reason to expect that it would become a practical reality of the near future. The Author had had no experience of the "pitot-sphere" referred to by Mr. Headland.

CORRESPONDENCE
ON PAPERS PUBLISHED IN
JANUARY 1937 JOURNAL.

Papers Nos. 5054 and 5055.¹

“The Lower Zambezi Bridge.”

By FREDERICK WILLIAM ADOLPH HANDMAN, C.B.E.,
M. Inst. C.E.

and

“The Construction of the Lower Zambezi Bridge.”

By GEORGE ERIC HOWORTH, M.C., B.Sc., M. Inst. C.E.

Correspondence.

Mr. W. J. DOAK, of Brisbane, considered that further information Mr. Doak. might have been given in regard to the depths at which the bridge-piers should be founded. Mr. Handman, for instance, after describing how careful investigation had been made as to the greatest probable depth of scour, stated on p. 334 § that it was assumed that 60 feet was about the maximum depth, and that, assuming 50 feet below bed-level would be safe, it was considered that a depth of 110 feet below low-water level would be sufficient. Surely something more scientific than such a simple assumption was involved in the determination of the founding depth? Literature on the subject of pier-design was meagre and unsatisfactory, and as the reduction of perhaps 20 feet in the depth of all the piers in the bridge would have saved many thousands of pounds, it was remarkable that the science of pier-design had made so little progress.

Experience in sinking that class of pier had established that the surface-friction of sand against concrete was much the same at all depths, and had a value of about 4 cwts. per square foot. That being the case, Rankine's theory of pressures in granular materials would have to be abandoned, on the reasonable assumption that the coefficient of friction remained constant. If that were true, how could the theoretical bearing power of the sand be affected? Since increase of depth apparently did not increase lateral pressures, the resistance to upheaval might not increase either, so that it was not apparent what was gained by going to great depths. For instance,

¹ Journal Inst. C.E., vol. 4 (1936-37), pp. 325 and 369 (January, 1937).
§ Page numbers so marked refer to the Papers.—ACTING SEC. INST. C.E.

Mr. Doak.

it might have been as safe to found at, for example, 80 feet below low-water level, because the bearing power of the sand was just as great at that depth as at 110 feet, and the load on it would have been reduced by about the same amount as the frictional support. While considering the question of foundations, what class of material was met with in piers 23, 25, and 26, which Mr. Howorth said was unacceptable (p. 398 §)? Mr. Howorth's views upon the design of the piers were of great interest, and it appeared that a different type of well altogether might have saved much time and trouble. For instance, a circular well 30 feet in diameter, with an outer wall 12 inches thick, would be an attractive design; the necessary weight for sinking could be given by a solid cylinder 10 feet in diameter in the centre, connected to the skin by radial walls, thus giving a number of dredging wells close to the outer skin. The central cylinder would have a sharp conical point at the bottom, forcing the sand into the wells. When the necessary depth was reached and the bottom sealed, the wells might be filled with water rather than with sand, and the open top then filled to such a depth with concrete as was necessary for supporting the piers above.

Mr. Fereday.

Mr. H. J. FEREDAY could confirm that the geological and physical conditions in the area, as ably described by Mr. Handman, had called for anxious preliminary study in deciding upon the location of the bridge, and also that the foundations had been carried down to such a great a depth not only as a very necessary precaution against scour but also by reason of the risk of earthquakes. Although the tremors experienced during construction had been of no great intensity, stronger movements might occur at any time.

The allowances made in design for wind-pressure as well as for impact were in accordance with requirements of the British Standard Specification. In point of fact, however, the wind-pressure was not a controlling factor in the design of the bridge-members.

With regard to equating the cost of the superstructure with that of the piers and establishing the length of unit span on that basis, since such a computation had necessarily to be made upon preliminary estimates of cost, the equation was seldom likely to be exactly fulfilled when actual contract prices were applied. According to the original estimates the span-length adopted was the economical length. Mr. Nichols had suggested in the Discussion that the substructure members to halve the effective length of the posts were unnecessary, and that they were a source of secondary stress. Their omission would have necessitated heavier posts, and their contribution to secondary stress was of little consequence.

He also wished to emphasize the great technical interest taken in

the fungus attack and bacterial action upon the paint. That experi- Mr. Fereday.
ence indicated the desirability of experimental observation to deter-
mine the suitability under site-conditions of any paint proposed for
an important work in a tropical climate.

It was a source of satisfaction that, by the means provided,
including the special domes for compressed-air work, and by the
energy and resource of the men on the spot, such difficulties as
those had been successfully overcome.

Sir ROBERT GALES observed that the final design of the bridge Sir Robert
formed a happy illustration of the value of collaboration between Gales.
the two firms of consulting engineers.

The method described in Mr. Handman's Paper for determining
the foundation-depths of the main piers had been found satisfactory
for alluvial rivers in India. He was unable to agree with the remarks
in Mr. Handman's Paper under the heading of skin-friction. So far
from a foundation of sand not generally offering the resistance
necessary to carry the full load safely without the assistance of skin-
friction, his experience at many bridges was that sand under piers
which was or which had been already compressed by overlying sand
and water, and which was so enclosed that it could not escape
laterally, was practically incompressible and formed the best of all
foundations. Moreover, since in spite of all precautions cases did
occur in which the sand around the pier was scoured away below the
assumed minimum bed-level, no credit should be taken for skin-
friction in the design of bridge-well foundations.

Mr. Handman introduced a term "critical depth" which he
defined as the depth "when a well has been sunk as far as it will
go without loading kentledge and without pumping," and sought to
deduce from it values for skin-friction. That critical depth was a
somewhat indefinite point because if the well were plumb and the
cabs were being worked simultaneously, the well would continue
to go down for some time at the cost of an increasing excess of
material dredged over the content of the well sunk. That showed
the formation of a crater around the well at ground-level. Clearly
no figure for skin-friction could be obtained under conditions in
which the sand was going down with the well. It was, moreover,
doubtful whether in the course of sinking in sand the cutting-edge
and cant-plate of the curb offered any resistance to sinking at the
moment of movement, since, when a well was being steadily dredged,
the water in the well was lower than the water outside, with the
result that the exterior surface of the well was being lubricated and
the sand under the cutting-edge being softened by a steady though
slight flow of water, such as took place in a greater degree when the
side water was rapidly pumped out.

It was possible that an approximate figure for skin-friction might be

Sir Robert
Gales.

obtained at the depth at which the volume dredged began to exceed the content of the well sunk, but that had not yet been done. The figures, expressed in cwts. per square foot as was customary, would represent the average value of skin-friction from ground-level to the depth of the cutting-edge. In the present state of knowledge very little use could be made of skin-friction in the design of well-foundations.

By the sinking-effort method, however, well-foundations could be designed with considerable accuracy to be of a weight suitable for sinking in sand to any required depth by dredging and pumping without additional weighting. As some difficulty appeared to be felt in understanding that method as set out in the Paper on the Curzon bridge,¹ referred to by Mr. Handman on p. 334 §, the opportunity was taken to try to make it clearer. The sinking-effort per square foot of the exterior surface of a well was calculated by dividing the weight in water of a linear foot of the well-steining, expressed in cwts., by the area of the external surface of the slice of steining in square feet. The main principle of the method was the preparation of a depth-sinking-effort diagram plotted from cases in which actual wells of known weight and dimensions had been sunk to known depths below ground-level in sand by dredging and pumping, but without added weight. To design a well all that was necessary was to draw out the plan of a well with normal dredging holes and of sufficient size to take the base of the pier with a suitable margin and, assuming the material most readily available, to calculate the sinking-effort which the design would furnish. If that sinking-effort were applied to the diagram it would show the depth to which the well could be sunk without added weight. If it were required to sink deeper it would be necessary to use a heavier material or to increase the thickness of the steining, or both, until the design showed a sinking-effort which would be sufficient for the depth desired. It might be that that depth could not be reached with a practicable design of well, and the amount of added weight required to sink the last length could then be calculated.

The diagram given in Sir Robert's Paper on the Hardinge bridge, also referred to by Mr. Handman, had been confused by too much information about the sinking at that bridge, and a revised diagram to which the sinking-effort of the Zambezi well had been added, was shown in *Fig. 1*.

Mr. Howorth devoted much attention to the difficulties of sinking wells by open dredging through thick beds of hard clay and semi-

¹ R. R. Gales, "The Curzon Bridge at Allahabad." Minutes of Proceedings Inst. C.E., vol. clxxiv (1907-8, Part IV), p. 27.


§ *Ibid.*

² "The Hardinge Bridge over the Lower Ganges at Sara." Minutes of Proceedings Inst. C.E., vol. ccv (1917-18, Part I), p. 33.

ndstone, and criticized the design of the well-curbs with which he Sir Robert
ad been supplied and the height above low-water level at which the Gales.
er construction had to be commenced.

Sir Robert had had a very similar experience 33 years ago in sinking
uble-octagonal wells with curbs designed on the principles advo-
ted by Mr. Howorth, as he had described in his Paper on the
urzon bridge,¹ and he had come to the conclusion that no well could

Fig. 1.



SINKING-EFFORT DIAGRAM FOR BRIDGE-FOUNDATIONS SUNK IN SAND.

(Hardinge bridge well No. 4 sunk by dredging only, and well No. 16 sunk by dredging and pumping.)

sunk through such strata by open dredging with anything like the
me facility and certainty as by the pneumatic process, within the
nit of depth to which that could be used. Very little advance
d been made in sinking through hard strata by open dredging, but
had been made possible by Mr. Fereday's ingenious dome-
nnexion, referred to in Mr. Handman's paper, to apply the
neumatic process at any time to a well primarily designed for open
edging, and all the wells of the Lower Zambezi bridge had been

¹ *Loc. cit.*

Sir Robert
Gales,

fitted with the rings for that connexion. Great advances have, however, been made in the application of pneumatic pressure in foundation work, and by means of the decompression-chamber the depth to which it could be employed with safety had been much increased. Mr. Howorth had placed on record that he had used a pressure of 50 lbs. per square inch and over, and that the maximum incidence of "bends" for both Europeans and natives had occurred at a pressure of about 35 lbs. per square inch, and was about double the mean incidence in both cases. A pressure of 50 lbs. per square inch was equal to the pressure of 115 feet of water.

Examination of the sinking-diagrams of the main-span wells showed that, with the assistance of kentledge, progress through the upper black clay and the brown sandy clay had been well maintained by open dredging, but that well No. 4, with a surcharge of 530 tons, came to a stop at 104.5 feet below water-level after a month of very slow sinking and was there founded, that well No. 21, with 688 tons, was sunk into black clay and satisfactorily founded at 114 feet below water-level without much difficulty, and that well No. 24, with 1,000 tons, was sunk without much delay (except for time taken in loading the kentledge), to 107 feet below water-level and was there founded. It was evident that both Nos. 4 and 24 came to a stop because the grabs were unable to excavate the underlying strata. In both those wells the conditions required the application of pneumatic sinking when the cutting-edge had reached a depth of 85 feet below low-water level.

Mr. Howorth had apparently not realized how extraordinarily easy the sinking of those bridge-foundations had been made for him by the provision of sufficient weight in the wells themselves to ensure sinking in sand to the required depth by open dredging; by the provision of kentledge to assist in passing through strata, such as plastic clays, more difficult than sand but still dredgable; by the provision of the alternative method of pneumatic sinking for strata too hard to be easily dredged; and, finally, by a curb with a short and stiff plate-and-angle-iron cutting-edge capable of resisting deformation.

Mr. Howorth criticized the requirement that the tops of the wells should be sunk to low-water level and that the piers should be started from that level, but he made no definite suggestion for the case of the Zambezi river. He asked for "a working freeboard when founding above at least the highest expected river-level during the working season." What was a "working freeboard," and what was the length of the working season? The working season for the purpose of founding wells and starting construction of piers in that river was very short, but it was not too much to expect of the construction-engineer that, with well-sinking made easy, he should

range his progress-diagrams to bring the founding of the wells and piers within the short working season. The tops of the wells could be kept dry, if in a sandbank by a little pumping, and if in the river by a removable cofferdam clamped around the well or by a temporary wall built at the edge of the top of the well. Alternatively, permission had been given in the specification to build a short length of pier, with dredging holes, on the top of the well, since deep wells were not likely to alter in position during the last few feet of sinking. From the earliest times the neat work of the visible superstructure had been set out on the rougher work of the hidden foundations at ground-level, which was represented in a bridge by low-water level, and nothing was more unsightly than piers founded on wells which were even only slightly out of position, all errors appearing at least to be doubled. If, however, that were overlooked and the tops of wells were fixed at, for example, 5 feet above low-water level, very little advantage would be gained. The working season would be extended for that work from a length of from 4 to 7 months to a length from 7 to 8 months, but the necessity would still remain to ascertain by borings the depth at which the well would be founded, in order to determine the length of steining to be built to bring the tops of the wells to the same level; there was no one, least of all the owner, who could tolerate well-heads of different heights, leaning in different directions, with piers to all appearance perched precariously upon them. Mr. H. B. GATES, of Perth, Western Australia, asked why the Pratt Sir Robert
Gales. type of truss had been employed, when the Warren type was demonstrably more economical, simpler to design, and freer from secondary stresses. That was now recognized by the American designer, Mr. Waddell, and it had apparently been recognized by Sir Benjamin Baker when he had designed the Forth bridge. Indeed, it was difficult to know why the Pratt truss had ever come into vogue, especially the form with redundant bracing. It was also pointed out by Dr. Waddell that the correct measure of economical span-length was to make the cost of main trusses plus wind-bracing equal to the cost of supports, omitting the cost of decking, etc., which was a constant quantity. However, in the case of a single-track bridge, the width between trusses had a limiting effect.

Mr. P. J. RISDON observed that Mr. Handman attributed the Mr. Risdon, reduction in the resistance of the smaller wells to sinking to the slightly steeper angle of the cone-plate with the vertical. Mr. Risdon had been largely concerned with the design of those well-heads, and the following comments might be of interest. The area of caisson having been determined by the permissible foundation-pressure, it remained to design the wells to offer the least resistance (within reasonable limits) to sinking. When the design considered had been evolved, a slight change had been made in the diameter

Mr. Risdon.

of the well, so that the air-lock domes used for the bigger wells could be again employed for the smaller wells, thus saving time and expense. Owing to the smaller size of well, it would have been difficult to apply anything like the same weight of kentledge which the bigger wells were capable of carrying, and that was an additional reason for reducing resistance to sinking. The weight of well being necessarily much less, the best possible compromise between thick and comparatively thin steining had been arrived at, the chief aim having been to reduce the clogging of the sand and clay at the junctions of the cross-wall with the sides, by enabling the grabs to excavate near those points as possible. It was that, far more than the steep angle of cone-plate, that had accounted for the greater ease of sinking. It was true that the angle from the top of the cone-plate to the point where the cross-cutting-edge joined the sides was also steeper, and that that was partly the result of a steeper angle of cone-plate, but Mr. Handman's statement might give rise to an incorrect impression that a steeper angle of cone-plate in any type of curb would make the difference in sinking, which was far from being the case.

Mr. Howorth suggested that cross-cutting-edges could be omitted, the possibility of that had been duly taken into account, but this had been deemed necessary for the sake of general rigidity owing to the length of straight sides, and the small height of curb in proportion to its length.

A type of curb that Mr. Risdon had designed 30 years ago might be of interest. Ten curbs had been employed, each carrying an 8-foot diameter cylinder filled with concrete. The curbs had had to be sunk through a maximum depth of water of 35 feet, and then through about 20 feet of earth, down to a rock foundation where air-lock had been employed. The comparatively small size of curb (16 feet by 10 feet) with rounded ends, and the number of rigid permanent upper strakes (skin-plates), had enabled a cross-cutting-edge to be dispensed with, and the lowest cross stiffeners had been 6 feet 6 inches above the cutting-edge. The upper cylinders had limited the single dredging hole to a diameter of 7 feet, but there had been no difficulty in dredging, the earth having been free from wedging or "arching" effect. A design for the smaller Zambezi curbs on similar lines had been considered, but such a design would have weighed and cost twice as much as those actually provided.

Mr. Handman.

MR. HANDMAN, in reply to the Discussion and Correspondence regretted that Professor Inglis had at first been puzzled by the use of the term "sinking-effort" in connexion with the sinking of the bridge-wells. That term had been used by Sir Robert Gales as far back as 1908 in his Paper on the Curzon Bridge,¹ and although

¹ Minutes of Proceedings Inst. C.E., vol. clxxiv (1907-8, Part IV), p. 23.

had not been in common use at the time, Mr. Handman believed that Mr. Handman had since become so. In addition to the explanation given by Mr. Bowditch on p. 399 §, Sir Robert further defined its meaning in the correspondence (p. 368) and emphasized the importance of the sinking-effort method in connexion with the economical design of well-foundations for bridges.

Professor Inglis reduced the sinking-effort graphs of *Fig. 16* (p. 342 §) to terms of the height of the well protruding above ground-level at the various stages of sinking, which was correct provided that the varying water-level as affecting the weight of the well was also taken into consideration. He thought it would have been helpful if those graphs had given some information about the average sinking-effort and sinking-resistances, but the graphs in question were intended to demonstrate only the various stages of sinking the wells and the final depth to which bridge-wells of a given design could be sunk entirely in sand without the addition of artificial weight or by pumping; in Mr. Handman's opinion the addition of any further details would have complicated the issue. Typical cases of the sinking-effort of wells which were sunk in sand and strata of harder material were shown by graphs in *Fig. 18* (p. 345 §) and reference was made to the nature of the material. The sinking-effort at any depth was shown by both the graphs mentioned above, but an average sinking-effort would be of little value for the reason that it was not governed by a linear relation but varied with the water-level and with the varying preponderance of the weight of the well over the resistances during sinking operations, and only became a definite constant at or near foundation-level.

The measure of resistance to sinking by skin-friction was a controversial matter, and, as Sir Robert Gales pointed out, the present state of knowledge permitted but very little use of it in the design of well-foundations. The large number of wells of the Lower Zambezi Bridge which were sunk entirely in sand presented, however, an opportunity of adding to the information available on the subject and of an attempt at arriving at a closely approximate coefficient. Mr. Handman agreed with Sir Robert that during dredging operations disturbances were created beneath the cutting-edge and cant of the well by the steady but slight influx of water and running sand, and that lubrication took place on the exterior surface of the well. However, the condition of the well were considered when at rest during the intervals of the dredging operations, and more particularly at foundation-level, it was clear that further sinking would be prevented by two causes, (a) the resistance by skin-friction on the exterior surface of the well, and (b) the resistance beneath the cutting-

Mr. Handman. edge and cant-plate, and the latter could not be ignored in arriving at the resistance by skin-friction alone. When the well came to rest at foundation-level the sand which had been disturbed was not fully compacted, but it became so as the weight of the plugs and the pier was added, and the well settled down on a firm foundation. In the figure of 6 tons per square foot that he had assumed fairly represented the measure of the resistance of the slightly disturbed sand acting beneath the cutting-edge and cant-plate when the well came to rest, then 3.76 cwt. per square foot represented the measure of resistance by skin-friction. Sir Robert Gales further observed that his experience at many bridges had been that sand under pier which had already been compressed by overlying strata and water and which was so enclosed that it would not escape laterally, formed the best of all foundations, but he added that in spite of all precautions cases did occur in which the sand around the piers was scoured away below the assumed minimum bed-level. As no allowance had been made in the design of the Lower Zambezi bridge well for the resistance by skin-friction, the actual position was that at the estimated depth of scour, 1.46 ton per square foot, or nearly 17 per cent. of the calculated unit load on the foundations of 8.17 ton per square foot, was taken up by the resistance by skin-friction. Should deeper scour take place, thus releasing part of the lateral pressure, there would be a margin of safety, but, of course, a diminishing one.

Professor Inglis thought that it would have been valuable if more observations had been taken to arrive at the measure of skin-friction on wells which were sunk by compressed air. Mr. Handman had taken a number of observations of wells which had been sunk partly in sand and partly in soft clay by open dredging and then by compressed air, but the information obtained had been so inconclusive as to be of little or no value; the reason was that the excavation in the air-chamber had been carried beyond the cutting-edge of the well-curb, and consequently the space outside the skin-plate had remained clear or had become partly filled with loose sand or other material, so that either there had been no resistance by skin-friction on that part of the well which was sunk by compressed air, or only partial resistance corresponding to the amount of loose material which had fallen into the clear space.

Sir Robert Gales had expressed the opinion that when a well sunk entirely in sand reached what Mr. Handman had described as its critical depth, it would still continue to sink without the addition of kentledge or pumping if the well were plumb and the grabs continued to work simultaneously. It was evident that when the well approached the specified founding level they became sluggish, and that the resistances were beginning to take full effect. In the case

f well No. 11, referred to on p. 343 § as being the well which had Mr. Handman.
 been sunk to the greatest critical depth, it would have been necessary
 to resort to pumping to sink it to any appreciable greater depth, and
 the fact that it had done so completely all that it had been expected
 to do was a tribute to its design.

He knew of no scientific method of determining with precision
 the greatest depth of scour which might occur in the bed of a river
 such as the Zambezi, and he agreed with Mr. Doak that little progress
 had been made in that respect ; apart, however, from that indeter-
 minate feature, it would seem that a distinct advance had been made
 in well-design, although he ventured to agree with Professor Inglis
 and Mr. Nichols that it had not yet reached finality. There would
 have been no justification for fixing the founding-level at a lesser
 depth than 110 feet, such as at the 80 feet suggested by Mr. Doak,
 for the reason that although it was known that the river-bed had
 been scoured to a depth of 60 feet below low-water level, it was not
 known, and there were no means of ascertaining, to what depth
 it might be scoured at the site of the bridge when the river-flow
 was obstructed by the piers. It was thought, therefore, that ample
 margin should be allowed and that the security of the bridge should
 be further assured by placing around the piers pitching stones of
 such a size that they would not be carried downstream when the
 river was in flood. Moreover, the probability of earthquake shocks
 had to be taken into consideration.

The conditions did not call for a circular well with multiple
 dredging-holes such as was suggested by Mr. Doak, apart from the
 question of cost and speed of work. A 20-foot diameter circular
 well with a single dredging-hole had been considered, but that
 plan had been dismissed for the reason that it would have necessi-
 tated the pier oversailing the well, which would have been par-
 ticularly undesirable in view of the probability of earthquake shocks.
 Mr. Nichols stated that such a well was the easiest to deal with in
 sinking, but it was questionable whether it would have been easier
 to control, and easier to rectify if it had gone out of plumb, than the
 double D-shaped well adopted. The speed and accuracy with which
 these wells were sunk were a tribute to good work by the con-
 tractors, and also a proof that they were controlled with great
 facility and that the design was a well-balanced one. That was still
 more pronounced in the case of the seven smaller secondary wells
 which were designed subsequently. It was calculated that they would
 reduce a sinking-effort 33 per cent. less than that of the main
 wells and that it would be necessary to load them heavily with
 kentledge. Such, however, was not the case. They were sunk with

Mr. Handman. the greatest ease in sand and sandy clay by open dredging without any kentledge or pumping until they reached soft sandstone, which they were sunk to the required founding-depths by compressed air. Mr. Risdon was of the opinion that the steeper angle of the cone-plate of the curb of those wells would not account entirely for the greater ease with which they were sunk, and with that Mr. Handman was quite in agreement, as would be seen from the following paragraph, which had been omitted from the Paper owing to lack of space:—

“The Author attributes the greater facility with which the secondary wells were sunk as compared with the main wells partly to the grab being able to dredge closer to the cutting edge of the well-curb owing to the reduced thickness of the steining, and partly to the sharper angle of the cone-plates of the well-curb.”

The proportions of the piers and wells had been settled by consideration of the dimensions necessary to accommodate the bearings supporting the spans and the bending stresses which might be produced by longitudinal forces acting at the bearings on the tops of the piers. The dimensions of the wells had also been arranged to facilitate sinking and were not controlled by consideration of the live-load figures, which, as Mr. Nichols stated, were very low when expressed in terms of bearing pressure on the base of the well.

In order to make good the loss of cement when the concrete was placed in water, 25 per cent. was added to the cement-content of the 1 : 3 : 6 concrete for the bottom plugs of the wells. He was in agreement with Mr. Nichols that test-specimens would be more representative of the concrete in a pier if they were cured under the same conditions of the pier itself, but it had not been found practicable to leave the specimens on a pier which was under construction when a pier was being constructed on a dry sandbank they were buried in damp sand near the pier, or, in cases where the pier was surrounded by water, in damp sand on a barge moored to the pier for 24 hours (in both cases) before being removed to the testing room. The concrete caps to the piers, when finished, were kept moist for 10 days.

The bridge had been designed for impact, as mentioned by Mr. Fereday, in accordance with the British Standard Specification, but the Pencoyd formula had since been discarded in favour of a new formula which permitted lower impact-coefficients, particularly for the longer lengths. Professor Inglis asked if the total impact allowance was the very high figure of 284 tons, but that was not so, as the impact-load of 71 tons on one bearing corresponded to the maximum end-shear conditions for the span, so that the total impact

ad was not therefore four times that amount. The wind-pressure Mr. Handman. allowance was also in accordance with the British Standard Specification, which had remained unaltered in that respect. It was suggested that that method was by no means illogical. Bridges, particularly long structures such as the Lower Zambezi bridge, were generally located in exposed positions, and even if during a violent storm the wind velocity were such as to derail vehicles the bridge should remain stable on its supports. In actual fact the amount of extra material required to provide the necessary strength and stability under the regulations in force was in most cases of minor account. The specified method of treatment did ensure that any such material was placed in its most advantageous position.

With regard to the economical length of the spans, the varying distribution of the contractors' costs when tendering so affected the cost of the different classes of work that if one at least of the other tenders had been accepted, the spans would have cost more than the wells and piers, that was to say, the reverse of what actually happened. The reverse would also have been the case with a span of 50 feet, for the ratio of the cost of the superstructure to the cost of the well and pier would then have been in the neighbourhood of 20 as compared with 0.92 for the 258-foot spans. The actual cost of the latter was £13,368 and the cost of a typical well and pier was £4,555.

The comparison made by Mr. Nichols of the spacing of the track-sleepers with the corresponding spacing on Indian bridges was of interest, but the fact that the Lower Zambezi bridge sleepers were secured by stout guard-timbers notched and bolted to each sleeper might have some bearing on such a comparison. With regard to the anti-creep plates, Mr. Handman had recently visited the bridge and he had been informed that the keys were secure and had needed little or no attention since traffic was started on the 1st March, 1935.

In reply to Mr. H. B. Gates, it was extremely doubtful whether the Warren type of truss would have shown any economy over the Pratt type for the span-length in question. Intermediate verticals would have been necessary at alternate panel-points to keep the length of the floor-stringers down to economic limits, whilst additional vertical members would also have been necessary at the other panel-points to support the mid-points of the top-chord segments, or alternatively, additional material would have been necessary in the top chords to cater for bending stresses due to their own weight. The omission of sub-horizontals supporting the mid-points of the vertical members would have rendered it necessary to have increased the dimensions of those members, which would then have acted as struts on the full depth of the trusses. The same remark applied with greater force to the long diagonal struts in the Warren type

Mr. Handman. of truss. The actual trusses adopted were designed, fabricated and erected in such a way as to reduce the secondary stresses to a minimum when the primary stresses in the members were a maximum and in those circumstances the design presented no particular difficulty. The appropriate outline of Warren truss would not have been free from redundant members, and methods of design, fabrication and erection similar to those which had actually been adopted would have been necessary to minimize secondary stresses.

In conclusion, he wished to point out that the section of the Paper dealing with the geology of the district was to a great extent compiled from notes supplied by Mr. F. Dixey, O.B.E., D.Sc., F.G.S., who had rendered valuable assistance during the preliminary investigations.

Mr. Howorth.

Mr. HOWORTH, in reply to the Discussion and Correspondence observed that Mr. Bateson appeared to attach some special significance to the use of the term "contract depth." No special significance was intended. The expression had been in daily use on the works and was understood by everybody to mean 110 feet below low-water level. No criticism of the engineers' decision to sink certain wells beyond that depth was made or implied in his Paper. The bottom in at least two of those wells at 110 feet was definitely too soft to give a satisfactory foundation, and there was never any reasonable alternative to extra sinking. His Paper merely recorded the fact that the wells in question were taken down to extra depth and expressed disappointment that the decision to sink them to extra depth could not be taken at site in time to complete a well-sinking before the 1933-34 flood-season.

He could assure Sir Robert Gales that the easy normal sinking conditions at the Zambezi were fully realized and appreciated by the contractors' staff. As stated on p. 388,§ the design of the wells would appear to leave little room for improvement when sinking through sand. The adaptation of all the well-shafts for the application of compressed air naturally relieved the contractors of some anxiety in that it provided an alternative method by which the wells could be got down with certainty to the limiting depths at which the pneumatic process could be employed with reasonable safety and economy. Unfortunately such difficulties as were met with in connexion with plastic strata occurred at depths greater than the limiting depths for compressed air, and had to be overcome—never with entirely satisfactory results—by the application of excessive kentledge and by resorting to excessive pumping. The criticism of the design of the well-curbs was strictly confined to their unsuitability for sinking through stiff though dredgable material without the application of compressed air. In that connexion there appeared

be some misunderstanding with regard to well No. 24. No Mr. Howorth. Material was ever met with in that well which was unduly difficult to dredge. The difficulty, as with other wells, was to break down the end-resistance after dredging to depths well below the cutting-edge. He agreed with Professor Inglis that "human ingenuity should be able to devise some grabbing mechanism whereby the excavation could be carried almost to the limit of the cutting edge," but he considered that a more hopeful line of approach was offered by the alternative of adapting the design of the working chamber, so that existing forms of grabs, combined with more effective wedging action, could achieve the same object. He was in agreement with Mr. Risdon that the angle of cone-plate was immaterial in the case of the small Zambezi wells. They never encountered plastic material and were never sunk by open dredging to depths sufficient for skin-friction to absorb more than a fraction of their available sinking-effort.

Certain information had been asked for with regard to the finishing-level of the well-heads. The working season proper extended from April to November, and it might have been possible to arrange the work so that all founding and plugging of wells in the open river took place between August and November. In May the river-level might be expected to be about 10 feet, and in August about 5 or 6 feet, above the nominal low-river level specified for the finished level of the well-heads. For a fortnight or so in November it might or might not fall to nominal low-river level or even below. By a "working freeboard" he meant a reasonable height clear above water. He would suggest that a suitable modification of the Zambezi requirements would have been to finish off the well-head proper at 15 feet above low-river level; the last few feet would have been added after founding and plugging. If necessary, a small correction-offset would be made in the well itself before the final stages of sinking at some point which would eventually be definitely below low-river level, but which need not be predetermined except within wide limits. As Sir Robert Gales pointed out, deep wells were not likely to alter in position during the last few feet of sinking, and he could assure him that on the Zambezi bridge it would have been quite impossible to detect any residual error in the position of the well-heads without the use of instruments. He agreed with him that the somewhat futuristic arrangement of well-heads suggested in his comments would be intolerable.

With regard to the question of skin-friction, he could not subscribe to the view that any figures given in his Paper supported a case for the abandonment of Rankine's theory of pressures in granular materials. Except when cutting-edges were quite clear, skin-friction values were always obscured by end-resistance to penetration. That was particularly so in the early stages of sinking, when sinking-

Mr. Howorth. efforts were big compared with skin-friction. The figure of 4.25 cwt. suggested on p. 400 § represented a mean value between surface level and 130 feet below ground. Using Rankine's theory the unit value would be zero near the surface, and it followed that the unit value at 130 feet below ground would be of the order of 8 or 9 cwt. per square foot. That value would be obtained with Rankine's theory with a material weighing 56 lbs. per cubic foot in water and having an angle of repose in water of 30 degrees and a coefficient of friction in water between sand and concrete of 0.22. Those values were by no means improbable for the Zambezi sand.

It was perhaps as well to add that with Rankine's theory there was also available an unlimited choice of other combinations of values of angle of repose and angle of friction, which, with the same weight of material (56 lbs. per cubic foot), would produce the same value for unit skin-friction. They included and lay between limits of angle of repose $12\frac{1}{2}$ degrees with angle of friction $12\frac{1}{2}$ degrees and angle of repose 61 degrees with angle of friction 61 degrees. That apparent anomaly was due to the fact that in the equation for skin-friction

$$f = wk. \tan \theta \frac{1 - \sin \alpha}{1 + \sin \alpha},$$

where α denoted the angle of repose of the material and θ denoted its angle of friction with the surface of the concrete, the two factors $\tan \theta$ and $\frac{1 - \sin \alpha}{1 + \sin \alpha}$ tended to neutralize one another.

It would appear that the inference could be drawn that the angle of repose of a material had only a minor effect as regards the skin frictional resistance to well-sinking of that material, and that the important factors were its effective weight, its depth, and the difference between its angle of repose and its angle of friction with concrete. If its angle of friction with concrete could be varied either by rapid vibration, as was suggested by Professor Inglis, or otherwise, the result was bound to be beneficial. The effect of shot-firing was well known in that connexion.

Although Rankine's theory did not apply without modification to non-granular materials, those figures certainly indicated that there were theoretical grounds for suspecting that the same skin friction values might be produced under the same conditions by materials having such widely differing properties as stiff clay and soft silt. They might also possibly offer an explanation of the widely differing values for skin-friction in various materials which has from time to time been put forward.

CORRESPONDENCE
ON PAPERS PUBLISHED IN
FEBRUARY 1937 JOURNAL.

Paper No. 5089.¹

“The Second-Stage Development of the Lochaber
Water-Power Scheme.”

By ARTHUR HOLDEN NAYLOR, M.Sc., B.Sc. (Eng.),
M. Inst. C.E.

Correspondence.

Mr. H. B. GATES, of Perth, Western Australia, referring to the Mr. Gates.
construction of the Laggan dam, observed that too much attention
appeared to be given to the effects of cracks in concrete dams. He
had recently visited the Mundaring dam in Western Australia, which
applied the well-known pipe-line to Kalgoorlie. The dam was
100 feet high above the bed of the stream, and was about 700 feet in
total length (or about 500 feet, neglecting the shallow ends). It
had been constructed in 1900–1902, before so much science had been
applied to concrete structures, without special joints and without a
drainage-system. Nevertheless it was safe and in quite good con-
dition. The water was about 9 feet below crest-level, and there was
no visible seepage. It was a warm day and such small seepage as
did occur evaporated too quickly to be visible. The cement skin
was just worn off the overfall-section, leaving the stones showing.
Some years ago cracks had appeared on the internal face, but
those cracks had never passed through the dam. It was evident that
cement-concrete would shrink and might crack when dry, but it
swelled again when wetted, and the cracks closed. He might also
cite the case of a smaller dam, for which he had been personally
responsible. That dam was 32 feet high and 240 feet long and had
been constructed without special joints. When dry it showed a
crack in the centre on the upstream face, but after refilling the
inspector failed to locate the crack. Another example was that of a
series of reinforced-concrete tanks of monolithic construction. After
the first dry-out a few small shrinkage-cracks had appeared, but the
engineer had found no sign of a crack when the tanks had been
filled. Those tanks had a total length of 282 feet.

¹ Journal Inst. C.E., vol. 5 (1936–37), p. 3 (February, 1937).

Mr. Gates.


It would, therefore, seem sufficient, even in large dams, to observe the following precautions :—

- (1) Construction-joints should be provided with simple joggling, painted, or pasted, with an asphaltic composition.
- (2) Plenty of plums should be used.
- (3) The water/cement ratio should be kept down.

Two alternative designs for self-stanching joints were shown in *Figs. 28.*

The value of a gunite lining seemed doubtful. If the main body of concrete cracked, the skin was bound to crack also, and it would seem more profitable to employ the extra money in using pre-cast blocks.

Figs. 28.



Mr. Gullan.

Mr. A. G. GULLAN observed that the grey plagioclase granite which outcropped at the Laggan quarry and tunnel-intake, would have made a very suitable monumental rock, had it not been marked with dark patches of xenocrysts of the country rock, schist, which had been caught up by the granite in its intrusion. The section between expansion-joints 2/3 and 6/7 was a very much coarser rock, and contained red felspar near each of those expansion-joints; evidence of faulting could be seen, and near expansion-joint 6/7 a fine-textured intrusion (aplite) similar to a dyke was found. On the south side of that intrusion, the rock became very coarse indeed. The rock in block 3S was very decomposed, as was shown by the large amount of chlorite present, and a $1\frac{1}{4}$ -inch vertical clay seam had been found running east and west at the main fault in block 3S, whilst in block 3S ice-markings were clearly seen running north-north-east and south-south-west about 20 feet south of expansion-joint 4/5. Beautiful and unusual crystals of calcite had been found intruded into the granite, which from their appearance had not come in from above, but had been obtained from below. Near the same

ne a band of schist and an acid felsite had been intruded into the Mr. Gullan. granite at a later phase.

The setting out of the dam had been carried out using as co-ordinates two main base-lines, one 75 feet north of, and the other 75 feet south of, and parallel to, the chord-line. At every 30 feet painage- and bench-marks had been established.

The physical and geological conditions of the Spean valley would suggest the final position chosen, but he disagreed with the Author in the advisability of sinking trial-pits in the bed of the river. When the ice of the glacial epoch had receded it would naturally take the easiest path and would remove all the loose rock, but at the same time it would leave the top surface greatly marked and shattered, which was what had been found, and it was not uncommon to find at such a section a fault which meant deep-lying rock relative to ground-level. That had been the case at Laggan, and a similar condition had been found during the construction of the Silent Valley reservoir.¹ He felt sure that had accurate rock-levels been available before commencing the work a great deal of money and anxiety might have been saved. The position of the cofferdams could certainly have been selected more favourably, and the heavy excavation in block 5S, in some places to a depth of 50 feet, might have been avoided.

By fixing the position of the outfall at a point near the north end of Loch Treig, and joining up to the tunnel at adit B, a rock outcrop could have been used without any fear of scour. That would have lengthened the tunnel, but it would have done away with any soft tunnel and costly outfall work, especially when it had been found necessary to prevent serious erosion, with the possibility of undercutting Treig dam and the railway embankment.

Had the granite pitching at the toe of the dam been found satisfactory? The limits of the pitching had been governed by the original idea of fitting spillway-gates in the centre-section of the dam. The rough-dressed pitching, 18 inches deep, was laid in "contour" courses with 2 : 1 cement mortar with maximum of 1-inch joints, and the courses had a minimum width of 9 inches and a minimum length to break bond of 6 inches. The piece-work rate for laying was 7s. 6d. per square yard on the horizontal, and 8s. 6d. per square yard on the slope, the dressing cost having been 2s. 6d. per cubic foot. It had been decided to build the pitching with the concrete, but that had been found to be impracticable, and a small part had been tried

¹ G. McIlldowie, "The Construction of the Silent Valley Reservoir, Belfast Water-Supply." Minutes of Proceedings Inst. C.E., vol. 239 (1934-35, Part I), 465.

Mr. Gullan.

out by building up random rubble wedge-shaped walls in 4 : 1 cement-mortar to take the pitching. That method had also been found to be too difficult, and finally the concrete had been finished off at 2 feet from the surface. To safeguard against the possibility of dislodging the stones, steel dowels $1\frac{1}{4}$ inch in diameter and 3 feet long had been grouted in at 3-foot centres.

The equipment in Laggan quarry had consisted of one 30-inch by 16-inch slogger and two 25-inch by 12-inch Broadbent crushers having a maximum output of 20 cubic yards of 2-inch aggregate per hour, and an average output of 15 cubic yards per hour. In general 14-foot vertical holes and 60 per cent. low-freezing gelignite were used, giving an output of 2.4 cubic yards of 2-inch aggregate per lb. of gelignite. The density of the plagioclase granite was 165 lb. per cubic foot. On the dam-excavation about 2 cubic yards were obtained per lb. of explosive.

The average hourly working-output of each crane had been 10 cubic yards of placed concrete over 9 weeks during the busiest concreting period. The concrete-mixing plant had consisted of two 2-cubic yard "Victoria" Stothert & Pitt mixers, and a 67-cubic foot Henderson bottom-opening skip had been used throughout with satisfaction. In order to speed up the work, the monotower crane had been fitted with an additional high-speed gear, the hoisting speed having been increased from 110 feet per minute to 178 feet per minute which meant a decrease in load from 7 tons to $3\frac{1}{2}$ tons on high gear at 80 feet radius. Based on the average output, the following were the labour-costs per cubic yard :

Quarry	1s. 10d.
Ropeway	4d.
Mixing	9d.
Placing	11d.

The Ransome diesel-electric drag-lines were of types 460 and 480. Type 480 gave an average output of 20 cubic yards per hour, giving a labour-cost of $5\frac{1}{4}$ d. per cubic yard. The 145-B.H.P. sand-pump had an average output of 7.5 cubic yards per hour, giving a labour-cost of 8d. per cubic yard. A 110-hour week was worked in two shifts.

Had it been found necessary to keep the channel dredged, especially at the extension-end, where it had been almost impossible to maintain the slopes? The grey-clay slopes referred to at the top of p. 8 § had an angle of repose of just over $2\frac{1}{2}$ to 1.

The Author, on p. 29 §, gave the water/cement ratios of 7 :

§ Page numbers so marked refer to the Paper. (Journal Inst. C.E., vol. (1936-37) (February, 1937).)—ACTING SEC. INST. C.E.

concrete and 4 : 1 concrete as 0.55 and 0.4 by weight respectively. Mr. Gullan. Those figures seemed to be high, and 0.3 and 0.2 respectively would appear to be more nearly correct.

Mr. J. W. MEARES asked, in connexion with the considerable Mr. Meares. amount of water lost over the spillway of Laggan dam, whether the possibility of utilizing Lochan na H-Earba had been considered. The plan in the Paper (Fig. 1, Plate 1) was not concerned with that small loch, and did not show either its marginal contours or its elevation. It was, however, so close to loch Laggan that its elevation above the latter was likely to be small. If that was so, and the tanks would give a large waterspread with increased depth, it appeared that it might be dammed to give a considerable amount of supplementary storage, which could be filled by direct electrical pumping from loch Laggan in time of excess and used in times of defect. Whatever the elevation of that reservoir might be, it was certain that the lift would bear a very small proportion to the head available at the power-house. When dealing with such large quantities, it was probably impracticable to use any form of automatic water-lift, such as the ram or the "Hydrautomat," though the latter had been used in irrigation-canals in India. It became mainly a question, not of engineering, but of capital charges and working expenses, and of whether the extra kilowatt-hours stored in the upper loch were worth while. The principle of main or subsidiary storage pumped to elevated reservoirs was already in use in many places.

Mr. T. W. MORAN considered, with regard to the occurrence of Mr. Moran. permeable cracks due to shrinkage and temperature-stresses, that it was possible that a suitable use of gunite on the upstream face of Laggan dam might simplify the treatment of the problem, provided that the gunite was carefully designed so as to fulfil its required functions beyond all possibility of doubt. The conditions to be dealt with in the case of a dam designed and constructed in a similar manner to the Laggan dam were :

- (1) *The initial shrinkage due to drying out and cooling.* That shrinkage would be a maximum in the upper part of the dam, where most of it would be accommodated by the radial joints at 45-foot intervals. In the middle and lower levels, however, intermediate cracks were likely to occur between the radial joints, since the tensile strength of the concrete would not be adequate to cope with the distortion of the blocks due to the marked difference in temperature between the face and the hearting.
- (2) *Seasonal temperature-movements.* Such movements would be greater in the upper part of the dam than in the lower, and greater at the face than in the hearting. Both

Mr. Moran.

the radial joints and the shrinkage-cracks would give relief to the stresses. The Author and several speakers had referred to the possibility of dispensing with a facing of 12 inches of rich concrete. That would certainly help to reduce the facial cracking. If watertightness were to be the criterion, it would appear that the best place for the rich mix would be as a core in the middle thickness of the dam. However, as none of the shrinkage cracks appeared to penetrate as much as 11 feet from the face, it would seem, from that and from other data given by the Author, that the dam would be perfectly watertight if the rich facing were dispensed with altogether.

The functions to be fulfilled by a gunite facing were therefore :

- (1) Sealing the radial joints and shrinkage cracks on the upstream face, in order to prevent percolation and progressive disintegration due to the dilute acids of moorland water.
- (2) Sealing the surface pores of the concrete.
- (3) Sealing the horizontal construction-joints. The Author could not say whether any trouble had been experienced with percolation through those joints in the case of the Laggan dam, but judging by observations elsewhere, the horizontal joints were more likely to permit leakage than the vertical joints, owing to the difficulty of forming a dense mixture at the bottom of each lift.
- (4) Providing a protective face to resist wave-action and slow disintegration from frost between top and low water level.

If the gunite facing were to fulfil those requirements adequately it was clear that it should not fail by reason of (a) uncontrolled cracking in line with the contraction-joints and shrinkage-cracks in the dam, and (b) uncontrolled cracking due to shrinkage and temperature-stresses in the gunite itself. It was important to remember that the critical period was that which elapsed between construction and filling with water. Once the reservoir filled, temperature variations would be greatly reduced ; furthermore, the gunite, and the concrete behind, would tend to increase in volume by absorbing water and thus would partially close the contraction-joints and shrinkage-cracks. It would be of interest to know if that had been observed at Laggan dam.

The first step was to select a suitable gunite mixture with a view to minimizing shrinkage. On the Laggan dam a 3 : 1 (dry) mix had

en used, which probably yielded a finished mix of about 2 : 1, Mr. Moran. d was much richer than the face-concrete. There was a strong *prima facie* case for using a much leaner mix, as near as possible to that of the face concrete ; it was quite probable that such a mixture could be equally as watertight as the 2 : 1 (finished) mix because the percentage of rebounding sand would be increased, and the particles imposing the finished mix would have been punned home all the more thoroughly. An increased working-pressure would assist in curing that result. A further point was that the gunite would be greatly improved if some fine chippings were employed, as that would help to minimize shrinkage. He suggested that the finished proportions to be aimed at should be 3 : 1 or $3\frac{1}{2}$: 1. The dry gauging required to produce such a mixture would depend *inter alia* upon the fineness-modulus and water-content of the aggregate, and on the working pressure, but would be somewhere about $4\frac{1}{2}$: 1 or 5 : 1. The proportion of chippings should be about 20 per cent. of the total aggregate, and the size from $\frac{3}{8}$ inch to $\frac{1}{2}$ inch, or $\frac{1}{4}$ inch to $\frac{1}{2}$ inch screenings. The admixture of chippings would give a much rougher surface-texture to the gunite than if sand only were used ; but that was of no importance when compared with the superior qualities obtained.

The next consideration was that of shrinkage and temperature-stresses in the gunite itself. There was little hope of being able to provide (economically) enough steel to cover the stresses without allowing cracks, and the reinforcement should therefore be designed for the sole purpose of controlling the cracks and distributing them evenly. Tensile tests on slabs of reinforced gunite showed that the gunite cracked in tension at each of the transverse wires ; hence if a light fabric of, say, 6-inch mesh were used the result would be a large number of very minute cracks at 6-inch centres. Alternate-bay construction might also be adopted with advantage.

Another possible method of minimizing the size of individual cracks in the gunite would be to dispose the steel fabric in fairly small sheets, for example about 7 feet square, with a 2-inch gap between adjacent sheets instead of the usual laps. That would produce fine cracks at 7-foot intervals, thus relieving the tensile stresses, and ensuring that the latter should not become sufficient to overcome the adhesion to the concrete. A detail which would require investigation was whether to break the joints in the perpend in the horizontal edges of the sheets. It would probably be best to keep the perpend in line, parallel to the joints in the concrete. The whole proposal was a reversal of existing practice, but it appeared to be perfectly logical, and merited consideration.

It was of the utmost importance that the adhesion should always

Mr. Moran.


remain as perfect as possible. To that end, the surface of the concrete should be roughened with shallow hacks close together, or alternatively the surface might be stripped after applying an aggregate-exposer on the shuttering. Sand-blasting with the cement-gun itself was of very little value for that purpose, as the stripping effect obtained was negligible. The surface of the concrete should be thoroughly drenched with a water-jet for some time before the gunite was applied, and every effort should be made to keep the gunite continually moistened with a fine spray for about a week after application.

A $1\frac{1}{2}$ -inch layer should provide adequate watertightness under a head of 180 feet of water, but if the reinforcement were to be situated in the best position, namely, at mid-thickness, the cover on the water face would be slightly less than $\frac{3}{4}$ inch, which was too small for safety. A 2-inch thickness of gunite would be preferable, as giving about 1-inch cover to the steel at the centre of the layer.

It appeared that there was not very much danger of cracks occurring in the concrete along the horizontal construction-joints, so that the main object was to secure watertightness across them. The reinforcing fabric of the gunite should therefore be so disposed as to lap over the horizontal joint-planes. If individual cases were found where cracks had formed, they could be dealt with in the same way as described below for vertical joints.

With regard to the vertical joint-planes and shrinkage-cracks the use of gunite could be so arranged as to dispense with the necessity for placing the radial contraction-joints in the concrete closer together than 45 feet. That would be done by postponing the application of gunite to the latest possible date so as to allow as long as possible for shrinkage-cracks to develop on the face-concrete. Joints of a suitable pattern would be provided in the gunite in front of them. He was interested in the type of contraction-joint described on p. 30 §. He had frequently had occasion to consider methods of bridging contraction-cracks with a layer of reinforced gunite, but although the tensile strength of 3:1 (dry mix) gunite was at least 500 lbs. per square inch it was difficult to see how pronounced cracking could be avoided in a joint of the type described. He had experimented with buckled copper strips, but it was an awkward matter to place a joint of that description in a thin layer of gunite. If inaccurately fixed, the gunite tended to crack in line with the edge of the strip, and the joint became useless. A method which he had adopted in lining service-reservoirs was based on arranging that the gunite would crack in line with the

crack in the concrete. A chase was cut in the concrete $1\frac{1}{2}$ inch wide Mr. Moran. and 2 inches deep, and filled with bitumastic putty, which was left projecting about $\frac{3}{4}$ inch proud of the concrete. The gunite reinforcement was cut and hooked opposite the chase (*Fig. 29*). That arrangement controlled the alignment of the crack in the gunite, and the water-pressure was used to press the putty more firmly home. That type of joint was made very quickly, it cost little, and it had proved effective. Joints of that type should be sited in line with every contraction-joint and shrinkage-crack. It would be of interest to hear whether a functional use of gunite on the lines indicated above would have simplified the problems met with in the design and construction of the Laggan dam.

Fig. 29.

Mr. J. H. WALKER considered that one of the interesting problems Mr. J. H. Walker. in the construction of concrete dams, whether of the gravity type or of the arch form, was that of the prevention of permeable shrinkage-cracks. The Author mentioned several methods of mitigating the trouble resulting from shrinkage-cracks, and stated that the problem ceased to exist if the dam were built up of pre-cast blocks. The latter opinion was shared by several who took part in the discussion in the Paper. It was worth while considering a further alternative solution, for the full appreciation of which it was desirable to have in mind the following facts :—

- (1) Concrete, unrestrained in setting and hardening, would shrink 1 inch or more in a length of 100 feet.
- (2) Concrete, subjected to a rise in temperature of 150° F., would expand 1 inch in a length of 100 feet; that shrinkage was far in excess of any probable expansion due to normal rises in temperature.
- (3) Shrinkage of concrete was observable within 36 hours of casting, and consequently the shrinkage took place before the concrete had attained sufficient tensile strength to resist shrinkage stresses imposed upon it, perhaps by a solitary large stone displacer, or by a step in the foundation.

Mr. J. H.
Walker.


- (4) Dock-walls 20 feet wide at the base and made of 8 : 1 concrete, had developed vertical cracks about $\frac{3}{8}$ inch wide, spaced at distances apart of from 60 to 80 feet. Those cracks were observable before the dock was finished and filled with water.
- (5) In dock-walls made with a sufficiently large number of stone displacers, as in the case of docks constructed by the Mersey Docks and Harbour Board, vertical cracks were not apparent.
- (6) A large slab of concrete 8 inches thick, cast on a rough sub-base, would warp up at the edges off the sub-base. Eventually the expansion and contraction, due to varying weather-conditions, would cause it to crack across the centre and attempt to re-bed itself.
- (7) If the above slab had been buried in it, below the surface, a layer of rigid circular swaged steel hoops, each laid flat and touching one another, and each hoop 20 inches diameter by 2 inches deep by 18 S.W.G., the slab would not warp at the edges. Each hoop, as the concrete encircled it, set and hardened, would become a solid displacer; consequently the upper part of the slab could not contract in length and breadth; the result would be that the concrete, instead of shrinking bodily to the centre of its mass, would shrink locally and become permeated with fine, invisible cracks. In other words, the concrete would be "crack-controlled."

Accepting the above statements as correct, it was easy to apply the displacer-theory to large dams, where the mass-concrete was brought up in lifts of 3 feet 6 inches.

He would suppose that in the surface of each lift a layer 12 inches deep of large stone displacers, or pre-moulded concrete slabs, were inserted each stone half in and half out of the wet concrete, and each jammed up against its neighbour (*Fig. 30*). Obviously such a layer could not shrink in length and width. The concrete imprisoned between two such layers, one above and one below, was, however, bound to shrink in setting. The inevitable result would be that the concrete, shrinking while it was weak in tensile strength, would develop minute vertical cracks, or vertical cleavage planes, such as occurred in stratified rocks similarly imprisoned. That procedure might or might not be practicable, as firstly a ample supply of displacers would be requisite, and secondly it might be difficult to locate them in such stratified layers.

If, however, instead of stone displacers, swaged steel hoops were

Fig. 30.

Mr. J. H.
Walker.PART-SECTION THROUGH CONCRETE WALL CRACK-CONTROLLED BY
MEANS OF LAYERS OF STONE DISPLACERS.

used, say 3 feet in diameter by 9 inches deep, made of No. 20 S.W.G. steel, the procedure would be simplified, as such rings could be laid flat and touching one another, half in and half out of the surface of each 3 foot 6 inch-lift (*Fig. 31*).¹

Fig. 31.

PART-SECTION THROUGH CONCRETE WALL CRACK-CONTROLLED BY
MEANS OF LAYERS OF SWAGED STEEL HOOPS.

It would be obvious from the study of *Fig. 31* that by introducing layers of hoops in the mass concrete as shown, the concrete has been forced to form for itself layers of solid concrete displacers, each

¹ Since writing the above, it had been ascertained that the dock-walls of the King's Dock, Swansea, built about 1910, had been brought up in lifts as shown in *Fig. 30*. The plums, however, had been spaced not less than 6 inches apart. So far as could be seen above water-level, there were none of the cracks so observable in dock-walls built of mass-concrete without plums.—J. H. W.

Mr. J. H.
Walker.

surrounded by the steel sheeting, which could not be pressed out of shape on account of the weak tensile strength of the concrete at the time it was thus "crack-controlled." Such control resulted in the formation of minute invisible vertical cracks or planes of cleavage (they might also be termed planes of tension), the distance apart of which it was possible to estimate if the relative strengths of the concrete in direct shear and tension were known. For instance, assuming that the tensile strength f_t was one-third of the shear strength f_s , then, referring to *Fig. 31*,

$$(AB + CD)f_s = (33 \text{ inches}) \times f_t$$

That was,
$$xf_s = (33 \text{ inches}) \times \frac{f_s}{3}$$

Whence
$$x = 11 \text{ inches}$$

If the total shrinkage of the concrete were 1 inch in 100 feet, the width of an induced crack would be approximately $\frac{1}{1200} = 0.009$ inch.

Mr. C. A. Hogentogler, Senior Highway Engineer of the Bureau of Public Roads, Washington, U.S.A., referring to concrete road-slabs cast on a rough sub-base, had stated that the shrinkage-cracks initiated by the adherence of the underside of the slab to the ground occurred before the tensile strength of the concrete was 20 lbs. per square inch. If that were correct, the compressive stress in the steel of the embedded circular hoops did not exceed $16\frac{1}{2}$ tons per square inch. Considering that the steel could not buckle or otherwise evade the stress, the hoops should function even if that stress were greatly exceeded. Mr. James Williamson in a Paper¹ had mentioned the difficulty of maintaining watertightness at the horizontal joints between successive lifts. It would be seen from *Fig. 31* that the upper parts of the hoops, projecting upwards into the layer above, effectively bonded the two layers together and prevented percolation along the joint.

If it were desired to dissipate the heat of the concrete in each lift, the basins formed by the upstanding hoops could be filled with water, which could be left standing for a week or more without delay to the work, provided that the concrete of each lift be pumped or otherwise laid in continuous layers, from one end of the dam to the other. That method was a reversion to the old English practice and differed entirely from the skyscraper method often employed.

Assuming that each steel hoop, weighing $11\frac{1}{2}$ lbs., crack-controlled $1\frac{1}{2}$ cubic yards of concrete, there would then be 10 lbs. of steel to a cubic yard. Estimating hoops in place at £18 13s. 4d. per ton, or 2d. per lb., the additional cost for hoops would be 1s. 8d. per cubic yard of concrete. Part of the extra cost might be off-set by the use

¹ Second Congress on Large Dams, Washington, 1936.

of stone displacers in the intervening layers of concrete. Such a small addition to the cost of the mass concrete might be warranted, not only in the construction of dams, but also in the many instances of foundations and walls for docks, harbours, etc. where the elimination of unauthorized permeable cracks was desired.

It might be useful to consider the possibility of crack-control of mass-concrete by means of, say, 0.25 per cent. of longitudinal bar-steel and a similar amount of transverse steel. To do that would necessitate the use of $2\frac{1}{2}$ lbs. of steel per cubic foot of concrete, or $87\frac{1}{2}$ lbs. per cubic yard. The cost of that would be 11s. 3d. per cubic yard, which was far too high to warrant any serious consideration of the use of bar-steel for the purpose of crack-controlling mass-concrete, even if it were successful in doing so, which was doubtful.

Casting the concrete in alternating blocks, and thus pre-forming the joints, or burying thin slab-sheets in it to form induced joints, was only a partial control of shrinkage, and the opening and closing of joints thus formed had to be made watertight by copper strips or by other means.

An interesting feature of the Laggan dam was the facing of the 7:1 concrete with an outer layer of 4:1 concrete, the latter being made with a small-sized aggregate, consisting of stones 1 inch and downwards. As a further precaution against percolation of water, the 4:1 concrete facing was itself faced with a still more richly mixed reinforced-concrete coating of gunite, using aggregate of $\frac{1}{4}$ inch and downwards. Such elaborate precautions suggested that the method of facing the dam could be much simplified, if only for the reason that the correct solution of any problem was usually very simple. The experience gained in the construction of concrete roads might help, as their surfaces were not only subjected to the wear and tear of traffic, but also to extremes of weather-conditions.

Concrete roadways had been made in Edinburgh in 1873, for one of which, $\frac{1}{4}$ mile long, the maintenance costs over a period of more than 60 years had been less than £50. Those road-crusts were 6 inches thick and were without reinforcement, the bottom 3 inches being ballast-concrete with the top 3 inches macadam concrete, the aggregate of the latter being largely of sizes from 2 inches to 4 inches, which to-day showed as a large-sized mosaic. Those examples of excellent concrete roadways had been forgotten, and when some 40 years later interest in concrete-road construction had been revived, the roads were formed of large rigid slabs up to 15 inches thick, laid on brown paper, etc., and reinforced with 21 lbs. of steel per square yard, such slabs having coarse aggregate in the base and finer aggregate in the surface concrete. One of the faults of such slabs was that they warped upwards at the edges, and gave bad running

Mr. J. H.
Walker.

Mr. J. H.
Walker.

over the joints, so that sooner or later, they had to be tar-carpeted. About 15 years ago the Edinburgh example had been unknowingly followed, as the reinforcement had been omitted as costly and unnecessary, with the result that there were many miles to-day of such roads in excellent condition, which being devoid of warp, gave most satisfactory running to motor vehicles. The only departure from the Edinburgh system were that the lower part of the slab was from 4 to 6 inches thick, and contained the usual aggregate of 1½ inch and downwards, whilst the surface coat was mainly of 2½-inch broken granite.

The success of such a simple form of construction might be sought in the facts that concretes rich in cement, and concretes made with small aggregate, shrunk more than concretes weak in cement and made of large aggregate. Such surfacings of large-sized macadam-concrete might be readily conceived as a conglomeration of small plums or displacers, wherein each large stone was too deeply embedded to be hammered or sucked loose by iron- or pneumatic-tired vehicles; due, however, to such comparatively large aggregate, the concrete in shrinking not only yielded minutely around each stone, instead of developing large cracks widely spaced (that was to say, it was self-crack-controlled) but the surface concrete lacked strength to warp the edges of the slab off the road-base, with which it had to remain tightly in contact. The slab was freed from the beam and cantilever stresses inseparable from the warped and rigid, and therefore imperfectly bedded, reinforced slab.

A further feature, worthy of notice, was that the macadam-concrete surface, unlike small-aggregate concrete, gave perfect adherence to a brushed coat of dehydrated tar or bitumen, which was waterproof and to a certain extent, plastic. That experience might be applied to the facing of the Laggan dam, where the 7 : 1 concrete with 2-inch aggregate was faced with a richer mix of 4 : 1 concrete containing smaller aggregate, and the latter was faced with a still richer mix with still smaller aggregate; the principle of the successful concrete road might be used and the 7 : 1 concrete might be faced with a 6 : 1, or even a 7 : 1, mix of concrete, containing granite aggregate varying from 3 inches to 1½ inches, which could be brushed over with a coat of dehydrated tar. The latter should however, not be necessary, neither might it be æsthetically desirable. In support of that suggestion, it might be of interest to note that the Port of London Authority, previous to 1920, had faced new dock walls of 8 : 1 mass-concrete with a 6-inch thickness of 4 : 1 concrete containing small aggregate. Since then, they had increased the size of the aggregate in the facework to that of 2½-inch macadam which was the same size as in the surfacing of all their concrete

pads. The result was good, and moreover the rubbing of barges alongside the walls did less damage. Mr. J. H. Walker.

Mr. RONALD WALKER would like to make reference to the following wording at the top of p. 29 §: "The grading of the aggregates was analysed and compared with Fuller's maximum-density grading, but no attempt was made to separate out and proportion each grain-size of the material. . . ." He thought that it would be of interest to have a diagram showing: (a) what variation was obtained in the sieve-analyses of the aggregates, and (b) to what extent the ascertained limits of the sieve-analyses deviated from Fuller's maximum-density curve. Mr. Ronald Walker.

With regard to variations in sieve-analyses, the experiments carried out by Professor H. N. Walsh¹ showed that comparatively small variations called for increased cement to obtain the desired workability and strength. Assuming that the sieve-analyses of the aggregates had varied materially, he would further suggest that it would be of interest to have, in the form of a second diagram which could be compared with the first, information as to how densities and strengths had been affected by variations in sieve-analysis.

He would welcome the Author's observations on the following suggestion: with regard to the construction of large concrete structures for the retention of water, requirements would best be met by the use of aggregates conforming to such gradation-curves as would, in conjunction with the minimum contents of cement (preferably coarsely ground), result in workable concretes of maximum density, with minimum liability to be adversely affected by temperature-effects.

Applied in practice, the foregoing would mean, so far as the gradation of aggregates was concerned, that the ideal gradation-curves would be found by experiments, and plant (which was now available) would be employed to ensure that all aggregates used would constantly and reliably conform thereto.

Mr. G. BRANSBY WILLIAMS observed that British dams, until recently, had been chiefly notable for the cautious (he might almost say timid) lines on which they had been designed, and for their proportionately high cost. It had been claimed as a merit in Papers read before The Institution that the maximum stress-intensities in particular dams had been restricted to figures much below those which the material of which they were composed could safely withstand, and much time and labour had been expended in elaborating Mr. Williams.

§ *Ibid.*

¹ Bulletins of Inst. C.E. Ireland, May, 1933, and April, 1936.

Mr. Williams.

profiles which had been intended to ensure those uneconomic stresses and had been expected to obviate the possibility of tensile stresses in parts of the dams where tension could not occur. It had at length come to be generally realized that a plain triangular section was suitable for all gravity dams of sizes built, or likely to be built in Great Britain. The Laggan dam was, practically speaking, triangular, and its profile was safe and economical.

The Author mentioned that the alternative of an arch dam had been considered. He presumably meant a composite arch-and-gravity section dam; a single-arch dam would not have been suitable. He stated that, in the case of the Laggan dam, 700 feet had been found to be the limit beyond which there was no advantage in a dam of that type, and that the wisdom of longer arched dams was open to question in view of the lack of knowledge of the stresses set up by temperature-changes and shrinkage. That view did not seem to be shared by engineers in the United States, who had projected considerably longer dams of the arch-and-gravity type and who had apparently found those more economical than gravity dams. It was not easy to understand why a lack of knowledge of temperature and shrinkage-stresses should be more prejudicial in the case of dams consisting of arched centres and gravity approach-lengths, than in dams of the ordinary gravity type. It might be noted that the first suggestion for the construction of combined arch-and-gravity dams in Great Britain, seemed to have been made by Colonel J. Pennycuik, the builder of the Periyar dam, at a discussion on a Paper read before The Institution.¹ Until recently that suggestion had not been followed up, but the Galloway dams had shown its value.

It would be of interest to know whether the alternative of a multiple-arch dam had been considered for the Laggan dam. Such a dam would have been much cheaper, and objections to it, with the improved quality of cement concrete available to-day, were largely based on prejudice. A few years ago an Italian engineer, as a result of his experience of the multiple-arch dams that had been built in Italy, had stigmatized the masonry gravity dam as an "economic crime." His statement might perhaps be regarded as too sweeping but it was likely that those solid masses of material would be superseded in the future by lighter, more economical, and more scientific forms of construction. There was little doubt that in many places where masonry dams up to 200 feet high had been built, or proposed

¹ L. A. B. Wade, "Concrete and Masonry Dam-construction in New South Wales." Minutes of Proceedings Inst. C.E., vol. clxxviii (1908-1909, Part IV), p. 1.

multiple-arch dams would have been quite satisfactory and much cheaper than gravity dams.

The Author had suggested the possibility of having an all-siphon spillway. The objection to a spillway of that type was its lack of elasticity. The Committee of The Institution on Floods in Relation to Reservoir Practice had recommended that the design of spillways should be based on the discharge during a probable maximum flood, and that what were termed "catastrophic" floods should be provided for by a margin above the anticipated flood-water level in the reservoir, within which the water could rise if necessary.¹ That seemed to be the common-sense method of dealing with the problem, and in the case of an ordinary spillway the rise necessary to discharge twice the probable maximum flood-flow would usually not be excessive. If, however, an all-siphon spillway were in use which had been designed on the same basis, a catastrophic flood would completely overwhelm it and a major disaster might result.

It could not be said that the estimated flood-discharges in the Lochaber scheme erred on the safe side. It seemed rather misleading to state the run-offs in terms of inches per day, for the periods of concentration were generally less than 24 hours, and on the Treig catchment they were very much less. According to figures Mr. Williams had adopted for that type of catchment, the probable maximum flood-discharge from the Treig catchment would be about $\frac{1}{2}$ inch per hour, and from the Laggan catchment $\frac{1}{8}$ inch per hour. In a "catastrophic" flood those figures might be considerably higher. At all events it would hardly be denied that such rates of discharge were physically possible, and in a work of the type under consideration any flood even remotely possible was a contingency to be reckoned with.

The Treig dam was a combination of a rock-fill and an earth-fill dam, somewhat similar to some dams constructed in America, and was of a type which, so far as he knew, had not previously been constructed in Great Britain. It would be interesting to know on what basis the thickness of the reinforced-concrete corewall had been determined. In most dams where such corewalls had been used, their thickness had been decided by what had been found satisfactory in other similar dams. Efforts had been made to arrive at the correct thickness by calculation, but they had not been very successful, and had obviously started from faulty premises.

The information regarding the temperature-rises was interesting, and would be valuable for future reference in connexion with other dams. The length of time required for the dispersal of the heat

¹ Interim Report, Inst. C.E., 1933.

Mr. Williams. produced by the setting of the cement in a comparatively small dam, illustrated the necessity for the artificial cooling-devices which have been adopted for a dam of the size of the Boulder dam.

The agreement between the calculated and measured deflexion was as close as could be expected, when allowance was made for the uncertainty regarding some of the assumptions on which the former were based. The Author suggested that the method of ascertaining deflexion described in the Paper was justified by the assurance of safety obtained from it; it hardly seemed that any such assurance was required in the case of a dam designed and constructed by the methods employed for the Laggan dam. The failure of that dam during the next few hundred years seemed unlikely, unless caused by some cataclysm of nature. If such were to occur, the information obtained from measuring the deflexion under normal water-loads would not be of much help in averting the disaster.

The Author.

The AUTHOR, in reply, observed that since the construction of the works no maintenance had been necessary in the dredged channels from loch Laggan.

Mr. Meares had suggested the damming of Lochan na H-Earraig to give supplementary storage and thus to reduce flood-loss. The difference of level was over 300 feet and it would be quite uneconomical to pump to such a supplementary reservoir. It would, however, be possible to regulate the gravity flow therefrom so as to render the extra storage effective. The small amount of additional power would probably be more than counterbalanced by the capital expenditure involved.

Mr. Williams' remarks appeared to imply that insufficient provision had been made for flood-discharge. In the Discussion Mr. Gourley had dealt with that point at some length, and the Author's reply thereto (p. 81§) covered the present criticisms. It was interesting to contrast Mr. Williams' implication that flood-conditions at Treig dam were particularly underestimated with Mr. Gourley's opinion that, while there might be some doubt in the case of the Laggan dam, there was an ample margin at Treig dam.

The Author was in full agreement concerning the danger attending the use of an all-siphon spillway of insufficient capacity, and he had elsewhere emphasized that very point. Such a spillway should, in his opinion, have sufficient capacity to provide a considerable margin beyond a "catastrophic" flood, but that surely did not necessarily mean that an all-siphon spillway should be ruled out of consideration.

In the preliminary designs both single-arch and composite are

and-gravity dams had been considered. When the sides of the valley were steep the advantage of the latter type was largely offset by the longitudinal yield of the gravity-section abutments. The Author agreed that arch dams of greater length and less than gravity section might be constructed without much danger of actual failure, provided that cracking and high stresses could be regarded with unanimity. He did not suggest that a lack of knowledge of temperature and shrinkage stresses was more prejudicial in the case of arch dams, but rather that in view of that uncertainty it might be unwise to adopt a section less than was given by a gravity design. The multiple-arch type was not suitable for an overflow dam. The Author did not agree that such a type would have been much cheaper. It was doubtful whether, in such a V-shaped valley where the section of maximum depth was short, either the multiple-arch or the Ambursen type would show any economy.

Mr. Gullan considered that a trial pit should have been put down on the bed of the river at Laggan dam. The rock-levels were not very different from those anticipated. Even had such a pit shown the lowest point of the rock-surface to be at a considerably greater depth the location of the dam would not have been affected, and the difficulty of sinking such a pit would have been commensurate with any saving that might have been effected in connexion with the cofferdams. The Author did not understand the reference to the heavy excavation in block 5S, since that had been dictated solely by the level of the sound rock.

The Author agreed with Mr. Ronald Walker that information relating variation of strength to variation of sieve-analysis would be of interest. Since strength depended more upon water/cement ratio than upon grading, very accurate control of the former was essential before conclusions could be drawn concerning the effect of grading. That had not been practicable owing to variation in moisture-content of the aggregates and the difficulty of accurately measuring the added water. Attention had been directed to the approximate maintenance of a grading known to be satisfactory, and had not been feasible to conduct a research into the effect of departures from that grading. The high densities consistently maintained were evidence of the successful results obtained. The suggestion for optimum grading appeared to the Author to be somewhat platitudinous in form. The question of coarsely- versus finely-ground cement was still open, the slower evolution of heat with coarsely-ground cement being offset by improved workability with finely-ground cement. The suggestion omitted all mention of water/cement ratio, upon which the strength so largely depended, and it would allow a concrete in which the cement was replaced by

The Author.

finely-ground sand. The water/cement ratios given were approximately in that an estimate had been made of the water-content of the coarse aggregate. The figures suggested by Mr. Gullan, namely 0.3 and 0.2, were impossibly low even for concrete vibrated in the laboratory.

Several different views had been expressed on the question of cracking in dams. Mr. Gates thought the importance of the matter to be overrated and special construction to be unnecessary. The value of gunite he considered doubtful, but Mr. Moran favoured its use. Mr. Walker favoured a dam permeated with cracks. The cracking was not experienced to any great extent in many old dams was explained by their slow speed of construction, which allowed adequate dissipation of internal heat. Such a policy was not now economically practicable. There was abundant evidence that cracking might cause unsightly seepage, and with moorland water progressive deterioration of the concrete might ensue. The Author understood that no leakage had been observed on the downstream face of Laggan dam. He did not feel competent to comment on the interesting suggestions put forward by Mr. Moran for possible improvement of the gunite mix and mode of application. It was of interest to note that gunite cracked, as would be expected, opposite the cross-reinforcement. That was a satisfactory result as far as protection of cracks in the dam was concerned, as it was extremely unlikely that those hair-cracks would coincide with the cracks on the face of the dam. Except where separated from the concrete of the dam by a slipping layer, the gunite was bound to contract and expand with the concrete and the percentage of reinforcement was of little moment, so that there would appear to be no advantage in forming it in 7-foot squares as suggested. At contraction-joints where sealing had been effected by a joggled copper strip the tendency for cracking of the gunite opposite the edges of the stone was minimized by a local thickening of the gunite cover.

Mr. J. H. Walker advocated the avoidance of obvious cracking and the minimization of contraction by ensuring the formation of innumerable hair-cracks. His suggestion of steel hoops had been embedded in the surface of a lift apparently killed three birds with one stone—controlling cracking, ensuring proper curing and forming an excellent bond with the next lift. As applied to roads and other situations where structural strength was not of great importance there was no doubt much to be said for his principles. Applied to a dam, the Author considered it would be a mistaken policy. Once a hair-crack had formed there was a tendency for it to develop owing to the concentration of stress at its growing tip. Mr. Walker's construction would tend to cause a dam to crystallize out into

columnar structure like basalt, and the strength of the dam would be gravely impaired. The use of layers of stone displacers in contact was not so objectionable from that point of view, but there were practical difficulties. With the low water/cement ratio desirable for dam-work it was not possible to bed displacers satisfactorily without allowing a fair space between adjacent stones and without a considerable expenditure of time and energy.

It was difficult to see how the use of a lean upstream facing with large aggregate could prevent the formation of definite vertical cracks due to the thermal expansion of the heart of a block. Such a facing might contract less if allowed to dry out, but contraction could in any case be prevented by keeping the face damp until the dam was filled. A crack-controlled facing as suggested would, in the Author's opinion, be more vulnerable to attack by aggressive ground water notwithstanding a coating of de-hydrated tar.

The granite pitching at Laggan dam extended over that part of the curved toe where the overflowing water had maximum velocity and turbulence. It was too soon by several centuries, he hoped, to assess its behaviour. It would be more correct to describe the earlier methods of constructing the pitching attempted as being sound and inconvenient rather than impracticable. The contractors had been allowed to lay the pitching afterwards, provided that adequate bonding was ensured by the use of steel dowels. There appeared to be no objection to that method since, as there would be no contraction due to setting- and drying-shrinkage in the layer of pitching, it could bear its due share of the stresses set up in the dam when full. The alternative location of the Laggan-Treig tunnel outfall in which Treig itself had been carefully considered. In the light of the information then available from borings that was the more expensive scheme.

Treig dam was functionally a rock-fill dam. There was little guidance as to the thickness of concrete corewalls. It had to be impervious and capable of resisting bending and shear stresses with the water-pressure acting down to the rock foundation. In the case of Treig dam, with two-thirds of the corewall below ground, the thickness had been determined from considerations of trench-depth, a minimum width of 6 feet having been maintained at the rock-surface in order to ensure the formation of a satisfactory key with the sound rock and room for dealing with influx of water during construction.

Paper No. 5076.¹

"Pre-Stressing Bridge Girders."

By HERBERT JOHN NICHOLS, B.Sc., M. Inst. C.E.

Correspondence.

Mr. Everall.

Mr. W. T. EVERALL observed that mention was made (p. 103) that the camber had been found to be reduced permanently by 0.42-inch, and that the reason for that was not altogether clear. It was found that the deformation-stresses showed little change in individual members, but that there was a substantial permanent set in all members, except the top chord. Was that permanent set accounted for by the slip in the rivets at the joints and connexions due to the loads applied immediately after and during the erection?

Considerable initial axial stresses were imposed by the pre-stressing, and slip in the rivets would occur in the reverse direction to the extent of that loading. He considered that the movements due to that slip were in addition to those caused by the application of the normal load, and that that would account for a large proportion of the 0.42-inch reduction in camber. The importance of refinement in the fabrication of the girders was stressed by the Author, and the details of the tolerances permitted, given in Table III (p. 115) were of considerable interest. The degree of accuracy and the limited tolerances under which the Nerbudda bridge girders had been manufactured were essential features, and had been largely responsible for the excellent results obtained from the pre-stressing method of erection employed on the bridge. Bridge-engineers in India and elsewhere owed much to the firm of Messrs. Braithwaite & Co. (Engineers), Ltd., and especially to the engineer, Mr. T. Douglas, for the way in which they had developed such a high standard of construction.

As the system adopted for obtaining girder-work suitable for pre-stressed conditions of erection might be of interest, he appended

¹ Journal Inst. C.E., vol. 5 (1936-37), p. 91 (February, 1937).

§ Page numbers so marked refer to the Paper.—ACTING SEC. INST. C.E.

the following notes on the jig-method of fabrication, as developed Mr. Everall, Mr. Douglas and used in India.

Notes on Jig-Methods of Fabrication.

- (1) To obtain the best results, both as regards workmanship, cost of production, and output, experience in England and India has proved that the system must be made as foolproof as possible. This applies not only to the actual making of jigs, but also to their application during all stages of the job.
- (2) Perfect workmanship is demanded by the development of pre-stressed bridge-work.
- (3) Jigs are to be made of steel, and fitted with case-hardened bushes.
- (4) Some notes on the making of jigs :—

(a) All setting-out is done by tape-measurement and by trammels, on the bench of a totally-enclosed jig-shop, in an even temperature.

No setting-out is done on the template-shop floor.

- (b) One tape only is used (having an N.P.L. test-certificate). It is fitted with a spring-balance tension handle, and all measurements are made with a pull of 10 lbs.
- (c) Standard drilling strips (bushed) are made in the fitting shop for all running pitches. These strips are applied to a minimum number of pilot-holes, previously marked off and drilled by sensitive drills, and checked by trammels and dividers.
- (d) Jigs are first made for all the small fittings, and these in turn are later applied to larger main-member jigs.
- (e) The maximum wear allowed in bushes is 0.008 inch, and jigs are tested daily with a "go and not go" gauge.
- (f) Groups of holes in web-members (connecting to main gussets) are located on a specially-designed surface-table, and drilled after the members have been completely shop-riveted. It is almost impossible to guarantee exact length-measurement and absolute squareness of holes in all sides by the use of tapes and by "squaring over" from one surface to another.
- (g) When chord-members have been fabricated in halves, these halves are assembled with the use of special cast diaphragms, machined all over, and drilled for insertion of turned bolts through the machined diaphragm-castings.
- (h) The maximum variation in any length-measurement and/or test of squareness after complete fabrication is plus or minus $\frac{1}{8}$ inch.
- (i) In ordinary bridge-work, strictly interchangeable joints can be made with turned bolts and parallel drifts with a maximum opening, measured over four corners, of 0.005 inch.
A special taper gauge and straight-edge is used at the milling machine, in conjunction with temporarily-inserted machined diaphragms, to prove the accuracy of milling.
- (j) In addition to the guarantee of squareness, length, etc., temporary machined diaphragms used for assembling

Mr. Everall.

ensure uniformity of width between webs of such built-up members.

- (5) Jig work has proved successful in England as regards quality of workmanship, and for economic reasons; in consequence (and in any country where skilled-labour wages are high) much of the work has been reduced to semi-skilled or unskilled labour standards.

In India, labour is cheap, and skilled labour is not so good or so plentiful as in England, but by the adoption of a foolproof jig-system the Indian workman can produce finished bridge-work equal in quality to that of any other country.

- (6) In the case of big repetition bridge-work such as Nerbudda, Jumna, Bally, etc., the process of marking-off and drilling to centre-points was eliminated entirely.
- (7) For the class of repetition-work referred to, the manufacturing costs are lower than for ordinary plated bridge-work, and the relative increase in output is not less than 25 per cent.
- (8) Other advantages of strictly interchangeable work are :—

(a) A system of marking, resulting in all identical pieces bearing one mark only regardless of the span to which they may belong. This permits easy reference throughout of all routine-work, and permits speedy handling of component parts during fabrication.

(b) Interchangeable work requires very much less stacking space both in the works and at site prior to erection.

Handling and sorting charges are thus reduced to an absolute minimum.

(c) Only in the case of "plated and match-marked" work is it necessary to paint each span a different colour. Interchangeable work renders this unnecessary, as well as the very costly and laborious process of "match-marking."

(d) Erection at site can be performed by reference to one or two fully-marked small-scale plans, and without any reference to numerous detail-drawings.

(e) Strictly interchangeable work produced by jig-methods gives the same degree of accuracy throughout, whereas, in plated (marked-off) work, the shop-riveted portions are inferior in workmanship to site-riveted connexions which have been reamed in position.

- (9) The design of jigs and their control, when being made, is usually entrusted to one man, and by means of special cross-checking of completed jigs, their accuracy can be assured before fabrication commences.

- (10) Modern jig-methods have made "shop-erection" unnecessary, and in recent cases where temporary erection of one span has been required, this has often been done during the closing stages of the contract; namely when from 50 to 75 per cent. of the whole tonnage has been delivered to the site.

- (11) When jigs for repetition work have been prepared and checked, perfect workmanship results from their distribution to and fabrication in any number of works; for example, Jumna bridge was fabricated in random parts (not in spans) at two works 1,100 miles apart.

This system has the very important advantage of halving the normal delivery of one works, as in the case of Jumna, simply because 50 per cent. of the steelwork was delivered from Bombay, and 50 per cent. from Calcutta. Mr. Everall.

(14) Some points to be observed during fabrication :—

- (a) *Clearances* are to be made as an allowance for the gathering of thicknesses, for the insertion of web-members between main gussets, and also end clearances in such members as cross-girders connecting into chord-members.
- (b) *Riveting.* A careful selection of riveting machines exerting pressures of 25 tons, 35 tons or 50 tons, according to the type of work being riveted, is very necessary.
- (c) *Service Bolts.* Use a liberal supply of service bolts and high-tensile parallel drifts during assembly of all work in the shops or at the site.
- (d) *Cooling-out after riveting.* To avoid distortion or permanent set in large members, pay special attention to the correct laying-out of members on level stallages, after shop-riveting.
- (e) *Distortion (during temporary erection).* In pre-stressed bridge-work, care must be taken if drifting is done; in the case of end rakers where the stress induced is fairly considerable, it is advisable to do this by means of union-screws and not by drifting.
- (f) *Span erection.* Wherever practicable it is advisable to erect in the following sequence :—
 - (i) Lay out the bottom chord, complete with the floor-system and all lower lateral bracing, on grillages which have been set dead level, completing all the chord-joints as the chord-erection proceeds.
 - (ii) Insert all the web-members.
 - (iii) Lower the camber-jacks to give the correct theoretical camber-ordinates.
 - (iv) Working alternately from the centre-line of the span towards each bearing end, erect the top chords together with the top laterals and/or the sway-bracing.
 - (v) Complete the top-chord joints as and when the adjacent pieces are placed together, finally closing the span (end rakers) at the bearing ends of the span.
- (g) *High-tensile steel.* Although its workability is almost equal to that of mild steel, it is advisable to drill high-tensile steel at a lower speed than that used for mild steel.
- (h) *Drills.* It is important to have drill-grinding done by a mechanic on an automatic drill-grinder; this results in accurate drilling, less wear on steel bushes, and gives increased life to the drills.
- (j) *Rivets.* They must be heated uniformly to the correct temperature, being careful to remove all scale before driving the rivet. Obtain uniformity in the dimensions of rivet-snaps.

Mr. Everall.

When driving close-pitch rivets in long members, drive "stitch" rivets first at 2-foot intervals, and then return to drive the remaining rivets.

The Author had made some valuable suggestions for modifying the design of floor-systems, with a view to eliminating cross- and stringer girders and timber sleepers, by adopting a transverse-trough floor. That, however, would mean that the metal required for the stringer girders would be transferred to the chords. Mr. Everall agreed that under that conversion the concentration of metal in the chords would increase the lateral stiffness of the bridge.

In attaching the running rails to the transverse troughing, he presumed that the rails would be welded in lengths equal to two spans, and that expansion and contraction would be allowed for by means of slip-joints situated at each end of the welded length of rail.

The Author might have some views on that matter, and it would also be of interest to know the saving in weight of metal, etc., which he hoped to obtain in adopting that type of bridge.

Mr. La Touche.

Mr. J. N. D. LA TOUCHE noted that the bases which had been used for the strain-gauges employed in the experiments had been 20 inches and 10 inches. He suggested that a base measuring $E/1,000$ inches would be preferable, as an extension or contraction of 0.001 inch then meant a stress of 1 ton per square inch. The stress in fact could be read direct without calculation. He had adopted that length for his own strain-gauge, taking the value of E at 13,000 tons per square inch, and the accuracy of the results had been proved in more than one testing-machine.

The effect of change of temperature on such measurements was of considerable importance. When applying tests to plate-girders in India with his strain-gauge, an attempt to obtain the maximum effect of a day's traffic had been made by leaving the gauge on the girder all day. His idea had been that the parts of the gauge would expand equally with the part under test, but it had been found that the girder expanded more than the gauge. The reason for that was, he thought, that the gauge had had a draught of air all around it and had not absorbed as much heat as the girder; the fact that the gauge had been of bright steel, whilst the girder had been black might also have had some effect. That difficulty might be avoided by taking observations at night.

He was glad to see that direct measurement had been added to calculation as a check on the security of the bridge; he had always advocated such a step.

Mr. Toms.

Mr. A. H. TOMS observed that the method of pre-stressing which had been advocated by the Consulting Engineers was theoretically

found, but as applied it had suffered from certain practical limitations Mr. Toms, which the Author had described. It would appear that in order to increase its effectiveness the following modifications were necessary :—

- (a) Chord-joints should be so arranged that they had adequate rigidity at the time when the chords were being brought to the desired camber.
- (b) Web-members should be brought into correct alignment at the joints by straining-devices rather than by drifting.
- (c) The accuracy of alignment should be checked by accurately-scribed marks on members and gussets.
- (d) Sub-members should be eliminated as far as possible, and the K-type truss adopted in cases in which the full panel-length of the unsubdivided N-girder would be uneconomically long for the floor-system.

The Author did not describe the procedure adopted for drifting members into position at the joints, but as many drifts as possible should be used at each joint consistent with adequate bolting, and in order to minimize distortion of holes they should be driven in strict rotation so that the shear due to moment on them would be distributed as evenly as possible. The procedure in removing drifts and riveting-up was equally important, the centre holes in a joint being filled first and the drifts in the outer holes retained as long as possible.

On p. 114 § the Author stated that an error of 0.010 inch in the length of a member 40 feet long would result in an undesired axial stress of 0.28 ton per square inch. That would be true if the member had to be forced into place in a perfectly rigid frame, but in normal cases the frame was flexible until the member was in place, and consequently the effect of such an error was negligible.

With regard to the use of Whittemore strain-gauges (mentioned on p. 99 §) it would be of interest if the Author could give further particulars of the instruments and the manner in which they were used, and also if he would state whether any trouble had been experienced from hand-effects.

The Author's proposals for using web-members with lacing in the plane of the trusses appeared to be unsound for the following reasons :—

- (a) In general it would be practically as difficult to drift up the end connexions of members as in the normal case, since the components of the member had not only to be bent

Mr. Toms.

but had also, in most cases, to be axially stressed by the drifting. For instance, in the case of a member bent in single curvature with equal and opposite moments at the two ends, the shear was everywhere zero, and consequently the lacing-bars were inoperative. The end rivet-groups would in that case still have to do all the work of pre-stressing exactly as in the original method. In the case of a member bent in double curvature it would certainly be easier to make the end connexions with the lacing loose, but when that had been done it would be found that the amounts of the strains by which the lacing-bars had to be drifted would be so small that they would be inadequate for the production of strain in the main section. The member would therefore be riveted up crooked but practically unstressed.

- (b) In view of the foregoing, in addition to fulfilling their normal functions, lacing systems in the plane of the truss would have to be capable of withstanding the shear forces corresponding to the deformation-moments.
- (c) Connexions would in general be less satisfactory from the point of view of design.

With regard to the device used for magnifying the axial deformations of the model-members, the Author stated (p. 134 §) that since the two components were rigidly attached at points *A* and *B* (*Fig. 27*, p. 133 §), a moment tending to bend the member would cause no movement in *DE*. That was only true provided that no relative rotation of the members *DE* could occur about the points *A* and *B*. If the only connexion at those points was by a single screw, then, unless held by friction, each of the two components would deform in the manner shown in *Fig. 30*, with consequent loss of rigidity in bending of the member as a whole.

On p. 108 § the Author stated that on the model itself it had been a simple matter to measure the deflexion-angles. It would be of interest if the Author would describe how that had been done, since the accurate estimation of the directions of the tangents to the members at joints would appear to be very difficult without the use of special tangent-indicators permanently fixed to the joints.


With regard to the Author's proposals for the reduction of floor-interaction stresses by the substitution of trough floor-plates supported by the chords in place of the normal floor-system, it should

be observed that, unless specially supported, that type of flooring Mr. Toms. would cause secondary stresses in all members due to :—

- (a) bending of the supporting chords as beams between the panel-points, and
- (b) torsion of the chords and transverse bending of the web-members due to the deflexion of the troughing and eccentric loading of the chords.

The Author's criticism of the method of calculating the stresses and strains in trusses on the principles of rigid-body statics, and his statement that the actual stresses in sub-members were reduced by the loads carried in bending by the chords to which they were

Fig. 30.



attached, were correct in the case of a truss erected in the ordinary way and not pre-stressed. However, in the case of a truss which was initially pre-stressed, the chords were deliberately bent to conform with the cambered profile, there being local deformations to suit the cambered lengths of the sub-members. If the pre-stressing were correctly carried out, then under the full load for which it was pre-stressed the chords of the truss would be perfectly straight. Consequently, under that load, no load would be taken by the chords in bending, and all members would be subjected to the full forces as calculated by rigid-body statics.

With reference to the economy of the use of steel-bushed jigs, experience in the erection of spans fabricated in that manner (and in which all similar parts were therefore interchangeable) had shown that, in bridges in which there were several similar spans or many similar parts, the time saved in fabrication and erection offset any extra cost of jigs. The question of the cost of jigs as an

Mr. Toms.

objection to pre-stressing was therefore ruled out in the case of such bridges.

The Author.

The AUTHOR, in reply, observed that it would be agreed that the notes on jig-methods of fabrication by Mr. Everall constituted a most valuable contribution to the subject under discussion. It was probably the first time that such information had been made available, and he would like to see it used as a basis for a specification controlling the manufacture of pre-stressed girders. He acknowledged the debt due to Mr. T. Douglas and to the firm of Messrs Braithwaite & Co. (Engineers) Ltd., for the development of that technique, which he considered to be as nearly perfect as it could well be made. He would like, however, to suggest that paragraph (14), *f(v)*, of those notes, which dealt with the joints in the top chord, should be amplified to cover the provision of temporary brackets to support the chord in a horizontal position while splices were being made. The case of deck-spans might also be considered. The maximum wear allowed in bushes was given in paragraph (4) (*e*) as 0.008 inch, which compared with the slightly more severe 0.007 inch given on p. 115. § The Author would like particularly to record his agreement with paragraph (14) (*j*) which stressed the importance of the uniform heating of rivets. In practice that was a most extraordinarily difficult thing to get done. There appeared to be something perverse in human nature which persistently made it heat the points of rivets more than the heads, and nothing short of a completely automatic heater would appear to be capable of overcoming that difficulty. He could endorse the statement made in paragraph (10). In the case of the Nerbudda bridge about 5,000 tons of steel had been fabricated before the first "trial" erection of a complete span was made, and that erection constituted span No. 16 in the bridge. Each span weighed about 680 tons.

With regard to the question of the loss of camber, which Mr. Everall had raised, it was recorded on p. 102 § that an initial loss of 0.11 inch had been measured when the span was carrying only a 120-ton locomotive which was caused to "slip." A further loss of camber of 0.42 inch occurred when the span was loaded with the full designed load. It appeared that top-chord-joint slip was the cause of both losses of camber, and that it therefore increased as the load increased. That appeared to preclude the possibility of slip occurring during and immediately after erection, as suggested by Mr. Everall. The initial stress imposed in members by pre-stressing had been everywhere of the same sign as that resulting from the application of a load, but as the load increased the stress would vanish and the

maximum primary stress in a given member was no more than that The Author.
 due to the designed load. It was possible that slip in the top chord had been due to the fact that when the chord-splices were being made, each section 35 feet 3 inches long was supported at the ends only and was in consequence sagging. The square butts could not therefore have been in perfect contact over the upper half of the section without drifting. The rivets in that region had therefore been closed with the two sections tending to move apart, and the direction of shear in them had been reversed when the compressive load had been applied to the chord. It was possible that that reversal might have accounted for the small amount of slip noticed. A splice in a tension-member would not be affected in the above manner.

The question of positioning the splices in the top chords away from the panel-points had already been referred to, and the change would tend to reduce the gaping of the square butts mentioned above. The use of straining devices to get the web-members correctly deformed had been mentioned again by Mr. Toms, but the difficulty of adequate supervision which that method involved ruled it out in the Author's opinion, except for special cases. A purchaser could never be sure of the extent to which they had been employed, and an alternative method which produced uniform results was far more satisfactory from that point of view. Mr. Toms' suggestion that the accuracy of alignment should be checked by scribed marks did not impress the Author. In the improbable event of inaccuracies of 0.001 inch or less being detected in that manner, Mr. Toms did not say how he would then proceed.

Mr. Toms gave three reasons why he did not favour the rotation of web-members as proposed in the Paper, but in stating his objections he had overlooked several important points. In the first place, dealing with members bent in simple curvature, he stated "... the components of the members had not only to be bent but had also, in most cases, to be axially stressed. . . . The end rivet-groups would . . . still have to do all the work of pre-stressing exactly as in the original method." That, of course, was not so. The type of deformation which was bound to occur was shown diagrammatically in Fig. 19, Plate 3 (following p. 160 §). In the case of a member 40 feet long and possessing a cross-section as shown in Fig. 18 (b) (p. 119 §), each flange possessed an $\frac{L}{r}$ ratio of about 140, and an Euler crippling load when straight of about 200 tons.

The Author.

The operation of pre-stressing to ± 2 tons per square inch by drifting might be considered in two parts, firstly the rotation of the ends to a slope of about $\tan^{-1} \frac{1}{340}$, bending the flanges to a circular curve and causing a centre versine of 0.35 inch, and secondly the imposition of axial stress in the flanges. A pre-stress of ± 2 tons per square inch would involve an axial load of about 65 tons in each flange if it retained its truly circular shape without deformation during the operation. It might be shown, however, that deformation was bound to take place, and such deformation operated to reduce the nominal axial load of 65 tons. A reduction of from 30 to 40 per cent. could be expected in the case of the members considered. That, however, was all that would be required, since as mentioned on p. 116 §, members bent in single curvature were in any case easier to deal with than were those bent in double curvature.


In connexion with members bent in double curvature Mr. Toms stated that "it would be found that the amounts of the strains by which the lacing-bars had to be drifted would be so small that they would be inadequate for the production of strain in the main section." Although the amount of fairing to be done in the case of the lacing-bars was small, it should be remembered that the amount of fairing was the same for all the lacing-bars in the member, and that the loads on the drifts would be very light. In the case of the section shown in *Fig. 18 (b)* (p. 119 §) of a member 40 feet long bent in double curvature the amount of fairing at the ends of lacing bars 30 inches long would be about 0.0023 inch and would be the same for all. Alternately, the amount of fairing of the holes at the end of the member shown in *Fig. 18 (a)* under similar conditions would vary between zero and about 0.01 inch, depending on the position in the group, and the drifting would be heavy. The procedure mentioned on p. 117 § of applying a load to the span before finally riveting the lacing-bar connexions was an alternative method which should overcome Mr. Toms' objections, if they still remained.

End connexions of members designed as in *Fig. 18 (b)* (p. 119 §) had been found by the Author to offer no special difficulty; in fact they lent themselves to a particularly convenient form of joint. It was shown in *Figs. 31*, and was self-explanatory. There could be no objection to the use of welding in that way, since the batten plate could be extended so as to reduce the stress in the weld-fillet to any desired figure. That arrangement enabled a riveted joint to be made in the field, and there was no weakening (in the case of

ension-members) by the deduction of rivet-holes. The weight of The Author.
ension-members was therefore reduced.

Turning to the flooring, the means of supporting the existing and
e proposed types of flooring were shown in *Figs. 32 (a) and (b)*.
was clear that the torsion in the supporting chord and the bending
the web-members would be reduced, when troughing was used,
an entirely negligible amount. The torsion would be very nearly

Figs. 31.




at due to the eccentricity c in *Fig. 32 (b)*, and the manner of
taching the troughing precluded any appreciable end fixing moment
be transmitted. With regard to the bending of the supporting
ords by the troughing-reaction, to which both Mr. Everall and
r. Toms had referred, since the supporting chord had been designed
th that object in view Mr. Toms' objection to it was not easily
nderstood. When, however, the work of the stringers was per-
rmed by the chords the worst bending moment was reduced by
e continuity of the chords from $\frac{WL}{8}$ to a figure which worked out


The Author.

Figs. 32.

(a)



(b)



COMPARISON OF SPANS WITH EXISTING AND PROPOSED
TYPES OF FLOORING.

The Author.

resting on the new top chords. The final rail-level was about $1\frac{1}{2}$ inch higher than the original. In reply to Mr. Everall's question as to the savings likely to result from the employment of that type of floor, the Author would like to quote figures from two actual designs. They were given in Table VII with current prices ruling in Bombay.

TABLE VII.


(1) Ravine viaduct No.1. Capacity: metre-gauge, single track, H.M. loading. Span: 105 feet; deck; structural steel.	(2) Mahi river bridge. 5-foot 6-inch gauge, single track B+50 per cent. loading. Span: 220 feet; through; structural steel.
Steel in normal floor, 14 tons at Rs.310/- . =Rs.4,350/-	Steel in normal floor, 70 tons at Rs.310/- =Rs.21,700/-
As revised: Steel in troughing:— 8.8 tons at Rs.275/- . =Rs.2,420/- Extra steel in chords:— 3.4 tons at Rs.310/- . =Rs.1,055/- <div style="text-align: right;">Rs.3,475/-</div>	As revised: Steel in troughing:— 59 tons at Rs.275/- =Rs.16,225/- Extra steel in chords:— 14 tons at Rs.310/- =Rs. 4,340/- <div style="text-align: right;">Rs.20,565/-</div>
Less capitalized value of 70 timber sleepers re- placed . . . =Rs.1,920/-	Less 110 timber sleepers=Rs. 6,550/-
Net cost . Rs.1,555/-	Net cost . Rs.14,000/-
Equivalent in tons of steel= $\frac{1,555}{310}$. . =5 tons	Equivalent in tons of steel= $\frac{14,005}{310}$. . =45.2 tons
Steel in floor reduced from 14 tons to an equivalent of 5 tons.	Steel in floor reduced from 70 tons an equivalent of 45.2 tons.

The saving amounted to about Rs.28/- per linear foot of 4 metre gauge span, and to about Rs.35/- per linear foot in the case of the 5-foot 6-inch gauge span. Those figures showed definite and substantial savings, but no account had been taken of the reduction of the secondary stresses and stresses due to lateral loads which the use of troughing ensured.

A rational manner of dealing with track-rails would appear to be to provide an expansion-joint over each girder expansion-bearing and to weld rails solid over each span rather than over two spans as suggested by Mr. Everall. The former plan was adopted in the case of the Nerbudda bridge. Fig. 34 showed the type of rail expansion-joint which the Author had designed for that purpose. The track had now been carrying traffic for about 2 years with complete satisfaction.

Mr. Toms had expressed doubt as to the possibility of measuring The Author. deflexion-angles on the model. That operation offered no difficulty, because at the end of each member there was a solid piece of celluloid representing a gusset plate and upon that the scribed line remained straight. In the case of the model used the straight portion was from 1 to 2 inches long. For purposes of measuring angles a strip of celluloid about 15 inches long and 2 inches wide was used. A

Fig. 34.



was scribed down the centre of the strip and towards one end parallel lines 0.1 inch apart were also scribed across the whole length of the strip. When the centre-line was laid over a member made tangent to the left-hand gusset-line the displacement of the right-hand intersection could be read off immediately. The net so read was divided by 100. The magnifying devices had worked satisfactorily, and rotational slip at the point A in Fig. 30 not occur.

The Author.

Mr. La Touche's strain-gauge with a base of $\frac{E}{1,000}$ appeared to offer advantages provided that the calibration of the instrument remained constant, and provided that the instrument was always used on metal having a constant value of E . In the case of wrought-iron bridges, which constituted a considerable proportion of the testing work in India, any advantage would be lost.

Full particulars relating to the Whittemore strain-gauge could be obtained from the makers.¹

¹ The Southwork Foundry and Machine Co., Philadelphia, Pa.

CORRESPONDENCE
ON PAPERS PUBLISHED IN
MARCH 1937 JOURNAL.

Papers No. 5065 and 5097.¹

“The Salonika Plain Reclamation-Works.”

By BENJAMIN WILLIAMS HUNTSMAN, B.Sc. (Eng.), M. Inst. C.E.

and

“The Lake Copais, Boeotia, Greece: Its Drainage
and Development.”

By ALEC JAMES DEAN, B.Sc. (Eng.), Assoc. M. Inst. C.E.

Correspondence.

Mr. OSCAR BORER observed, with regard to the Salonika Plain Mr. Borer. Reclamation-works, that Mr. Huntsman referred to the deposition of silt consequent upon flood-discharges, and it was obvious that a great deal of gauging had been done by the Foundation Company and its predecessors to secure the figures which had been given in the Paper. It was, therefore, of particular interest later in the Paper to see how far the designed velocities had been capable of carrying the silt in suspension. Mr. Huntsman showed that the ratio of the maximum flood-discharge to the carrying capacity of the channel ranged from 9 : 1 to 7 : 1. The late Mr. E. C. Hillman, Assoc. M. Inst. C.E., who had been connected with river- and canal-work in Egypt, had given a figure for English rivers of about 3 : 1, but it was somewhat difficult to arrive at a figure. From a consideration of the River Great Ouse, the ratio would appear to be between 2 : 1 and 3 : 1, but in the case of a river flowing through different classes of soil and material it became evident that the size of the normal river-channel and the flood channel was bound to depend upon the contour of the land, the fall of the river, and the nature of the bed-material. Where the bed was deep and the land adjoining the river was not unduly flooded, the ratio became only 2 : 1, whereas when the river was flowing through gravel with large stretches of land on either side at approximately bank-level, the ratio naturally increased considerably ; as far as could be determined, however, the nature of the

¹ Journal Inst. C.E., vol. 5 (1936-37), pp. 243 and 287 (March, 1937).

Mr. Borer.

land in Salonika and the Salonika Plain was fairly uniformly silt. would appear that the reason for the large ratio in the case of the rivers in the Salonika Plain lay in the figures given in Appendix V (p. 284 §), which showed rainfalls up to 6 inches per day (and even then most of it fell within a few hours). Quite irrespective of the nature of the catchment-areas, which in that case were somewhat mountainous, that would cause intense peaks in the flood-discharge. That was also reflected in the run-off per square mile, which reached as much as 350 cusecs per square mile in one case, as compared with a run-off for the Ouse and the Thames of about 8 cusecs per 1,000 acres.

The percolation-slope of 1 in 7 seemed to have been a safe one. In the Fens it was mostly necessary to work to gradients of 1 in 10, although in some cases it was possible to have a gradient of 1 in 12. That could be improved by having berms at the back, but it would be expensive on account of the claims for compensation which might arise. In the same way the Foundation Company would appear to have erred on the safe side with a freeboard of 1 metre as compared with the Fen allowance of 2 feet, which was the figure commonly used in England; then again, however, the sudden rise in the flood had to be taken into consideration which might equally easily exceed the maximum which had been hitherto recorded. That was borne out by the record of sudden floods given on pp. 266 and 267 §, which showed that a margin of safety, as it might be called, of 1 metre had certainly to be provided under such flood-conditions.

The stripping of the base of grass before the embankments were built had been referred to by Mr. Huntsman; that was a practice which was followed on some of the rivers in Lancashire, the material which was stripped off being afterwards used for protecting the new embankment. That might be an unnecessary refinement, however, in that past experience in the Fens seemed to have shown that ill effects followed the local custom of depositing straight on the grass after the removal of the heavy top growth.

The cross-sections of the river Axios showed that for convenience of excavation from the bed had been put on the berms. It would be of interest to know the size of the silt-grains which were deposited under those conditions, and whether there was any sign of the silt moving under flood-velocities of 4 feet per second, or whether it had become consolidated and grown over, remaining in that position permanently. The practice would lead to the danger of water lying at the foot of the new embankment between that and the spoil where it could not

asily find its way back into the main channel, with the result that the Mr. Borer. main bank remained unduly wet, and might eventually lead to seepage into the external borrow-pits. Possibly the material of which those embankments were made was fairly sound, but experience in the Fens was against the practice of depositing dredged spoil on the edge of the washlands.

He was not quite clear as to the design of the Upper Notched weir, which seemed to be a satisfactory arrangement for dealing with the entrance of the flood-waters into the Circulatory canal. Apparently the waters passed through a series of V-notches, and the eddying consequent upon the change of velocity was dealt with by means of dry-stone pitching and curtain strips of stone bedding, placed right across the channel below at intervals of 4 metres. He could not quite follow the design of the apron below the notched weir ; was there a direct vertical fall of about 3 metres on to the lower apron ?

The provision of a breaching section such as that on the Moglenitsa was excellent practice, and it was of interest to learn that it was sufficient to make it of earthwork. The River Great Ouse Catchment Board had recently had to undertake the dredging and embanking of one of its Fen rivers, and they proposed to adopt such a spillway, as the holding-up of water to a higher level, consequent upon the construction of the embankment, would put such a strain on the banks that in the event of a burst there would be more danger than if the banks had not been so raised.

The constructional difficulties of dealing with the building of the new Circulatory canal while maintaining the existing rivers reflected great credit on the care exercised by the Company in the execution of the work. That was emphasized by the construction of temporary drainage-channels and by the general practice of excavating in a downstream direction so that the silt was carried downstream and the excavated section was left clear. That was contrary to general practice, but had been adopted by Mr. Borer when circumstances permitted, not only because the silt travelled downstream and could be picked up later, but also because the method was very valuable when dealing with weed-infested rivers ; when work was carried out in the upstream direction the roots which broke off after the dragline had passed were carried down on to the new work, which formed an ideal bed into which to transplant them. The result was that the condition in a few years might be found to be worse than before the dredging had been undertaken.

He was interested to hear that wire-netting bags filled with stones had been used ; such bags had been tried out on the New Zealand rivers some years ago, with great success. In view of the somewhat high velocities that had to be dealt with, would the Author state

Mr. Borer.

whether subsequent experience had suggested that the groynes would have been even more successful if they had been at any angle rather than at right angles?

There must have been great difficulty in some sections of the work in maintaining "green" embankments, as owing to the great width between the embankments considerable wave-action must have been created by heavy winds under flood-conditions on account of the fetch. Experience in that matter was that the fresh embankments that were most in danger were those which faced the stretches of any particular river which was subject to the full force of the prevailing winds. One of the main barrier-banks in the Fens, which had been raised and strengthened only a few years ago, had been subjected to heavy erosion during the floods of the past year. Many years ago the Bedford Level Corporation had provided for the growth of osier-beds immediately in front of the toe of the bank, so as to resist the action of the winds on the water, and that practice was much to be recommended, in spite of the possible loss of discharging capacity consequent upon the intrusion of the osiers; in his opinion it provided for lower velocities immediately alongside the embankment.

Mr. Huntsman stated that the spur-groynes were generally placed about six times their length apart, which was possibly about the usual practice under British conditions, although they appeared to be only one-half that distance apart in Continental practice. The sentence at the foot of p. 272 § did not appear to be quite clear because if the spurs were spaced at three or four times their length apart that would imply that silt had accumulated right up to the front, whereas if they were further apart it would accumulate even more. That, however, might be a misinterpretation of the statement. It was of interest to see Mr. Huntsman's conclusion that it was cheaper to have spur-groynes than to employ continuous bank revetment.

There was much useful information in the evidence on p. 269 following upon the diversion of the Axios into its new channel. Had Mr. Huntsman any information as to the size of the silt-grain which went into suspension, and the slopes of the sides which remained stable, after the river had bedded itself down? Was there any change in the coefficient of friction as the conditions changed, or was the alteration in surface-slope of the river entirely due to the change of cross-section? For long straight stretches such as existed in some of the works the bed should have remained level according to the observations elsewhere, and it was upon that fact that some of the theories with regard to the transport of silt had been based.

It would therefore be of interest to learn whether the bed remained Mr. Borer. reasonably level across the channel.

Mr. Borer had endeavoured to compare the final velocities, as given on pp. 269 and 270 §, with those set out in the initial design. Without further particulars it was very difficult to compare them, but it would appear that the final velocities were somewhat lower than those for which provision had originally been made. At the same time the silt carried in suspension seemed to have fallen as the river settled down into its new bed, so that stability would appear to have been obtained with generally lower velocities; after all, all designs depended upon certain assumed coefficients, and the more information that could be obtained on that point the more valuable it proved on any future occasion.

Mr. FRANK GROVE, of Jersey, had been advisory engineer to the Mr. Grove. London Agency of the Foundation Company of New York from the inception of the Salonika Plain reclamation-works contract in 1925 until early in 1929. It had only been possible, in the time at his disposal early in 1925, to make a cursory examination of the scheme before negotiations for the contract were commenced. Those negotiations had been brought to a satisfactory conclusion in September of that year. He had been responsible for the original estimate attached to the contract of 1925, namely \$26,570,000, on which to December, 1935, a saving of \$10,910,000 had been effected.

His figure had been less than had been given in a report submitted to the Greek government by Mr. G. Yennidounias; that report had provided for the major works and had laid down the general principles which had finally been adopted. The very large saving had been due primarily to the excellent work done by the excavating and other plant, which had been selected solely on the advice and initiative of the contractors. It had been originally assumed that much manual labour would be insisted upon by the Ministry, but the officials had collaborated with the administration for the greatest possible economy. The saving was also largely due to meticulous care in the preparation of designs and estimates. It was greatly to the credit of the contractors and to the executive staff, bearing in mind the climatic and language difficulties, that those very heavy and intricate works had been carried to so successful a conclusion, and he hoped that most careful maintenance-works would be continuously undertaken so that the economic benefits to the district and to the finances of the Government would continue and increase. The contract had been on the terms of "cost plus commission." No other terms of contract had been possible at the time, the nature

Mr. Grove.

of the work being so ill-defined until extensive surveys had been completed and meteorological and other data had been procured over a period of some years. While such terms of contract were readily sought by contractors, the administration and the executive engineers were frequently placed in an invidious position. The Government was the principal party to the contract—the Government.

The first Agent of the contractors in 1925 had been Mr. B. T. J. Boothby, M. Inst. C.E., who unfortunately after a few months resigned owing to ill health. He was succeeded by Mr. Norman Sisson, M. Inst. C.E., who remained in charge until the early months of 1929, by which time the surveys were completed, the major works were designed, and the Ardzan and Amatovo lake reclamation was well advanced to completion. Major W. J. Ross followed as Agent and during the $2\frac{1}{2}$ years under his control the heavy works were commenced and substantially advanced. He was succeeded by Mr. K. J. C. Hill, B.Sc., M. Inst. C.E., and Mr. Huntsman took charge in 1934.

Mr. Lacey.

Mr. J. M. LACEY observed, with regard to the Paper by Mr. Huntsman, that the average slope of the Axios diversion-channel from the railway bridge to the sea was 0.0005, but at the commencement it was about 0.00075; the new channel had been designed with its bed- and water-slope parallel to the ground (p. 252 §). On pp. 26 and 270 § Mr. Huntsman stated that the river had been diverted into the new channel on the 5th April, 1934, the discharge in April being 6,000 cusecs, and the mean velocity in the upper reach on the 14th April being 4.75 feet per sec. The greatest bottom velocity observed had been 5.375 feet per second in April, and initially the water-surface in the reach had had a slope of 0.00078; that was the surface-slope had been greater than the bed-slope of 0.00075. Had Mr. Huntsman any records of velocity-observations taken at that time, showing the variation in velocity with the depth? It was stated that after 8 weeks the surface-slope had flattened to 0.00075, and a year later for the same discharge to 0.00056, approximately its average designed slope. In the meantime the mouth of the river had extended seawards over 1,000 yards in a straight line with parallel banks, so that apparently the river was adjusting itself to its regime-slope. As the mouth of the river proceeded seaward there would be a tendency for the bed to rise if the flood-water were controlled by levees.¹ Had the necessity of increasing the width of the channel as it proceeded seaward been considered?

§ *Ibid.*

¹ J. M. Lacey, "Some Problems connected with the Rivers and the Canals of Southern India." Minutes of Proceedings Inst. C.E., vol. ccxvi (1922-23 Part II), p. 155 *et seq.*

Mr. W. O. LEITCH considered that interesting maintenance-Mr. Leitch. problems would arise on the Salonika Plain reclamation-works. Damage might occur from maximum floods, during which the central channel might deviate from a straight course and might attack the unprotected dikes, whilst serious erosion occurred in the high lands during heavy rains. If the silt-proportion were too great for the current to carry, the space between the dikes would gradually fill up. Could Mr. Huntsman state the proportion of silt from samples of water taken during floods? The average proportion throughout the year of 1 in 350 might not be applicable to flood conditions.

The space between dikes had to be wide enough to contain safely maximum floods, and smaller floods would therefore apparently be shallow, approximating to the conditions before the dikes had been made, when the river-bed had become gradually raised above the adjacent land. Was there any sign of that occurring?

Mr. THOMAS MAKINS observed, with reference to the lake Copais,Mr. Makins. that the arrangement and extent of timbering required to ensure safety in deepening a tunnel 9·5 metres high through a stratum of fissured limestone was bound to have presented very serious considerations. A travelling shield such as was generally used on the lining of railway tunnels might have proved of great service.

Had the rock-cutting in the tunnel been carried out entirely by the aid of pneumatic rock-drills and hand-tools? That question was prompted from experience gained on extensive rock-excavation in the Piraeus district, 50 miles distant from lake Copais, where the geological formation consisted of calcareous marl and whitish limestone with numerous faults, fissures and cavities. It had been found here that the use of explosives invariably loosened more rock than was desired. In the case of certain foundations which had to support particularly heavy loads, the necessary rock-excavation had been specified to be carried out without the use of explosives. In consequence, the contractor's price for those excavations had been higher than the general price for unrestricted work. Notwithstanding that, however, when no one was looking, the temptation to blast appeared to be too great, which illustrated the importance of constant and careful supervision in that class of work.

Mr. F. W. SCOTT, of Johannesburg, had found, when he had takenMr. Scott. over the Salonika Plain surveys early in 1926, that the work had been started on a basis of skeleton chain-traverses on which had been built up a tacheometrical system covering the area. He had continued that system, although it had often occurred to him later that the conditions would have been better met by a triangulation-system. The survey-work of all the parties engaged in the area was reduced

Mr. Scott.

as rapidly as possible to a common system of co-ordinates and datum levels, after which check-sights on well-known points were regularly picked up by the parties, and some of the advantages of a triangulation-system were retained. The gradients of the proposed canals were in many places so low that extreme accuracy of levelling was required, and the results reflected credit on the survey-parties, particularly when it was remembered that soft ground and swamps were the rule rather than the exception. Trouble arose in some cases as a result of the seasonal rising and falling of the ground-surface, and with it the bench-marks, due to the swelling of the ground in the winter rains. In that connexion he was gratified to note how closely the actual shrinkage of the mud in lake Yenitza corresponded with the prediction of 50 per cent. made in 1926 as the result of experiment. One matter had to his knowledge never been satisfactorily explained—the levels of the floor of lake Yenitza, taken and checked by most competent and reliable engineers, were found during construction to have risen by 1 metre, causing considerable difficulty in obtaining flotation for the dredger on the lake-drains. That that was the result of silt carried in by the Aliakmon in the 1928–29 floods seemed improbable, but it had never been explained otherwise.

The surface of lakes Amatovo, Yenitza, and the Kato Limni (the portion of the Loudias lying south-east of the Athens Railway) had originally been covered with masses of “sudd” (floating reed beds about 2 feet thick), which gave trouble during both survey and construction. The edges of the lakes were also fringed with reeds, and in the case of lake Amatovo the burning-off of the reed-beds had lowered the ground surface by over 3 feet. He recollected an occasion on which he set up an instrument on the roof of a fisherman’s hut in an island in lake Yenitza, only to find, on looking through the eyepiece, that the landscape appeared to be revolving slowly in front of him: the hut had been built on floating “sudd”. The survey of the swamp-area offered many problems on account of its great extent. The use of three sections of 2-inch pipe, driven like a screw-pile into the lake-bottom and capped with a fixed table to hold the instrument, had been freely resorted to when sights from shore had become impossible.

The littoral drift off the mouth of the Loudias canal, mentioned by Mr. Huntsman, had been ascertained by the survey of floats connected to 4-gallon tins which had been sealed after being loaded with sufficient water just to submerge them. The tins were suspended just above the bottom, and the movement of the attached float was taken as indicating the probable tidal current close to the bottom, which could be taken into account in moving the silt laid down by the adjoining outfalls of the Aliakmon and Axios diversion. To avoid

the closing of the mouth of the Loudias by that silt, he had put Mr. Scott forward proposals for submerged stone banks continuing the mouth of the Loudias seaward, to be extended as the adjoining silt deposits grew, but there was no record that the proposal had been adopted up to date.

It might be considered that the cost of the scheme was not justified by results, but it had to be remembered that Greece, a country comparatively poor in cultivable land, had been faced with a staggering increase in refugee population, mainly agriculturists, for whom provision had to be made no matter at what cost. Reduction of malaria, too, had its value, although not easily priced in financial terms. Apart, however, from those questions, the port of Salonika, so important to Greece and to Jugo-Slavia, and such a factor in Near-Eastern politics, had been assured a long term of freedom from the fate of silting, which had overtaken so many ancient riverine ports in the Levant. He was whole-heartedly in favour of the alternative proposals put forward by the Foundation Company and by Messrs. Couper and Ker for a progressive series of diversions utilizing gulf areas near the port for silt-deposits, and laying aside funds for future work on the main Axios diversion to accumulate at compound interest. Theoretically that would have been less costly and would have increased the life of the port still further, but the Greek Government took the unanswerable view that man could not foresee political conditions in 1977.

He would like to record his appreciation of the courtesy of the Hellenic State Railway engineers, whose co-operation in all matters affecting their line, and especially their bridges, had been invaluable. He noted Mr. Huntsman's reference to wooden bridges over minor canals, and to steel superstructures for road bridges elsewhere, with interest. In the earlier stages, the Greek Government were strongly opposed to the construction of steel or wooden bridges on the grounds of later maintenance. They pressed for reinforced concrete in all cases, and such bridges were built in some cases, where less expensive bridges would have fully met the case. It would seem that economy in first cost rose from a secondary to a primary consideration at a later date. It would be noted that wherever possible, manually or automatically operated sluice-gates had been avoided, and preference given to self-acting foolproof structures. That was made a principle on account of the probable difficulty in finding suitable and conscientious attendants among a population quite unused to mechanical contrivances of any kind. The Lower Notched weir was a special design, and was conceived on that principle. The great scale of the "notches" and the "no fall in bed" condition were quite unusual in a structure of that kind. The design was arrived

Mr. Scott.

at by two engineers working independently and by two separate methods, the results being practically identical. When the first 1 : 100 scale model was put into operation it was found that the coefficient of the notch, normally about 0.67 in small notches, was 1.00. The conditions of the experiment were not very favourable owing to the lack of co-operation by the local staff at the site, but there was no doubt about the discrepancy. Accordingly, a 1 : 10 scale model was set up on the sea-front at Salonika, and supplied by pumping from the sea. A series of most careful observations with varying rates of flow and varying upstream and downstream levels was carried out; with duplication of the experiment on a different scale, there could be no longer any doubt that the coefficient was as stated. The cause was undoubtedly the coffin-shape of the piers, which were lengthened downstream to resist the overturning moment of the 14-foot 3-inch excess head anticipated on the upstream side. The consequent "bellmouthing" had had the effect of increasing the coefficient, and it was therefore possible considerably to reduce the width of the structure. The model indicated that at high flow, after passing the notches, tended to rush straight down the central channel with excessive velocity, leaving dead water on the berms; that resulted in the introduction of the baffles mentioned by Mr. Huntsman. It was a matter of interest that alteration in the position of the baffles in the model seemed to make no difference in the position of the standing wave below the weir, nor was the rate of discharge affected. Advantage was taken of the model to have similar experiments made for the Upper Notched weir. The curved form of the piers between the notches in the upper weir (shown in *Figs. 5. p. 254* §), resulted from the conditions of discharge. No single batter on the sides of the notches would effect the desired control at all heights of flow, and consequently an opening with curved sides was required. It was a matter of great satisfaction to Mr. Scott that those structures were said to have completely fulfilled their purpose in the floods which had occurred since the completion of the works.

Excavation in considerable excess of the original estimates was reported by Mr. Huntsman. That was not unexpected in an area nearly entirely composed of silt-deposits with extreme variation in consistency. Experiments made by Mr. Scott had showed that some of the worst silt in a wet condition flowed to a slope of 1 in 6, but as drainage would effect a consolidation, it was impossible to design for so flat a batter. Much of the excess of underwater excavation was bound, therefore, to be accounted for by the flow of mud into

the new channel, as well as by the inaccuracy due to working under-Mr. Scott. water.

Much use was made of dragline scrapers working on pontoons as a result of the "sudd" in the submerged areas. Direct excavation by hydraulic dredger was impossible owing to the dense growth of vegetation and roots. No machine requiring heavy anchorage ahead, such as a bucket or shovel dredger, could be used, owing to the difficulty of fixing anchors forward of the work in the "sudd." The very soft consistency of the bottom in most cases made spuds an uncertain proposition. The draglines, excavating towards the pontoon, could have their main anchors fixed behind them in the channel already cleared, with light steadying anchors placed ahead or beam by the dragline itself, and for that reason they were adopted. They had certain disadvantages: accurate grading of the bottom was most difficult, the output was from 20 to 25 per cent. less than when working from land, and they could not be used for a final cut when moving forward towards their work on account of the spill from the buckets as they were dragged in, but that was overcome by taking a partial cut on the forward trip and finishing off the work to final level by a second cut while backing out. In the Kato Limni it was arranged for the dragline to remove the top layer containing the reeds and other vegetation, and the final cut was made by the suction-cutter dredger.

The extreme variations in the flow, particularly of the smaller rivers such as the Gorgop (locally known as the "mad river" on account of its fierce and sudden floods) presented difficulties in the design of channels to meet as far as possible all circumstances. The Gorgop channel, for example, was excavated wide enough to meet flood-conditions, but during small flows there had been a strong tendency, while he had been on the works, for the stream to meander in the wide new bed, cutting at the base of the bank and tending to form loops. It would be of interest to know if it had been necessary torevet that and other similar rivers, or if the trouble had ceased to develop further.

Malaria had been one of the greatest difficulties met with in the earlier stages of the work, and the conditions of the Salonika Plain had made it next to impossible to take anti-malarial measures during construction. In some parts the type of malaria had been malignant, and one refugee village had had to be evacuated after 110 deaths had occurred in a fortnight, out of a total population of 225 families. At the start of the works on the Amatovo-Ardzan section, it was not uncommon to have a sick roll of 20 per cent. during the autumn. Regular prophylactic doses of quinine eventually reduced the proportion to about 2 per cent. He observed that Mr. Huntsman

Mr. Scott. recorded the minimum temperature of the plain as 5° F. on the 20 December, 1925; during a Vardar gale in the winter of 1928-9 the Amatovo thermometers registered to -13° F.

Mr. Huntsman. Mr. HUNTSMAN, in reply to the Correspondence, considered that the ratio of the maximum flood-discharge of a river to the normal capacity of its natural channel depended not only on the contour of the land, the fall of the river and the nature of its bed-material, as stated by Mr. Borer, but also on its silt-content, and particularly on its average discharge during the flood-season and the variation of its discharge during the year. The following were figures for the two largest rivers in the Salonika plain:—

River.	Axios.	Aliakmon.
Capacity of natural channel: cusecs	14,700	15,100
Maximum flood-discharge: cusecs	134,000	116,500
Ratio	9.15:1	7.7:1
Average discharge (March and April): cusecs . . .	11,400	6,100

The Axios channel was comparatively more liable to siltation, but the Aliakmon floods were more rapid in their rise and fall (accounting for the average discharge in the flood-season being comparatively lower), and were more violent in their scouring action. The ratio for stable rivers elsewhere might be 2:1 or 3:1; but for torrential rivers much larger ratios would occur. The new river diversion-channels were, in Mr. Huntsman's opinion, correctly designed with capacities equal to those of their natural channels; larger diversions would have silted, encouraging meandering of the low-water channel, and smaller diversions would either have caused more frequent inundation of the berms, interfering with winter grazing and summer cultivation, or else would have scoured, causing objectionable deposition of silt downstream. For the artificial drainage-channels a ratio of 3:1 had been advocated (p. 248 §), and the Vardarovassi channel, for instance, had, as constructed, a ratio of about 4:1.

Generally satisfactory results had been obtained as regards the transport of silt in channels where velocities had been designed on the basis of the Kennedy formula $V_o = c.d^{0.64}$, using a coefficient of 0.84 (feet units), although in some cases a slightly larger value could probably have been adopted. In the Circulatory canal, where the bed-material was coarser and firmer than the soils in the centre of the plain and where the silt was finer than the bed-material, the maximum velocity, 7.9 feet per second, had been designed great

an the critical velocity, 7.3 feet per second; the results during Mr. Huntsman. ods had been satisfactory as regards silt in suspension.

Mr. Lacey and Mr. Borer had asked for further information concerning the Axios diversion and the variation in its coefficient of rugosity. The following were figures concerning some of the measurements taken on 31st May and 1st June, 1934, 8 weeks after opening:—

Kilometre.	R : feet.	S .	V : feet per second.	f .	V_c : feet per second.	C .	N .	N_b .	N_c .
3	3.64	0.00079	3.04	1.40	2.60	1.17	0.0325	0.0244	1.33
6	4.34	0.00053	2.72	1.35	2.81	0.97	0.0339	0.0242	1.40
10	5.64	0.00027	2.73	1.30	3.11	0.88	0.0283	0.0240	1.18
13	5.32	0.00024	2.95	1.25	2.97	0.99	0.0238	0.0238	1.00
15	4.60	0.00015	3.13	1.15	2.65	1.18	0.0161	0.0233	0.69
18	6.63	0.00006	2.15	0.95	2.89	0.75	0.0189	0.0222	0.85

(Symbols explained in the succeeding text.)

at that time some scouring was still continuing in the upper reach (K.3 and K.6). The section at K.15 was at the thickest part of the silt which was being rolled along the bottom of the channel (p. 270 §). The section at K.18 was further downstream than that rolled silt, and there silt in suspension was being deposited. At K.13 the bed had been raised during April with the material rolled down from the upper reach; some scouring of that material, which had commenced at the beginning of May, had ceased at the end of that month, and on the 1st June that section might be considered as having been in a state of temporary equilibrium, for the silting which occurred later when the discharge decreased did not commence until the end of June. The usual coefficient of rugosity, N , was deduced from Manning's formula, $V = \frac{1.486}{N} R^{\frac{2}{3}} S^{\frac{1}{2}}$. That and other formulas involving the coefficient of rugosity had often to be used in estimating flood-discharges at times when scouring or silting was occurring or had recently occurred, and, as it was often difficult in such cases to assign the correct value to the coefficient, its variation in the present instance might be of interest. N might be considered as equal to $N_b \times N_c$, where N_b was a coefficient of "absolute" rugosity as defined by the silt-factor,¹ and where N_c was a factor allowing for the variation from a state of regime and measuring the channel-condition as opposed to the channel-material. No accurate analysis of the sizes of the silt-grains was made, but the silt-factor, f , had been estimated on the following assumptions (made for the present purpose of indicating the variation in N_c); (1) that at K.13, $N_b = N$,

Mr. Huntsman, since at that point the channel was straight, the cross-section was uniform, the bed and the silt in suspension were of similar material, and neither scouring nor silting was occurring at the time; and (2) that at other points the value of f was somewhat greater in the upper reaches and somewhat smaller in the lower reaches. V_c was the critical velocity as defined by $V_c = 1.15 f^{1/2} R^{1/2}$, and C was the ratio V/V_c . The amount of scouring which was occurring below K.3 was approximately equal to the amount of silting which was occurring above K.18, so there was no appreciable difference in the silt-content of the water at those two sections. The figures indicate that there might be a 40-per-cent. increase over the normal value of the coefficient in reaches where scouring was occurring, and that the coefficient might be 30 per cent. less than normal when the bed was composed of recently-deposited rolling material and when deposition of silt in suspension was in progress. The alteration in the value of N in the upper reaches after diversion was :


Date.	April, 1934.	June, 1934.	July, 1934.	Aug., 1934.	Sept., 1934.	Sept., 1935.
$N :$	0.0287	0.0317	0.0335	0.0275	0.0245	0.0255

Velocity-observations at various depths, about which Mr. Lacey had made inquiry, had shown great irregularity in the Axios diversion channel, as was to be expected in a channel adapting itself to a new regime. Curves A, B and C (*Fig. 6*) showed the mean of observations in the upper reach of the diversion-channel in April 1933, September 1934, and September 1935, respectively, and D was the usual curve for rivers in the Salonika plain, being the mean of 140 readings on the Axios and the Aliakmon. Curve A was the flattest, that was to say, the rate of increase in velocity along the vertical was greatest, and the maximum velocity was nearest the surface, when the amount of scouring was greatest. Unfortunately no observations were available in the lower reaches where silting was taking place, but it was known that relatively greater bottom velocities occurred there. The banks of the upper reaches became steep and often vertical, as in the natural channels elsewhere in the plain, and the bed in the top reach did not remain level across but was generally deepest near one of the banks; in the lower reaches however (for example at K.13 and K.15), the bed became fairly level across with a slight rise towards the foot of each bank. The spoil from the channel, which had had to be placed on the adjacent

¹ G. Lacey, "Uniform Flow in Alluvial Rivers and Canals." Minutes Proceedings Inst. C.E., vol. 237 (1933-34, Part 1), p. 421.

berms (p. 264 §), became consolidated. There was a smaller depth of water in flood on that spoil than on the remainder of the berms, and no direct scouring was occasioned by normal floods; trouble from scouring did occur, as anticipated, at points where the flood-water on the berms flowed back into the central channel. There was considerable variation in the silt-content of the Axios during the year; as an instance, samples taken during a small flood in October, 1931, showed a mean value of 1 in 194 (by weight of dried silt, excluding rolled silt), whereas 2 weeks later, at a low stage, the proportion had fallen to 1 in 1,180. The October observations

Fig. 6.




showed proportions of 1 in 255 near the surface and 1 in 156 at a point 1 foot above the bed. Mr. Leitch had referred to the well-known difficulties of maintenance of works like those of the Salonika plain, and to the tendency of the rivers' channels to deviate and possibly eventually to endanger the protective embankments; continual inspection was necessary and the construction of river-cleaning works was required every year. The natural raising of the berms by silt and the consequent necessity of raising the crest-levels of the embankments was not considered likely to be one of the most urgent questions of maintenance. The problem of the mouth of the Axios diversion, referred to by Mr. Lacey, would doubtless have

Mr. Huntsman, been solved more satisfactorily by the scheme for a progressive series of diversions with their embankments widely bell-mouthed (p. 252) but, as Mr. Scott had mentioned, the Government had had to give consideration to other views besides those of engineering. The proposed stone dikes at the mouth of the Loudias canal had not yet been built, as the authorities had preferred, before committing


Fig. 7.

RIVER CHANNEL



SPURS FOR RECLAIMING ERODED RIVER-BANK.

RIVER CHANNEL



TRAINING SPURS, FOR RIVER-BANK PROTECTION.

(Not to scale)

SPURS IN THE RIVER AXIOS.

themselves to any expenditure, to wait for the action of time indicate their necessity.

With regard to the spacing of spurs in the bed of the river Axios Mr. Huntsman hoped that the sketch (Figs. 7) would supply information which Mr. Borer had asked for in addition to the notes given on p. 272 §. The outer ends of the spurs were designed on a smooth curve, and the deep-water channel had to be left wide enough to maintain a good discharge-capacity. The use of wire-netting

bags had been common for some years in Italy and Switzerland. Mr. Huntsman, the life of the bags depended upon the efficiency of the galvanizing, and severe testing of that galvanizing had been included in the specifications.

Mr. Scott had remarked upon the difficulties in the design of channels where there were extreme variations in the flow. The amount of maintenance-work which had been required in the Gorgopotamos, which he had mentioned, had not been very great; the channel had maintained its alignment, but the clearing of silt-deposits had been necessary in the lowest reach. There had been, of course, a tendency in several cases for streams to meander in their channels at low stages, but bank-pitching had not usually been needed; those troubles which had developed had generally been due to excessive gradients. A certain amount of "bed-heave" had occurred in channels where the spoil had been deposited close to the edge of the cut, and in the Circulatory canal a small rise and fall of the bed had been observed, varying with the rise and fall of the water-level. The theory to account for the observed rise of part of the central bed of lake Yenitsa had been that the rise resulted from the serious earthquakes which occurred after the surveys had been completed. Mr. Scott had commented on the experience of draglines mounted on pontoons and using drag-buckets; actually most of the work by draglines in lake Yenitsa was done with grab-buckets. Better results had been obtained with grabs, as had already been mentioned (pp. 262 and 315 §).

Stripping the sites of embankments had been necessary, and key-renches also had been required in some instances; moreover, that stripping had provided the top-soil which was needed if grass were to be successfully grown on the slopes, and the stripping of the borrow-pits was essential, he considered, in order to exclude roots and vegetable matter from the core of the embankment. Stone-pitching had been laid on embankments exposed to wave-action; scouring were likely a strong foundation or flexible apron had to be provided at the toe of the embankment. On other works in northern Greece thin "gunite" work had been used on the slopes of consolidated embankments; this had appeared to be quite satisfactory, but in the Salonika plain the ordinary stone pitching could be done very cheaply.

Mr. Borer had inquired whether there was a direct vertical fall of about 3 metres at the Upper Notched weir. Reference to *Figs. 5* (p. 254 §) would show that the fall in the bed-level was dimensioned at 2 metres: that was correct, the upstream and downstream bed-

Mr. Huntsman, levels being 22·17 and 20·17. As the water-level downstream the canal rose more quickly than the water-level upstream in the gathering-basin, the fall in water-level at the weir became less than 2 metres as the flow increased, and at high-floods level the difference in water-level was 40 centimetres, as was shown in *Figs. 1 and 2*. The curved tortoise-shaped sides of each notch (*Fig. 1*, facing p. 306) automatically maintained the correct levels of the upstream and downstream water for all discharges up to 8,500 cusecs; above this level (25·17) "backing-up" resulted upstream as previously described (p. 255 §).

The temperatures recorded in the Paper (Appendix I, p. 277) were those officially measured at stations in the Salonika plain. The lower minimum temperatures had certainly occurred elsewhere in the district, and higher maxima also had been unofficially reported. Mr. Grove had emphasized the importance, in the case of works like those in the Salonika plain, of the correct choice of plant; this would be appreciated, since 1 penny extra per cubic yard on the cost of excavation by machines would have increased the cost over £200,000. Reference had been made to the estimated costs of bridges in the choice of the types to be adopted. Excluding some of the earlier small bridges, which had been relatively expensive, the actual costs of some typical road-bridges constructed between 1910 and 1935 had compared as follows:—

	Type.	Name.	Cost per linear foot.	Cost per square foot.
Main roads:	Steel (short)	Loudias	283	14·4
	Steel (long)	Axios	158	8·0
	Reinforced concrete	Vardarovassi	118	5·7
Minor roads:	Reinforced concrete	Selimli	47	3·6
	Reinforced concrete and timber	Koulakia	42	3·5
	Timber	Koufalia	26	2·2

The above figures included an allowance for overhead charges, but not for the cost of land, etc. Details of those and other bridges had been given in Appendix VI (p. 282 §). Timber bridges for minor roads had often been adopted on account of their low first cost, but bridges of reinforced concrete had been constructed very cheaply, and their extra cost was often justified on the grounds of cheap maintenance; timber bridges had a comparatively short life, particularly as there was often a scarcity of firewood in adjacent villages.

Reference had been made also to the cost of the whole scheme. Mr. Huntsman. It was not possible to make an exact sub-division on the total cost, but approximately \$2,300,000 had been spent on works of communication and on bridges, and about \$1,400,000 on diverting the river Axios. That left \$12,000,000 as the cost of draining 108,000 acres and of protecting from floods a further 198,000 acres, giving an overall rate of about £8 per acre, which seemed a reasonable figure. In 1928 Greece had had to import 2,950 million drachmae (about £5,500,000) worth of agricultural products, including 525,000 tons of wheat. The extent to which production had since been improved could be judged by the following figures:—

Year:		1928.	1934.
Total cultivated area :	Whole of Greece	15,901	21,445
square kilometres	Salonika Dept.	1,459	2,356
Cereal crops: tons	Whole of Greece	785,842	1,302,095
	Salonika Dept.	—	215,365
Value of cereal crops:	Whole of Greece	3,535	5,565
million drachmae	Salonika Dept.	—	891

Mr. DEAN, in reply to the Discussion and Correspondence, observed Mr. Dean. that the *katavothras* in the Copais and the surrounding districts seemed to have aroused interest from time immemorial. In recent times they had been studied by Dr. A. Phillipson¹ and by Mr. C. S. Cole, Assoc. M. Inst. C.E., in 1910, when Chief Engineer to the Company. Although they appeared to have been used by the ancient inhabitants for drainage purposes and similar use had again been proposed in recent times, their existence was by no means an unmixed blessing. Without those subterranean outlets it was to be presumed that the lake would have risen high enough for the water to cut out for itself an overland channel to the sea, and it might in time have drained itself naturally.

Most of the water from the *katavothras* would appear to go direct to the sea; springs of fresh water appeared along the whole coast opposite, near the edge and in the bed of the sea. A particularly large spring appeared at Skroponeri in line with the Grand *katavothra*. The use of the waters from the Copais for hydro-electric purposes at Anthedon was also rendered speculative because of the leakage from the lakes Likéri and Paralimni through *katavothras*. In connexion with that project the Author attempted, in 1931, to locate two *katavothras*, of which there was some record, in lake Paralimni. He had been eventually found some 20 metres below the surface

¹ *Zeitschrift der Gesellschaft für Erdkunde zu Berlin*, vol. xxix (1894), No. 1.

Mr. Dean.

of the lake, the flow of water being clearly indicated by a current meter. Several buckets full of a strong solution of fluorescein had been poured down a pipe at the spot, and as no sign was observed at the surface, presumably it had all gone into the *katavothra*, but an elaborate picket of all suspected points on the seashore had failed to observe any sign of coloration. It might be said that much smaller doses of fluorescein put into the water upstream of Anthedon tunnel, besides colouring the whole stream, were visible hundreds of yards out to sea. It would seem that besides *katavothras* which were large enough to be noticed there were probably hundreds of smaller ones, and that they were all probably interconnected below ground, so that the water took a long time to reach the sea.

The scheme adopted of deepening the outlet-works in order to improve the drainage of the lake would certainly seem to have been the right solution. It was now proposed to complete the lining of the tunnel and to render the bed and sides of the Emissary canal with cement mortar in order further to improve the drainage from the Great Central drain (thus combining the scheme adopted with the alternative mentioned by Mr. Halcrow). The lining of the tunnel was, however, primarily intended to ensure its safety. As Mr. Makins observed, considerable care was required in deepening a tunnel of that size. Explosives were employed in restricted lengths but, as mentioned in the Paper, a serious accident occurred probably through the contractor's desire to go too fast, although there was no evidence that blasting had occurred where instructions were to the contrary.

As mentioned in the Paper, little silting or scour appeared to have occurred in the lower channel of the Grand canal, whereas silting of the berms was in places considerable, particularly at the bend. A survey was in hand to determine the precise position. He thought that Mr. Borer was probably right in assuming that a self-cleansing velocity kept the central channel clear in flood-time; the velocity on the berms was less, and there silting took place. In normal conditions (that was to say, when the water was confined to the lower channel) the quantity of silt was negligible. In its upper reaches the channel had been excavated mostly in the heavy alluvial soil of the Kefissos and Hercyna deltas, but further east the sub-soil of clay rose nearer and nearer to the surface. In the latter soil artificial attempts to encourage scour had not proved very successful. The increases in the discharges of the rivers flowing into the Grand canal as shown in Tables II and IV (pp. 293 and 304 §), compared with

table I (p. 291 §), were due to further observations since Monsieur Mr. Dean, Rochet had made his original estimates.

The sinking of the old lake-bed described in the Paper (p. 293 §) was almost entirely due to the burning of the peat. When the interior canal had been designed it flowed through the lowest land. After the peat had burnt, the land in the centre of the Copais sank in places as much as 4 metres, and the area marked on Fig. 3, Plate 1 (following p. 316 §) became the lowest land at a level more than 4 metres lower than the previous lowest level, but not in the same place. That would explain to Mr. Borer the difference between the maximum shrinkage of 4 metres and the fall in level of the lowest land of only about 2 metres. Dust storms in the summer were bound to remove a certain amount of soil from the Copais, but no investigation as to the quantity had been made.

The only channels which were embanked for drainage purposes in the Copais were the Grand and Marsh canals, and the Melas river and canal. Apart from very short floods from torrents the Melas river had no flood-discharge to carry and, since it had been deepened, the water-level was normally below the level of the land and generally below the burnt-peat layer, so that infiltration from it had practically stopped. The floods which interrupted gravitational drainage were in the Grand and Marsh canals. When the water-levels in those canals were too high the regulators at the outlets of the Melas and interior canals and the Great Central drain were closed. Actually the Melas and Interior canal regulators were scarcely ever shut, but it was when the Great Central drain regulator was closed that the leading-up of the drainage-water from it tended to cause flooding of the lowest land. Paradoxically, it was not the maximum flood-levels which were a danger to the crops. Those floods were of short duration. A minor flood-level, which was liable to occur in February and March, due to a combination of rain and melting snow off the mountains, and to last for a long time, might interrupt the flow of the Great Central drain for days and cause flooding of young crops. It was then that pumping had to be resorted to (p. 300 §).

The drainage-improvement works, combined with the siphon under the Marsh canal, had solved the drainage problem of Division "A" (Fig. 3, Plate 1). Experience as to warping the basin was still small. Water was let into the basin through sluice-gates in the Marsh canal bank, and it was hoped in time to improve the quality of the land by silting. The valuable floods for that purpose were the first floods of early winter, which were not usually high enough to flood much of the basin. The construction of a barrage in the Marsh

Mr. Dean.

canal, suitable for use in winter, was being considered. Examination of flood-water had shown a silt-content as high as 1 part of dry silt to 1,600 parts of water, by weight.

The Emissary canal was pitched with dry stone about 30 centimetres thick throughout its length, except in the deepest part of length of 800 metres at the downstream end. There masonry cement mortar 50 centimetres thick replaced the dry stone pitching in alternate panels about 3 metres wide. No serious trouble had ever occurred in the canal upstream of that length. The stretch in question was through a soil changing from gravel at the top through alluvium to clay at the bottom. Since the deepening had been completed no sign of slipping, such as occurred before, had been observed.

When it was a lake, and during the early years of the drainage works, the Copais had an exceptionally bad reputation for malaria. To-day, although the reputation still held to a certain extent, malaria had ceased to be a serious trouble. As a matter of interest, with reference to Mr. Huntsman's and Mr. Scott's figures for the Salonika Plain, the maximum and minimum shade temperatures recorded in the Copais in 30 years were $113\cdot4^{\circ}$ F. in 1916 and $5\cdot0^{\circ}$ F. in 1921 respectively.

Paper No. 5101.¹

“Fundamental Research on the Application of Vibration to the Pre-Casting of Concrete.”

By DONALD ARNOTT STEWART, A.M.I.E.E.

Correspondence.

Mr.
Broomfield.

Mr. R. E. BROOMFIELD, of Lagos, Nigeria, observed that some people might think that the research as so far conducted might have rather too little reference to actual practice for it to be applicable to actual conditions. It was clear that the properties of concrete as a function of “statical” variants, such as water-content, aggregates, etc., would scarcely depend at all on the size or shape of the mould, and thus laboratory experiments could lead directly to commercial application. Considered, however, as a function of some mechanical movements, that was, “dynamically,” the shape

¹ Journal Inst. C.E., vol. 5 (1936-37), p. 318. (March, 1937.)

and mass would appear to be of considerable effect, and he would be interested to hear that some attempt had been made to consider that point. It would appear that what might be the best frequencies and magnitudes for a 4-inch cube of close-grained concrete might bear little relation to that needed to produce the same effects on a 1-inch flat-slab floor, or on a 3-foot-deep beam with heavy reinforcement.

Dr. E. J. HAMLIN, of Johannesburg, had tried out certain patented commercial vibrators to consolidate the concrete in a reinforced-concrete sewage-storage tank 20 feet by 20 feet by 15 feet high. The vibrators had been stated to have an effective range of approximately 54 inches diameter with the vibrator as centre. On the advice of the suppliers four machines had been used. The concrete proportions by volume were 1 : 2 : 4, with a slump of 2 inches. He was not in a position to state the frequency of the vibrators. When the formwork had been stripped the appearance of the concrete had been very disappointing, portions having been very good, whilst adjacent to such good portions there had been patches where little consolidation appeared to have taken place and the concrete was porous.

He thought that the following might be an explanation of the unsatisfactory results obtained. The energy-waves set up by the vibrators diverged in all directions in the plane of the formwork, similar to the ripples formed on the surface of calm water in which a pebble was dropped. Where there were two or more adjacent sources of exactly similar waves spreading in a plane, there were bound to be places where the crests (or troughs) of one system coincided with the crests (or troughs) of the other. At such places there would be waves with unusually high crests (or deep troughs) and violent agitation in the concrete. At other places, again, the troughs of one system might coincide with the crests of the other and the disturbances might be obliterated. At such places little disturbance in the concrete would result, with consequent poor consolidation. Whilst admitting the advantages established for vibrated concrete, he would like to know whether the Author considered that similar uniformity could be obtained when dealing with large volumes of concrete, and also whether reinforcement would have any effect in consolidation by means of vibration. Further, had the Author taken measures from the vibrated specimens to ascertain whether the density varied with the distance from the source of vibration?

Mr. G. P. MANNING pointed out that the Author had defined the term "amplitude," but had omitted to define what he meant by frequency. Such a definition was urgently required. He had purchased a number of vibrators operated by an eccentrically-loaded

Mr. Manning. rotor. The machines rotated at a speed of 2,800 revolutions per minute and according to his definition the frequency of vibration was therefore 2,800 per minute. The makers, however, claimed that the machines gave a positive and a negative impulse each revolution and that they therefore had a frequency of 5,600 per minute.

The definitions of the terms "amplitude" and "frequency" should be agreed upon, and should be made known to all concerned.

Mr. Marks.

Mr. J. R. MARKS, of Auckland, N.Z., observed that the Author's research had been confined to the application of external vibration (that was, vibration of the whole mould), and that therefore the effect brought out would be helpful mainly to a consideration of the moulding of pre-cast concrete products by vibration (as implied in the title of the Paper), rather than to concrete construction *in situ*, which necessarily involved quite different treatment.

In considering the results of the experiments the particulars of the mix the Author had employed should not be forgotten, as he had not properly indicated. For instance, he had used $\frac{3}{8}$ -inch maximum aggregate, of angular shape, in what was bound to be regarded as an extremely lean mix for that maximum size of stone. Clearly there was no surplus of cement-paste at all over voids in the dry-rodded volume of mixed aggregate, whilst the mix, being far from plastic, could have been hand-placed only by a great amount of hard ramming, so as to pack the aggregate tightly enough to enable the cement-paste approximately to fill the voids.

Mr. Marks thought that it would be helpful to those studying the Paper if more particulars were given of the mix, such as, for instance, an expression of the mix by dry-rodded volumes of sand and stone respectively, to 1 cubic foot (94 lbs.) of dry cement, and also of the "real mix" by volume of dry-rodded mixed aggregate to the same unit of cement. He estimated the latter to have been about 1 : 4, but he had had to make some "scientific guesses" to arrive at this approximation. It would also be of interest to know the respective fineness-moduli of the sand and stone, and their apparent absolute densities. What was the true water/cement ratio of the mix, by weight or by volume, after allowing for absorption in the aggregate particles?

In connexion with *Fig. 4* (p. 326 §), would the Author indicate the comparative density of the hand-packed specimens? It would appear to have been about 146½ lbs. per cubic foot. He noticed that the density curve in *Fig. 4* (p. 326 §), for 6,000 vibrations, agreed with neither that for the first nor the second series in *Fig. 6* (p. 328) nor was it an average of those series. Again, the strength-curve

§ Page numbers so marked refer to the Paper. (Journal Inst. C.E., vol. (1936-37), (March, 1937).)—ACTING SEC. INST. C.E.

Fig. 5 (p. 327 §), for 6,000 vibrations, was different from that given Mr. Marks.

Fig. 6 for the first series. Had there been a further series, or if not, what series was represented in *Figs. 4* and *5*?

Referring to the question of densities (*Fig. 4*) as compared to the probable hand-packed density, it would seem that, at an acceleration of $3g$ and upwards, both frequencies of 3,000 and 6,000 vibrations per minute developed small increases, whilst 12,000 vibrations per minute apparently failed to reach the hand-packed density at an acceleration of about $7g$. In the latter cases it would appear probable that the volume of cement-paste might have been inadequate to fill the voids, particularly at $3g$. Could the Author throw some light upon that question? Might it not be that the mix was just a little too lean to give fairly comparative results in the whole set of experiments? In any case, Mr. Marks suggested that it would be too lean a mix for any manufacturer to risk in the practical moulding of concrete products.

It would also be most instructive to know if the curves for the three respective frequencies would fall in the same order if larger maximum stone (say $\frac{3}{4}$ -inch) were used instead of $\frac{3}{8}$ -inch. It would be interesting to ascertain what actually happened in the cement-paste itself through high-frequency vibration. The closer compaction of the aggregate particles and the occurrence of the three stages observed by the Author (even if only water but no cement were present), could be readily understood. That was bound to reduce the voids requiring to be filled by cement-paste to a small extent. One could also understand that suitable vibration would permit the placing of a mix at very much lower water/cement ratio than would be practicable with hand-placing for the same cement-content. The former would be a factor of economical value only, and a comparatively minor one at that, as indicated by the small differences in density of the concrete. The latter factor (drier mixes) would appear to be the one from which most of the benefit of vibration came. For a given cement-content it was bound to result in stronger concrete, merely by virtue of its permitting the adoption of a lower water/cement ratio in the first place. Alternatively, for a given strength, it was bound to represent an economic factor of considerable value, because it was not necessary to waste cement by providing more cement-paste (of the consistency necessary for that given strength), merely to provide the "workability" factor.

Those views were based upon the assumption that the strength of concrete depended solely upon the quality (not to the quantity) of its binding cement-paste (that was to say, upon the water solidus

Mr. Marks,


cement ratio adopted at the time of mixing), provided that the voids in the aggregate were completely filled by such paste. In other words the strength of concrete was related to the density of its hardened cement-paste, and not to the weight per cubic foot of the actual concrete. In fact, lean weak mixes of hand-placed concrete were normally heavier than rich strong ones, owing to the presence of more aggregate solids, which were normally from 60 to 100 per cent heavier than hardened cement-pastes.

There was no doubt that, from the above considerations, vibratory placing (where such could be employed with certainty of no extraneous or secondary detriments) was bound to have a decided economic value, while, in addition, it reduced shrinkage and crazing defects. Apart, however, from the undoubted benefits to which he had referred above, he would like to know if vibratory moulding improved the resultant strength of a given cement-paste or otherwise. That was to say, did it actually increase the density of the hardened cement-paste?

The increased concrete-densities shown in *Fig. 4* (p. 326 §) were inconclusive on that point, partly because the mix was so lean that they might, perhaps, be attributed to closer packing of the aggregate alone, with the consequent exclusion of more air-pockets and free water-pockets and even the exclusion of more cement-paste. Further, the exclusion of more air- and water-pockets could easily account for the increased strengths shown in *Figs. 5 and 9* (pp. 327 and 331 §). It should be remembered that all cement-paste exudes some excess water during setting, even if allowed to lie perfectly still after placing. That water either found its way to the surface or else became entrapped as globules, ultimately leaving cavities. In either case, however, it definitely separated from the actual hardened paste. The question was, therefore, did vibratory placing actually increase the amount of excess water separating from the cement-paste, or did it only (or even) accelerate the time of its being freed? The interesting fact that the Author had encountered an apparent initial set in his endeavour to find a "rigidity-factor" might suggest that either one or other (or both) of those effects was brought about. Alternatively, was it possible that a "flash set" was developed by heat-generation caused by the vibrations? The latter question seemed well worth investigation. The energy that could create the explosive forces he described in the stage of "redistribution" was bound to be very considerable.

Mr. Marks considered that some tests of high-frequency vibration upon neat-cement mixes at different water/cement ratios would be

Mr. Marks.



VARIATION IN DRY DENSITY AND YIELD WITH WATER/CEMENT RATIO FOR "STAR" BRAND CEMENT.

Mr. Marks.

a useful contribution to the subject, and he suggested that the Author might undertake such tests.

In 1931 Mr. Marks had made a series of tests upon neat cement from which *Fig. 15* had been compiled, showing the yields of freshly mixed and hardened cement-pastes at different water/cement ratios with a normal Portland cement. The set-yields had been tested respectively for undisturbed pastes and for those which had been subjected to late vibration, in the form of tapping the table upon which the containers rested. Those tests had brought out the following apparent facts :—

- (A) That, if undisturbed, the cement ceased giving off excess water after approximately $1\frac{1}{2}$ hour (about $1\frac{1}{4}$ hour for rapid-hardening cement), for all water/cement ratios.
- (B) That early vibration of the form adopted (namely, extreme low frequency but fairly high acceleration) did not appear to hasten the rate at which excess water separated, or to increase the total water given off.
- (C) That, if vibration were commenced at the age of $1\frac{1}{2}$ hour, further separation of excess water occurred, resulting in much denser and proportionately stronger cement-pastes when hardened.

The densities shown in *Fig. 15* represented the weights of dry cement that became incorporated in each cubic foot of hardened cement-paste. To obtain the approximate actual dried-out weight per cubic foot, about 20 per cent. should be added for water permanently retained in chemical combination. Tests made later on concrete mixes in test-cylinders and in slabs showed a gain in strength of about 20 per cent. through similar late vibration.

In the United States the method of concrete-road construction known as the "Johnson Method," in effect adopted that practice with the result that independent and authoritative tests indicated conclusively that 94 lbs. of cement was saved per cubic yard, without reduction in strength.

He referred to those matters, not with regard to the late vibration of pre-cast concrete, but to draw attention to the apparent fact that there was a critical age before which cement-paste might not be tightened by slow vibrations. It might be that high-frequency vibration reduced that age ; otherwise the conclusion would have been reached that it did not tighten the cement-paste, but only permitted the mechanical packing of a drier-mixed concrete.

Mr. Mitchell.

Mr. JAMES MITCHELL observed that on p. 318 § the Author stated

that, as the result of vertical vibration, the force of gravity was periodically neutralized, and that during those neutral periods the particles of the concrete "tend to twist and turn." There was no clue offered, however, to the nature of the force which produced that twisting and turning. Anyone who had observed the effect of striking the shuttering of a mass of concrete horizontally with a heavy hammer, would probably be satisfied that the direction of the vibration had comparatively little to do with the resulting consolidation of the concrete. The effect of the vibration was to set the particles in motion, and thus enable gravity to move the solids downward, while at the same time the upward expulsion of air and excess water was facilitated. On p. 346 § reference was made to the question of whether workability or water-content was the best basis of comparison between concretes. It could not be too strongly emphasized that on the works workability was the more important, water-content being a means toward that end.

On p. 334 § it was stated that "a casting which has been made by vibration is a system of particles precisely adjusted." No system of ramming could produce such a precise adjustment, and the difference between vibration and hand or other ramming was one of degree, and not of kind. It was impossible in practice to prevent a certain amount of segregation, by "segregation" being meant the uneven distribution of the constituent parts throughout the mass of the concrete. Merely churning the materials together in a mixer did not assure that each particle would occupy the most desirable position in the mass. Even if it did, the subsequent operations, before the concrete reached its final position, would disturb any such nice balance. In order to counterbalance that segregation, it was necessary in the mortar to provide a proportion of cement in excess of that just sufficient to fill the voids in the sand, and in the concrete to provide a proportion of mortar in excess of that just sufficient to fill the voids in the stone. Furthermore, in order to produce a proper degree of workability, it was necessary to provide a proportion of water in excess of that just sufficient for the proper setting of the cement. One of the most important functions of the water was to reduce friction between the solids, and thus to facilitate the expulsion of the contained air, thereby promoting the density of the concrete.

With reference to the method of determining the mix used in the tests (p. 348 §), a more proper method would be to find the proportion of cement required to make a mortar of maximum density, and then to determine the proportion of that mortar requisite for concrete of maximum density. With regard to the water/cement ratio, that

Mr. Mitchell.

was not necessarily the best water/cement/aggregate ratio, the latter being affected by the degree of absorption of the aggregates, and the amount of moisture in and on them. In that connexion reference might be made to the remarks, on p. 333, § as to the advisability, in making test-cubes, of having the first portion of concrete to be put into the mould somewhat wetter than that which was to follow. That conformed to good field-practice, the reason being that given by the Author, namely, "the excess water from the lower stratum of concrete will very quickly pass up into the mix thrown in on top of it, which will, in turn, reject what it cannot hold." Where the aggregates were exposed to the contingencies of the weather, as was usually the case, it was obvious that the proportion of water required to make a properly workable concrete would vary very considerably. A heavy thunder-shower might have a disastrous effect on concreting operation. The use of dry concrete was a reversion to an older practice. There was a time when, relying on the results of laboratory experiments, engineers had seemed to vie with each other as to who would use the smallest proportion of water in his concrete. It needed some serious failures to convince them that results that might be obtained in a laboratory were not necessarily characteristic of good field-practice. One of the drawbacks of dry concrete was that it very quickly lost its workability, and therefore did not contain the necessary provision for meeting the various delays between the mixer and the place of deposit which were inseparable from ordinary working-practice. It seemed probable that that might have been the cause of the variability of the strength-results referred to in the Report of the Sub-Committee on Vibrated Concrete (p. 439 ‡). In making comparisons between the relative strengths of dry and wet concretes, it was desirable that tests should be made after a longer period than 14 days—say at 3 months—and there seemed ground for believing that at the end of the longer period the wet concrete would give better relative results.

The Author.

The AUTHOR, in reply, pointed out that Mr. Broomfield would no doubt be able to obtain data regarding the effect of varying the ratio of mould-size and shape to aggregate-size when the further reports of the Building Research Station were published. The Author regretted that he was unable to devote any further time at the present moment to that side of the research.

So far no useful data had been obtained in regard to in-situ work, and some considerable time was likely to elapse before a scientific examination of that aspect of the problem would be made. As was

§ *Ibid.*

‡ Journal Inst. C.E., vol. 5 (1936-37), (March, 1937).—ACTING SEC. INST. C.

pointed out in the Paper, the variables present in in-situ work were The Author. very considerably greater than those in pre-cast work. Again, most in-situ work involved the placing of a very much larger number of cubic feet of concrete than was ever likely to be handled in pre-casting, and hence it was unlikely that the whole of the concrete involved could be given the same acceleration, especially when the vibration was to all intents and purposes applied from a point. Dr. Hamlin found that when using asynchronous vibrators, nodes and antinodes were formed along the shuttering and in the mass of concrete. From the figures supplied it would appear that each vibrator covered an effective area of approximately 15 square feet. Assuming the wall of the tank to be 9 inches thick, the mass of concrete vibrated would be in the neighbourhood of 1,700 lbs. If the vibrators were of the induction-motor type running from a 50-cycle supply they would have a speed of rotation of approximately 3,000 revolutions per minute, and hence they would generate 3,000 vibrations per minute, or 50 per second.

Then from the formula $P = Ma$,

$$\begin{aligned} P &= 1,700 \times \text{amplitude} \times (2\pi f)^2, \\ &= 1,700 \times 4 \times \pi^2 \times 50^2 \times \text{amplitude}. \end{aligned}$$

$$P = 17 \times 10^7 \times \text{amplitude, nearly.}$$

It was clear from that that if the amplitude were of any magnitude greater than about 0.001 inch, the force required would be very considerable. On the other hand, if the amplitude were of that small magnitude at that relatively low frequency the acceleration due to the action of P would be very much less than that due to gravity. The conclusion was that since experiment had shown that accelerations equal to or less than gravity were ineffective in producing consolidation, the vibrations were not capable of covering such large area, or that vibration applied at right angles to gravity bore no relation to that applied in the line of action of gravity. So far there was no reason to believe that such a lack of similarity of effect existed.

Uniform results should be obtainable in consolidating large volumes of concrete both in pre-cast and in-situ work, provided that the technique adopted suited the particular circumstances of mix, etc. Reinforcement, except in exceptional circumstances, that was to say where the natural frequency of a bar coincided with the applied vibration, should offer no difficulty except as regards per-vibrating."

Since the Author's tests had all been carried out on 4-inch cubes and there had been little likelihood of marked damping of the vibration-wave occurring, there seemed no point in taking cores from those cubes. Some rather rough-and-ready tests had been

The Author.

taken of vibration-plant installed by the Author for the building department of the London Passenger Transport Board. Those tests had shown that the vibrations were transmitted vertically over a distance of approximately 14 feet from the point at which vibration was applied. It was, of course, impossible to distinguish between vibration transmitted from the base of the casting vertically, and that transmitted horizontally by friction from the sides of the rigid mould.

Mr. Marks had come to the conclusion that the mix had been lean, which was certainly correct judged from the standpoint of commercial practice. The effect of vibration was, however, to produce an excess of cement-paste, which came to the surface on all sides of the cubes. Experiments carried out later on the production of bricks had shown that a concrete made of 1 : 4 mix by volume and pressed into the moulds would not give as good a strength as concrete made of 1 : 5.5 mix which was vibrated into the mould. The workability of the two mixes was approximately equal. The strength of the vibrated brick was three times that of the pressed brick. The estimate of the volume ratio was very nearly correct, the slight difference being due to the fact that 94 lbs. per cubic foot was an excess of the figure determined for the rapid-hardening cement used in the research. The true water/cement ratio was not affected by absorption, as both the sand and stone used were specially chosen for their non-absorbent qualities, but it was possibly affected by separating-out of the excess water from the mix during vibration, although the water carried with it a certain amount of cement and fines. It was found on analysis that the weight-ratio had increased from 1 : 6 to as much as 1 : 7.5. The density of the hand-rammed cubes varied very considerably, but an average figure would be as Mr. Marks suggested, from 146 to 147 lbs. per cubic foot.

The discrepancy between the density-curves for 6,000 vibrations per minute was due to plotting and drawing each curve separately and not tracing one from the other ; in any case the slight variation was of no consequence. Only those curves shown in *Figs. 1 and 2* (pp. 320 and 328 §) related to the first series of tests. The curve relating to the second series in *Fig. 6* was so marked. The lack of compaction at the lower accelerations and at high frequencies, such as at 12,000 vibrations per minute, was due to lack of kinetic energy (see Table I, p. 319 §).

There seemed to be no way in which a decrease in the setting time of cement-paste could be effected by vibration, since the action of vibration was purely mechanical and consisted in compacting the

solids forming the cement paste, whereas the setting-time of the cement was a function of the surface offered by each particle to chemical action. The Author.

While no actual measurement of temperature-conditions had been taken of the concrete during vibration, it was doubtful if the energy absorbed in overcoming friction between particles was sufficient to cause any but the most minute change in temperature, and hence the hypothesis of "flash set" being caused on that account had to be abandoned.

Mr. Mitchell had pointed out that consolidation could be effected by applying the vibration at right angles to the direction in which gravity acted. It had not yet been demonstrated that the results produced in a given mix of concrete by applying the vibration at right angles to, or in line with, gravitational action were equal or even related. It was safe to suppose that the accelerations given to the particles forming the concrete could possess two components at 90 degrees to each other. That no doubt was what actually did occur, and it was when the force acting vertically tended to zero that the lateral pressure on the walls of the mould was reduced. The concrete, which tended to behave as a liquid, without a liquid's incompressibility factor, would tend to alter its position, and thus each particle which had been slightly compressed would expand against its neighbours, causing the "twisting and turning" remarked upon by the Author. As a rule the water-content, even in the case of very dry mixes, was greatly in excess of that required for proper hydration of the cement. There was no doubt in the Author's mind that the failure of engineers to produce satisfactory results with dry mixes was due to the fact that plasticity of mix was not obtained at placing, and hence proper cohesion between particles never took place.

Paper No. 5087.^{1, 2}

"Flood-Hydrographs."

By BERTRAM DARELL RICHARDS, B.Sc. (Eng.), M. Inst. C.E.

Correspondence.

Mr. J. S. ALFORD thought that every attempt to rationalize empirical formulas was a step in the right direction. It seemed

¹ Journal Inst. C.E., vol. 5 (1936-37), p. 405. (March, 1937.)

² In the Paper, p. 408, line 17, for $v = \sqrt{ds}$ read $v = c\sqrt{ds}$; p. 425, line for $h^{\frac{3}{2}} \times C_6 h = C_7$ read $h^{\frac{3}{2}} + C_6 h = C_7$.

Mr. Alford.

desirable to aim at the establishment of a group of expressions relating to each other, governing on the one hand the estimation of run-off from small urban areas, and on the other hand the flood-discharge from a large catchment. Clearly there was a limit to the size of catchment which could be dealt with in that manner. Where the relation i/I (p. 407 §) was non-existent or practically meaningless the problem passed into the realm of probability.

In the report of the Committee appointed by the Ministry of Health in 1929 on Rainfall and Run-off, rainfall-intensities in relation to time were given for use in normal cases for the design of urban storm-water drainage-systems. The practice had grown up in designing such works as though the rain started suddenly, fell at the precise rate of intensity laid down in the report, and ended suddenly or continued at a greatly reduced rate, although the report was silent on such points. One example of the practice was the use of the area-time diagram. The use of that diagram appeared to obscure rather than to clarify the principal point at issue, which was the determination of the run-off at a given time and place arising from rain falling under ascertained or assumed conditions.

In order to obtain the required result for a catchment served by a main channel with several affluents, it appeared necessary to plot the hydrographs for each affluent or principal affluent. Those having been superimposed suitably in accordance with deferment a covering graph for the main channel could be obtained whose ordinates were the sum of the ordinates of the hydrographs of the affluents. In that way the need of having a record of the whole storm, or alternatively the need of making definite assumptions about the commencement, continuance or falling-off, was forced to the attention of the computer.

Mr. Binnie.

Mr. W. J. E. BINNIE, Vice-President, observed that the Author had considered the question of floods from a theoretical point of view, having taken into consideration the intensity and duration of rainfall, run-off coefficient, extent and shape of drainage-area, and slope of the ground.

The hydrographs which were shown in *Fig. 5* on p. 17 of the Floods Committee's Interim Report¹ represented normal conditions which obtained in Great Britain for upland drainage-areas. Assuming those conditions to be correct, the Author had calculated the maximum intensity of run-off for catchment-areas varying in extent from 1 to 25,000 acres. The curves plotted from his results coincided almost exactly with the curves derived from actual flood

§ Page numbers so marked refer to the Paper. (Journal Inst. C.E., vol. 1936-37), (March, 1936).—ACTING SEC. INST. C.E.

¹ Inst. C.E., 1933.

cords as regarded the maximum rate of flood-discharge between those Mr. Binnie, units of area (*Fig. 3* of the Committee's Report), and the periods taken for the flood to arrive at its maximum intensity, as shown by the hydrographs in the Committee's Report, agreed fairly closely with the calculations. When, however, the catchment-area exceeded 75,000 acres, the Author arrived at a smaller normal rate of flood-discharge by percentages varying from 25 per cent. for a catchment-area of 75,000 acres to 50 per cent. for 450,000 acres. As the diagrams relating the maximum rate of flood-discharge with the extent of the catchment-area contained in the Committee's Report represented normal conditions, exceptional cases would occur where modification was required.

The Paper contained two diagrams (*Figs 4* and *5*, pp. 412 and 413 §) showing how the maximum intensity of flood-discharge and the period required to reach that intensity would be modified by variations in the maximum rainfall, slope of the ground, shape of the drainage-area, and coefficient of run-off. It was not possible, owing to the scarcity of information, to check those diagrams with actual gaugings, but they were based on logical deductions and should prove of service.

Fig. 7 of the Floods Committee's Report gave curves which showed the extent by which the length of the overflow weir could be reduced owing to the "lag" effect of the reservoir, assuming conditions which were illustrated by the hydrographs. Those curves were arrived at by a somewhat tedious process of calculation, and the Author had given formulas in his Paper by means of which the "lag" effect could readily be determined for conditions which differed from those illustrated by the hydrographs in the Committee's Report.

Mr. H. J. F. GOURLEY considered that the Author had evolved two Mr. Gourley, useful diagrams (*Figs. 4* and *5*, pp. 412 § and 413), to show to what extent the period of concentration and the maximum flood were altered by variation in the several factors involved: those diagrams could serve as a guide to engineers having to deal with catchment-areas other than those having the average characteristics assumed by the Floods Committee Report.¹ *Fig. 6* (p. 415 §) showed a close agreement with the normal maximum floods defined by the Committee's curve, and the times of rise of the flood as determined by the Author were in fairly close agreement with those shown in *Fig. 5* of the Report. The Report, incidentally, stated that a variation of 50 per cent. above or below the times assumed in drawing the flood-hydrographs had no material effect on the resultant reservoir-lag. The Author's observations on the somewhat scattered flood-points for the larger areas (as given in *Fig. 4* of the Report) in relation to his

§ *Ibid.*

¹ Inst. C.E., 1933.

Mr. Gourley.

curve for $R = 4$ in *Fig. 10* (p. 420 §), were fair criticism. The Committee had been at a disadvantage in not having rainfall-recon available for those floods, and if the Author's curve were approximately correct—and there seemed to be no reason to suggest otherwise—the consequence would be that the Committee's curve for normal maximum floods on the larger areas, if adopted, would give a larger margin of safety than was intended for such floods.

The method of determining reservoir-lag effect described by the Author was a distinctly useful contribution; it enabled the results to be obtained with relative ease and rapidity and, even if it gave results differing slightly from the more accurate and much more tedious step-by-step process, it had to be borne in mind that the prognostication of the peak rate of inflow was bound itself to be liable to no less error.

Mr. Lacey.

Mr. J. M. LACEY pointed out, with regard to widespread rainfall, that a description of widespread rainfall in Southern India had been given in a Paper by Mr. E. W. Storey,¹ whilst a description had also been given² of the results of a cyclonic storm which had crossed the Coromandel coast near Madras in November, 1903, and of the resultant floods in the Penner river; a description of the floods in the Upper Palar river basin, and of their destructive effect due to the same cyclone of November, 1903, had been given in a further Paper by Mr. E. W. Storey.³ The following Table showed the floods in the Kundair river, a branch of the Penner river,⁴ at the Rajahmundry anicut (situated near Prodatur) in October, 1889.

The catchment-area of the river above the anicut was 2,500 square miles, the length of the main stream was about 66 miles, and the mean width of the catchment was about 38 miles. The rainfall on the catchment-basin from the 14th to the 17th October, 1889 was

Date: 1889.	14th October.	15th October.	16th October.	17th October.
Station.	Rainfall: inches.			
Nandial. .	1.02	6.57	0.63	0.25
Koilkunta .	1.33	0.30	5.20	1.00
Prodatur .	0.35	0.45	1.46	0.10

§ *Ibid.*

¹ "Extraordinary Floods, Southern India: their Causes and Destructive Effects on Railway Works." Minutes of Proceedings Inst. C.E., vol. cxxx (1897-98, Part IV), p. 66.


² J. M. Lacey, "Floods in Southern India." *Ibid.*, vol. clxxi (1907-08, Part I), p. 360.

³ "Description of an Extraordinary Flood which occurred on the 11th November, 1903, in the Palar river, its Cause, and Destructive Effects." *Ibid.*, vol. cciv (1916-17, Part II), p. 410.

⁴ See Minutes of Proceedings, Inst. C.E., vol. clxxi (1907-08, Part I), p. 361.

Nandial was at the source of the river, Koilkunta was about 40 Mr. Lacey. miles above the Rajoli anicut, and Prodatur was south of the anicut. The rain-gauges were read at 8 a.m. every morning, and the amount gauged denoted the rainfall for the preceding 24 hours; thus the rainfall of 6.57 inches on the 15th October at Nandial denoted the rainfall at that station between 8 a.m. on the 14th and 8 a.m. on the 15th October, 1889.

Figs. 12.



Formulas:
 Clear over fall $Q = 3.56 L d^{\frac{3}{2}}$
 Submerged weir $Q = CL \sqrt{2gh} (d - \frac{h}{4})$,
 neglecting velocity of approach

The following Table showed the water register at the Rajoli anicut from the 15th to the 17th October, 1889. The length of the anicut was 964 feet and its height above bed was 6 feet. The zero of the gauges was the base of the anicut (Figs. 12). The figures on that diagram represented the readings at the time of the maximum flood:


Date: October, 1889.	Time.	Gauge reading: feet.		Discharge: cusecs.	Coefficient used: c.	Run off: cusecs. per square mile.	Rainfall: inches in 24 hours
		Above Anicut.	Below Anicut.				
15th	6 a.m.	6.70	4.50	2,000	0.666	0.8	0.03
"	6 p.m.	7.50	4.7	6,305	0.666	2.52	0.094
16th	6 a.m.	9.50	6.50	25,095	0.75	10.00	0.372
"	9 p.m.	18.00	17.00	85,714	0.95	34.28	1.275
17th	6 a.m.	15.00	14.00	63,600	0.95	25.44	0.946
"	6 p.m.	11.00	7.00	39,700	0.70	15.88	0.58

It was difficult from the data given above to correlate the rainfall in the basin with the discharge at the Rajoli anicut. He would assume that the high rainfall at Nandial of 6.57 inches for the 24 hours preceding 8 a.m. of the 15th October had been concentrated about that hour at Nandial; the first high flood had occurred at 8 a.m. at the anicut, giving a period of concentration of 24 hours,

Mr. Lacey.

or a velocity of flow of about 2.7 miles per hour. If the heavy rain fall of 5.20 inches gauged at Koilkunta on the morning of the 16th were considered to have concentrated at Koilkunta that morning it should have reached the Rajoli anicut in $40 \div 2.7$, or in about 15 hours, namely, at 9 p.m. of the 16th, thus resulting in the high flood at the anicut at that time and date. The high flood of 9 p.m. of the 16th was bound, however, to have been partly due to the heavy rainfall at Nandial gauged on the 15th, and the continuing high level on the 17th was bound to have been due to some of the rain gauged at Koilkunta on the 16th. *Fig. 13* showed the rise and fall of the flood at the Anicut, and it might be observed that generally a rising flood-discharge was convex, and a falling one concave.

Fig. 13.



If the mean rainfall on the basin were considered as having been gauged on the morning of the 16th (that was to say, if 2.43 inches were considered as chiefly contributing to the maximum flood at 9 p.m. of that date at the anicut), then the run-off would have been about 50 per cent. of the rainfall, which agreed with the results obtained in Mr. Lacey's Paper,¹ "Floods in Southern India."

The Author, on p. 407 §, gave a formula $\frac{i}{I} \times f(a)$, in which i denoted the average intensity of rainfall, I denoted the maximum intensity of rainfall, and a denoted the area of the catchment. Professor Walsh had given a formula² showing the relation between the

¹ Footnote 2, p. 454.

² *Ibid.*

³ Discussion on "Areas Covered by Intense and Widespread Falls of Rain" by J. Glasspoole. Minutes of Proceedings Inst. C.E., vol. 229 (1929-30, Part I), p. 185.

average depth of rainfall over a storm-area to the maximum fall Mr. Lacey. within that area; had the Author verified that formula?

On p. 408 § the Author assumed t , the time of concentration, to be given by $t = \frac{L}{v}$, and that v was constant; he also assumed that

$= c\sqrt{ds}$, where $d = it$ multiplied by a coefficient K , that was to say, he assumed that the water accumulated on the catchment and did not begin to run off until the time t had elapsed.

Floods were the result of rain falling on the ground faster than it could run off; it was possible that as the period of rainfall increased the depth of flow off the ground would increase, but it would rarely reach the value it , which was the state when the rate of fall equalled the rate of run-off.

Mr. G. E. LILLIE observed that for the purpose of his problem, Mr. Lillie. the Author started with two fundamental principles which might be accepted without reserve.

Mr. Lillie would state them in the following way:—

The average intensity of rainfall (i) over an area was an inverse function of the size of that area, and (ii) at any moment during a storm was an inverse function of the time the storm had lasted up to that moment.

Then followed two assumptions which needed consideration:—

- (i) that for the purpose of the Paper the rainfall was uniformly distributed over the area, and
- (ii) that the maximum flood occurred when the whole catchment area was contributing.

In practice the rainfall was never uniformly distributed, and, if the catchment-area were considerable, the storm might well have passed altogether before water from the remote parts arrived and the whole catchment was contributing. Nor was it obvious that even in cases of full contribution a greater rate of discharge might not have been attained before full contribution was established. The question therefore arose whether any great error would result from the Author's assumptions, when used in the somewhat limited cases involved in reservoir-work, for the purpose of preparing formulas for practical application.

The circumstances in which a record discharge might be expected were when a severe storm was centred over the discharge-point (that is to say, over the point where the water entered the reservoir) over the river or main stream feeding the reservoir. Possibly the effect would be even greater if the centre of the storm were over

Mr. Lillie.

the river, and the storm itself were moving down the river to the reservoir at about the same rate as the river was flowing.

In such a case the contribution from the remoter parts of the catchment would be comparatively small, for several reasons, which two were those implied in the Author's fundamental principles: (i) the intensity of precipitation of rain on elements of area remote from the centre of the storm was an inverse function of the distance away, and (ii) as it would take time for water from those remote parts to arrive at the discharge-point and the intensity of the storm was subsiding, the rate of precipitation at the centre would have diminished before that water from the remote parts had begun to arrive.

Mr. Lillie thought that that made it clear that the importance of an element of area in contributing to the maximum rate of discharge was an inverse factor of its distance from the discharge point. That was the fundamental fact underlying the deduction contained in his Paper on the discharge from catchments,¹ and

was expressed in the integral $\int \frac{dw}{y}$ which gave the sum of the values

of the elements of area over the whole catchment. The Author was, however, dealing with only small catchments which might be taken as being within the ambit of a single storm, and hence it was possible that the simplification of the problem attained by the Author's assumption was permissible.

It would be interesting, therefore, to compare the results obtained by the Author's methods and those arrived at by calculations with Mr. Lillie's formula given in the above-mentioned Paper. The formula for small catchments was simply $4\Sigma(\theta L)$, θ denoting the included angle and L the radius of various approximate sectors in which the catchment was divided for calculation. Before working out those figures, however, it was necessary to make one or two remarks in order that the comparison might be reasonably interpreted.

In the first place, the Author in *Fig. 10* (p. 420 §) contemplated catchments as large as 700 square miles in area. Those were much above the size of catchment to which the Author's formulas and those of the Floods Committee could reasonably be applied, but Mr. Lillie noticed that the Table in the Appendix to the Paper did not contemplate catchments of more than 40 square miles.

Secondly, the curve given by the Committee connecting the average intensity of rainfall over catchment-areas of various sizes with the

¹ "Discharge from Catchment-Areas in India, as affecting the Waterways and Bridges." Minutes of Proceedings Inst. C.E., vol. cxcvii (1923-24, Part I), p. 296.

§ *Ibid.*

reatest spot-intensity, and the similar curve¹ given by Col. Sir Gordon Mr. Lillie. earn, were logarithmic curves, neither having any mathematical origin but being empirically produced from observation. They were probably correct. Both were curves showing the average intensity of rainfall in maximum storms over areas of various sizes. On very small catchments, however (and that was the point to be remembered), the water could run off as fast as it fell, and as it obviously could not run off faster, those curves were themselves curves of maximum rate of discharge for very small catchments, say 2 square miles in ordinary country or 4 square miles in steep and mountainous catchments.

TABLE I.

Area of catchment :		Rate of discharge by Lillie's formula :		Rate of discharge by Author's formula :		Remarks.
Thousands of acres.	Square miles.	Cusecs.	Cusecs per 1,000 acres.	Cusecs per 1,000 acres.		
				R = 4.	R = 8.	
2	3.1	5,131	2,565	1,000	2,700	} Author's Fig. 6.
4	6.2	7,420	1,855	800	2,200	
8	12.4	10,500	1,310	600	1,600	
12	18.6	12,810	1,068	480	1,350	
16	24.8	14,700	920	405	1,170	
20	31.1	16,240	810	370	1,020	
25	39	18,620	745	300	870	
30	46.8	20,300	677	280	800	
50	78	26,600	532	200	600	} Author's Fig. 10.
100	156	36,750	367	140	430	
150	234	44,800	299	120	360	
250	390	58,100	232	80	285	
350	546	73,500	210	75	250	
450	702	91,000	202	65	220	

Accordingly, Mr. Lillie gave in Tables I and II the figures for the maximum rates of discharge calculated by his own, the Author's, and Lillie's formulas, the latter being $Q = 640A(4 - \log A)$, in which Q was in cusecs and A was in square miles. The information for very small areas was, he thought, particularly useful.

In the third place, the maximum rate of discharge was affected by the velocity of flow over the catchment, that was to say by the slope

¹ Fig. 3 (p. 273), in "The Effect of Shape of Catchment on Flood-Discharge." Minutes of Proceedings Inst. C.E., vol. ccxvii (1923-24, Part I).

Mr. Lillie.

of the country. Accordingly, the Author assumed an average slope which he took from the Floods Committee's Report.

Mr. Lillie's formula was for the area of flood-section at the moment of the maximum rate of discharge, and that flood-section was not affected by the slope of the country. In order to get the corresponding figure for the maximum rate of discharge, it was necessary to multiply by the velocity (which was naturally affected by the slope of the country), and accordingly a reasonable average velocity had to be assumed, in the same way as the Author took an average slope. Mr. Lillie had taken V as 7 feet per second.

TABLE II.—CASE OF VERY SMALL CATCHMENTS BY HEARN'S FORMULA.

Area : square miles.	Rate of discharge :		Remarks.
	Cusecs.	Cusecs per 1,000 acres.	
0.25	860	5,380	See the remarks above with regard to Hearn's formula. Except in steep mountainous country it is inapplicable above 2 square miles, and above this area it begins to give too large results for the discharge, with a quickly increasing error.
0.5	1,500	4,690	
1	2,560	4,000	
2	4,230	3,300	
3.1	5,690	2,840	This figure is too large.

Fourthly, in all but the smallest areas, up to say 2 square miles the shape of the catchment made a difference, and he had assumed a catchment of breadth about one-half of its length—namely, Type of *Fig. 9* (p. 315 †) of his Paper. If the breadth were equal to the length the discharge-rate would be some 10 per cent. greater on a 20-square-mile catchment, and 25 per cent. less if the breadth were only one-quarter of the length.

The figures in columns 4 and 6 of Table I should be compared.


The figures given in column 4 of Table I were plotted, together with the Author's *Figs. 6* and *10*, in *Figs. 14* and *15* (p. 462).

From *Figs. 14* and *15* it would be noticed that the curve for Indian conditions (which was well authenticated) lay wholly between the Author's two curves for $R = 4$ and $R = 8$, but nearer to the latter. The Indian curve seemed likely to cross the Author's curve for $R = 8$ for catchments larger than 700 square miles, but Mr. Lillie did not think that the Author's curves were admissible for catchments of 700 square miles; nevertheless, there was no doubt that it would

† Minutes of Proceedings Inst. C.E., vol. cxcvii (1923-24, Part 1), p. 315.

cross it somewhere, for it was certain that from large catchments of Mr. Lillie, some thousands of square miles the maximum rate of discharge in India would be much greater than in England.

Fig. 14.



In the Correspondence on Dr. John Glasspoole's Paper¹ he had given for comparison the figures for the Thames (which had a catch-


¹ "The Areas Covered by Intense and Widespread Falls of Rain." Minutes of Proceedings Inst. C.E., vol. 229 (1929-30, Part 1), p. 137.

Mr. Lillie.

ment of 5,300 square miles) and the corresponding figures for Indian rivers of the same area of catchment in districts where the annual rainfall was about the same as in England. The Indian figures were five times as much as those for the Thames. There was no doubt that the maximum rate of discharge from large Indian catchments was always much greater than the corresponding figures in England, and the reasons were not far to seek.

The action in large and small catchments was, however, quite different, and it did not follow that small catchments should be expected to show greater discharges in India than in England simply because large catchments did.

Fig. 15.



As stated above in connexion with Hearn's formula, the maximum rate of discharge from a very small catchment was the same as the maximum total rainfall on it. It followed that, in the limit, the maximum possible rate of discharge was the same as the maximum possible spot-intensity of rain, and would occur on the smallest conceivable catchment; from that up to 2 square miles the discharge would be the same as the rainfall, and above that again the runoff would be less than the rainfall.

How did the maximum spot-intensity of rain in tropical countries compare with the same figures in England? He could see no reason why it should be different; the phenomenon was the same and the weights of air and water were the same all over the world. In India 4 inches per hour on one spot had been recorded fairly often, and those

ates had lasted for an hour or more ; probably greater intensities Mr. Lillie. had happened and had passed unrecorded.

Dr. Glasspoole's Paper quoted many severe cases of extreme spot-intensity in London, from which Mr. Lillie cited the following. On 5th May, 1915, and on other dates, 10 inches per hour lasting only 2 minutes, 6 inches per hour lasting 5 minutes, 6 inches per hour lasting 10 minutes, 5.5 inches per hour lasting 20 minutes, 4.68 inches per hour lasting 30 minutes and 2.2 inches per hour lasting $1\frac{1}{2}$ hour. It was, he thought, abundantly clear that the spot-intensity could be as great in England as in India, for it might be added that quite as severe falls occurred in the country districts in England as in London, but had not been so carefully recorded. Similarly, in India the intense falls were not confined to the wet districts, or indeed to any districts, as some of the most severe records came from the Sind desert.

It seemed probable enough that the maximum spot-intensity was the same all over the world, although the fall might last longer in the tropics. It followed from that that the maximum rate of discharge from very small catchments might be solved for universal application, and that conclusion was supported by the curves in Fig. 14.

He also believed that the gradient of the intensity-curve from the centre of the storm outward was much the same everywhere ; in consequence, for small catchments up to say 40 square miles, the records of discharge would not be greatly different in the tropics. Above that figure the fact that storms lasted longer would make the tropical figures greater and greater in proportion to figures for Great Britain, until, in very large catchments, the disparity was considerable.

That fact was of great importance and ought to be recognized ; it meant that for small catchments the maximum rates of discharge might be taken to be the same everywhere, and they were stated in Tables I and II. The slope and the shape of the catchment remained as local factors, however, and would affect the rate of flow, but even that would not affect the maximum rate of discharge in small catchments below 2 square miles.

Mr. P. J. ROBINSON agreed that the factors affecting floods were Mr. Robinson. so varied and complex that no precise mathematical computation was possible. There was no need, therefore, for hesitation in adopting approximations that led to simplification in the formulas.

The form of the fundamental expression $I = \frac{R}{T+1}$ was somewhat unfortunate, since it led to an equation of the third degree for the valuation of t .

Mr. Robinson. For values of T greater than 1 hour, when $R = 4$, I could be closely represented by

$$I = \frac{2.3}{T^{0.770}}$$

Similarly, the factor $f(a)$, for areas greater than 2,000 acres, could be represented by

$$f(a) = \frac{1.08}{a^{0.115}}$$

Equation (1) (p. 408 §) could, therefore, be written

$$i = \frac{2.484}{T^{0.770} a^{0.115}} \quad \dots \quad (1a)$$

Substituting in the Author's formulas for the period of rise of the flood, and putting $L^2 = Ma$, where

$$M = \frac{n + \frac{1}{4n}}{0.64},$$

equation (2) became

$$t = 0.665 \left(\frac{MC}{Ks} \right)^{\frac{1}{2.23}} \cdot a^{\frac{1}{4}} \quad \dots \quad (2a)$$

With $K = 0.6$, $s = 0.03$, $n = 1.67$, $C = 0.014$, $M = 2.843$, it resulted in

$$t = 0.95a^{\frac{1}{4}}$$

Assuming that K was constant during the whole period of the flood, the total effective precipitation (that was, the amount of rain that ran off as flood-water) was Kit .

Substituting in (1a) the value of t from (2a), and calling the effective precipitation V , the result expressed in inches of rain was

$$V = 2.261 \left(\frac{MC}{s} \right)^{0.1} \cdot K^{0.9} \quad \dots \quad (3a)$$

or by volume, since 1 inch of rain on 1,000 acres = 3.63 million cubic feet,

$$V = 8.207 \times 10^6 \left(\frac{MC}{s} \right)^{0.1} \cdot K^{0.9}$$

With the values for the factors as previously assigned;

$V = 1.47$ inch of rain, or $5\frac{1}{3}$ million cubic feet per 1,000 acres.

With regard to the maximum intensity of flood discharge Q_m , some confusion appeared to have arisen. The quantity 1,000 K

in equation (3) (namely, $Q_m = 1,000Ki$), was a function of the rain- Mr. Robinson.
fall and represented the mean rate of effective precipitation expressed
in cubic feet per second per 1,000 acres of catchment. The peak
rate of flood-discharge depended on the shape of the hydrograph;
and that in turn depended on the characteristics of the catchment-
area. For certain specific shapes of hydrograph, equation (3a) held
good, but as a general expression for Q_m it was incomplete.
The general expression for Q_m was as follows:—

let A_2 denote the whole area of the hydrograph.

„ A_3 denote the area up to the end of time t .

Putting $A_3/A_2 = f_R$, then $1,000Kit = A_2 = A_3/f_R$, since the whole
area of the hydrograph was bound to represent the total run-off.

But $A_3 = Q_m f_s t$, where f_s was the ratio of the mean rate of discharge
during the time t to the peak rate of discharge.

Therefore, $1,000 Ki = Q_m \frac{f_s}{f_R}$.

Putting $1,000 Ki = Q_R$,

$$\text{then } Q_m = Q_R \frac{f_R}{f_s} \quad . \quad . \quad . \quad . \quad . \quad (4a)$$

If Q_m were equal to Q_R , $\frac{f_R}{f_s}$ was bound to have a value of unity. With
triangular hydrograph symmetrical about the vertical through the
peak, $\frac{f_R}{f_s} = 1$, and in general with an unsymmetrical hydrograph, it

was possible in certain cases for $\frac{f_R}{f_s}$ to equal unity.

Taking the Author's equations (4) and (5) for the growth of the
flood, and assuming, as he had done in *Fig. 3* (p. 411 §), that the
catchment was rectangular in shape, (4) might be written

$$Q_1 = Q_m \frac{rb}{Lb} = Q_m \frac{r}{L}$$

hence
$$Q_1^2 = Q_m^2 \frac{r^2}{L^2} \quad . \quad . \quad . \quad . \quad . \quad (5a)$$

But, from (5), $\frac{r^2}{L^2} = \frac{t_1^3}{t^3}$. Substituting in (5a),

$$Q_1^2 = Q_m^2 \frac{t_1^3}{t^3}, \text{ and } Q_1 = Q_m \frac{t_1^{\frac{3}{2}}}{t^{\frac{3}{2}}}$$

Mr. Robinson. Integrating between the limits $t_1 = 0$ and $t_1 = t$ for the part area of the hydrograph,

$$A_3 = \frac{Q_m}{t^{\frac{3}{2}}} \int_{t_1=0}^{t_1=t} t_1^{\frac{3}{2}} dt = \frac{2}{5} Q_m t.$$

As the hydrograph was symmetrical, $f_R = \frac{1}{2}$ and $\frac{f_R}{f_s} = \frac{\frac{1}{2}}{\frac{2}{5}} = \frac{5}{4}$,
5

whence $Q_m = \frac{5}{4} Q_R$.

As a further example, a trapezoidal hydrograph similar to *Figs. 1* (p. 423 §) could be taken. In that figure the initial storage was represented by the rectangular area *OADS*.

If the percentage initial storage had to equal $100 \frac{\frac{1}{2} t_2}{\frac{1}{2} t_2 + t_3}$, it could be proved that, when $t_3 = t_1$, the ratio

$$\frac{t_2}{t_1} = \frac{\sqrt{(1+8\epsilon)} - (1-4\epsilon)}{2(1-\epsilon)}$$

where $\epsilon = \frac{r}{1-r}$, and $r = \frac{Q_o}{Q_m}$.

When $\frac{Q_o}{Q_m} = \frac{1}{10}$, $\frac{t_2}{t_1} = 0.46$, and with that ratio established it could

be shown that $f_R = \frac{1.01}{1.56}$ and $f_s = \frac{1.01}{1.46}$; consequently $\frac{f_R}{f_s} = 0.936$.

The Floods Committee's hydrograph for an area of 40 square miles, exclusive of the initial flow, had an $\frac{f_R}{f_s}$ value of 0.48.

Fig. 16 showed the relative values of Q_m for four hydrographs of equal area of the forms dealt with above, the hydrograph conforming to that of the Floods Committee being chain-dotted.

With the values of i and t from (1a) and (2a),

$$Q_R = \frac{3,428}{a^{\frac{1}{2}}} \left(\frac{s}{MC} \right)^{0.845} \cdot K^{1.845} \dots \dots (6a)$$

or with $K = 0.6$, $s = 0.03$, $n = 1.67$, $C = 0.014$, and $M = 2.843$,


$$Q_R = \frac{1,564}{a^{\frac{1}{2}}}.$$

The close agreement shown in *Fig. 6* (p. 415 §) between the curve Mr. Robinson, marked $Q_m : a$ (from formulas) and the Floods Committee curve was illusory. The former curve was actually a curve of Q_R , whilst the latter was an empirical curve of Q_m based on actual records.

The Floods Committee stated in their Interim Report¹ that their simplified flood-hydrographs represented total run-offs (exclusive of initial flow) ranging from 80 to 90 per cent. of 3 inches of rainfall.

The Bransby Williams formula for t , adopted by the Floods Com-

Fig. 16.



mittee, could be written $t_{20} = 1.13a^{0.4}$. Accordingly, for $a = 25.6$ (40 square miles) the value of Q_R was $\frac{2,400}{1.31 \times 25.6^{0.4}} = 583$ cusecs, which was nearly double the Author's value, whilst for $a = 1.28$ (2 square miles) it was 2,180 cusecs.

The former of those two values of Q_R was identical with the theoretical value given by $K \frac{4}{t_m + 1} \cdot f(a)$ with $K = \text{unity}$, and the latter was about 450 cusecs in excess of that value.

It was axiomatic that the area of the hydrograph was bound to represent the run-off. Taking the Author's own formulas for a catchment-area of 26,000 acres with a period of concentration of 4.75 hours, the effective precipitation was 1.425 inch of rain, or a run-off of 5.173 million cubic feet per 1,000 acres. The corresponding hydrograph (*Figs. 11*, p. 423 §), had an area, inclusive of the initial

§ *Ibid.*

¹ Inst. C.E., 1933.

Mr. Robinson. storage, representing about 5.45 million cubic feet. As the rainfall that produced the initial flood was to be included in the total amount of rainfall, the area of the hydrograph was in excess of the theoretical run-off. The volume for the triangular hydrograph with no initial flood was not stated in the Paper, but from the examples given in the Appendix it appeared that it had been taken at about 3.8 million cubic feet. It was thus deficient to the extent of at least 1.3 million cubic feet, or by about 20 per cent.

The hydrographs shown in *Figs. 7 and 8* (pp. 416 and 417 §) were similar to *Figs. 11*, and had like discrepancies, and the Author's arguments with regard to their shape did not appear to be sound.

In the Floods Committee's Interim Report overflow-weirs were divided into two classes, A and B. Class A weirs were of a length to discharge the peak rate of inflow with the selected head on the weir, whilst Class B weirs were of a length to discharge the peak rate of outflow with the same head allowing for the full cumulative effect of lag. The ratio of Class B lengths to Class A lengths could be denoted by m , and that ratio was equal to the ratio of the peak rate of outflow (or weir-discharge) to the peak rate of inflow.

As he had pointed out in a recent article,¹ the value of m depended entirely on the shape of the flood-hydrograph and the volume of temporary storage above weir-level at the peak of the weir-discharge, and could be arrived at without reference to specific values of weir length, coefficient of discharge, or reservoir-area.

The value of Ph , P being the percentage reservoir area, was a measure of the amount of temporary storage, and, in his opinion, the most satisfactory method of exhibiting the lag-effect was to show values of m against values of Ph . If a comparison for differing hydrographs, or of differing methods of evaluation, were to be made, the comparison, to be a true one, ought to be made for the same value of Ph .

The Author's formulas (1) and (3) of Part II of the Paper could be combined and reduced to the following, which was in a form convenient for graphical solution :

$$Z^{\frac{2}{3}} = \frac{435,600}{A} \cdot \tan \theta \cdot r^{\frac{2}{3}} (1 - r) \cdot Ph$$

$$+ Z \left[\tan \theta (1 - r) \left(1 - \frac{435,600}{A} \cdot Ph \right) + r \right] \quad \dots \quad (7a)$$

where $Z^{\frac{2}{3}} = m$ and $r = \frac{Q_0}{Q_m}$.

§ *Ibid.*

¹ "Reservoir Lag," *Engineering*, vol. cxxxvii (1934), p. 422.

With no initial flood and a triangular hydrograph, (7a) reduced to Mr. Robinson.

$$m = 1 - \frac{435,600}{A} \cdot Ph \quad . \quad . \quad . \quad (8a)$$

which was the equation of a straight line.

He had pointed out in his article in *Engineering*¹ that if a definite hydrograph applicable to one catchment were taken as a type, and the hydrograph for any other catchment-area were derived from that type (by multiplying all the ordinates of the type by the ratio of the peak rate of inflow for the catchment under consideration to the peak rate of inflow of the type, and all the time-intervals of the type by the inverse of that ratio), then, under those conditions of relative shape and constant area, the value of m corresponding to any given value of Ph became a constant for all catchment-areas; it was, therefore, only necessary to derive m for the type hydrograph.

For that to hold, it had to be assumed that the characteristics of the catchments were similar; granted that that was so, expressions put forward above for t and Q_m showed that

$$\frac{Q_{mc}}{Q_{mT}} = \frac{Q_{Rc}}{Q_{RT}} = \frac{a_T^{\frac{1}{2}}}{a_c^{\frac{1}{2}}},$$

and

$$t_c = t_T \frac{a_c^{\frac{1}{2}}}{a_T^{\frac{1}{2}}} = t_T \frac{Q_{mT}}{Q_{mc}}.$$

Further, the effective precipitation given by (3a) was independent of the area of the catchment, and from that equation it followed that for all catchments having the same characteristics the areas of the hydrographs would be equal.

It would be seen that the Author's equations in the form given in (7a) and (8a) above agreed with the preceding postulate concerning the value of m ; indeed, (8a) went much further: it stated that all triangular hydrographs, no matter of what form, would give the same value of m for a given value of Ph , provided that the areas were equal.

The values of m derived from (7a), with $A = 4,567,000$ cubic feet, an $\theta = 1.246$, and $r = \frac{1}{10}$, as in the example on p. 426 §, were shown in Fig. 17 (p. 470) by curve (1). That curve cut the horizontal through $m = 1$ at a Ph value of 2.64. Below that value of Ph the Author's approximate equations could not be applied, for it was impossible for m to have a value greater than unity. The curve evaluated by the step-by-step method would give unity value for m at zero value of Ph .

Curve (5) of Fig. 17 was derived from equation (8a) with $A = 3,800,000$ cubic feet. Curve (6) was the curve shown in Fig. 4 of


¹ *Loc. cit.*

§ *Ibid.*

Mr. Robinson, a Paper that he had contributed to The Institution,¹ replotted against Ph values. That curve had been derived from a triangular hydrograph representing a total run-off of 3.3 inches of rain by the method of graphical integration advanced in that Paper.¹

Curve (7) was derived from (8a) with A equal to 3.3 inches of rain, a comparison of the approximate method of the Author with the more strict method of graphical integration was thus afforded.

Fig. 17.



Curves (2), (3), and (4) were those given in Fig. 7 of the Flood Committee's Interim Report, for permissible heads of 2, 3, and 4 feet replotted against Ph values.

It might be remarked that for the specific examples dealt with in the Appendix to the Paper, the values of m might be derived from the figures there given, for

$$m = \left(\frac{h}{h_m} \right)^{\frac{3}{2}} = \left(\frac{\text{Col. 8}}{\text{Col. 11}} \right)^{\frac{3}{2}}$$

and $Ph = \text{Col. (5)} \times \text{Col. (11)}$.

The Author.

The AUTHOR, in reply, thought that formula (2) on p. 408 § required some further elucidation, as appeared evident from Mr. Lacey's remarks. With the hypotheses taken, if t denoted the time of concentration, $t = \frac{L}{v}$, where v denoted the average velocity of flow at the point of concentration, the actual velocity gradually increased.

¹ "The Effect of Reservoir-Area on the Discharge of the Overflow Weir." Selected Engineering Paper No. 118, Inst. C.E., 1931.

§ *Ibid.*

from 0 to v_{\max} . Also $v_{\max} = c\sqrt{ds} = c\sqrt{Kis}$, and the average velocity was two-thirds of v_{\max} . The Author.

$$\text{Hence } t = \frac{L}{\frac{2c}{3}\sqrt{Kis}} \quad \text{whence } t^3 = \frac{9L^2}{4c^2Kis} = \frac{CL^2}{Kis}, \quad \text{where } C = \frac{9}{4c^2}.$$

The factor $\frac{9}{4}$ was not shown in the Paper, but it had been used in the determination of the values of C given on p. 414 §.

Doubts appeared to exist as to whether the formulas of the Paper could be applied to large catchments. The Author had used the records of British floods to check his formulas, as the Flood Committee's Report gave all the coefficients necessary except K , for which he had taken 0.6 as a reasonable value. He had attempted to check the formulas against records of major floods elsewhere, but since such records as he had found did not specify the coefficients, it was impossible to do so satisfactorily. By assuming probable coefficients, a reasonable measure of agreement was found between actual and estimated flood-intensity, but a formula could not be verified on such assumptions without more definite knowledge of the catchment. While, therefore, he could not claim to have proved the formulas as applicable to large catchments, as a personal expression of opinion he thought that they were so.

Mr. Lillie assumed that the Author only intended the formulas to apply to small catchments and cited the Table in the Appendix (pp. 430 and 431 §) as evidence. That Table had, however, been introduced solely to illustrate the method of estimating reservoir lag-effect.

Mr. Lacey had given some very useful data with regard to a big flood on the Kundair river, from which all the coefficients except s could be deduced. They were $K = 0.5$, $a = 1,600 \times 1,000$ acres, $R = 8$, and $L = 66$, giving $n = 1.7$, and $C = 0.0107$. For s the Author assumed 0.01. Taking $f(a) = 0.60$, as it would be approximately if the curve in *Fig. 1* (p. 407 §) applied to India, the maximum flood and period of concentration deduced from the formulas were 35,600 cusecs and 44 hours. The actual record of the flood showed 35,714 cusecs and some time greater than 39 hours.

Whilst agreeing with Mr. Lillie that a storm might cover only part of a large catchment, he would point out that the object of the formulas was to estimate the probable maximum flood-intensity, and that that was obtained with high values of R . Such high values were produced by long-continued heavy rainfall rather than

The Author.

by intense storms of short duration; long-continued rainfall was generally widespread and would cover a large catchment-area. In the formulas the average intensity was made a function of both area and time of concentration; that was to say, a theoretical average intensity was taken of a storm of area equal to that of the catchment and of duration equal to the time water would take to flow from the most distant part of the catchment to the point of concentration.

It might be argued that, with a high value of R , a small part of the catchment might give a higher flood-intensity than the whole catchment, and that point he had dealt with in considering the limit of maximum flood-intensity on p. 417 §.

Mr. Lillie had shown curves of maximum flood-intensity for Indian conditions in comparison with those in *Figs. 6 and 10* (pp. 41 and 420 §). The latter curves, however, represented particular curves for a specified class of British catchments with given coefficients. Variation of any one of the coefficients R , K , s , or n , would modify those curves, so that they were really representative of a long series of curves. It was difficult to believe that the conditions of catchments over so large a country as India could be standardized to one curve. To do so was in fact to make flood-intensity a function of the area of the catchment only. That was the weak point of the well-known Dickens formula, and engineers in various parts of India had endeavoured to correct that by varying the constant to suit their particular districts. In fact, they merged all the variable but area into one variable coefficient. The object of the Author's formulas was to provide separate coefficients for the various factors affecting flood-intensity.

Mr. Lillie pointed out the fact that the Thames catchment gave flood-intensity of only one-fifth of what might be expected from Indian catchments of similar area and annual rainfall. The Author suggested that the explanation might be found in the higher value of R given by the more prolonged Indian rainfall, and possibly also by a difference in the coefficient K .

With regard to Mr. Robinson's argument that the quantity 1,000 K of formula (3), p. 409 §, did not represent maximum flood-intensity the Author thought that the answer to that lay in the explanation of the derivation of i .

The evaluation of t from formula (2) presented no difficulty if curve of $\frac{t^3}{t+1}$ against t were plotted; the formulas were very simple to handle, and he doubted whether anything was to be gained by transforming them into the alternative forms suggested by Mr. Robinson

CORRESPONDENCE
ON PAPERS PUBLISHED IN
APRIL 1937 JOURNAL

Paper No. 5120¹.

“West Middlesex Main Drainage.”

By DAVID MOWAT WATSON, B.Sc., M. Inst. C.E.

Correspondence.

Mr. J. S. ALFORD asked if the Author would supplement his description by adding to the illustrations a longitudinal section or profile diagram of one of the siphons, preferably the Brent siphon, as the Minutes of Proceedings contained but little information on the subject of the conveyance in inverted siphons of liquid containing solids in suspension. Mr. Alford.

Mr. W. E. BUSH, of Brisbane, remarked on the growth of population shown, and the maximum and average densities to be provided for, as indicating the great problem entailed by the aggregation of population in large cities. Mr. Bush.

The Paper emphasized also the desirability of the unification of various local interests and the need for wide vision and wise control, unfettered by artificial boundaries, in dealing with the development of all community undertakings.

Whilst it was obviously impossible to give details of all fixtures, he suggested that it would be an advantage if, as a supplement to the diagram shown in *Fig. 18* (p. 503 §), a Table or vertical section could be given showing the entry and draw-off levels of the various tanks, screens and chambers. Would the Author also state the depth of wet sludge that it was proposed to deposit on the drying beds, and the estimated, or, if figures were available, the actual, shrinkage allowed for, and the average period of drying? The different types of backdrops by pipe, ramp, spiral and straight cascades were interesting, but it would appear that, unless there was some special reason for the adoption of other types, the pipe cascade was the best one to instal.

Finally, he would like to learn how the method of natural ventilation was operating in practice. It was assumed that interceptor-

¹ Journal Inst. C.E., vol. 5 (1936-37), p. 463 (April, 1937).

§ Page numbers so marked refer to the Paper.—ACTING SEC. INST. C.E.

Mr. Bush.

traps existed on all the house connexions to the sewers draining into the scheme, and that those sewers were more or less naturally ventilated.

Mr. Eddy.

Mr. HARRISON P. EDDY, of Boston, Mass., observed that the characteristic which impressed him as being most unusual in the scheme was the rapidity of the growth of the tributary population involving as it did radical increases in plant during the design and construction stages, to provide capacity at the outset of operation which could not have been anticipated at the inception of design. It was interesting to note that the Act of Parliament, under which the works had been constructed, had made provision for the effluent from the sewage-treatment plant "to contain not more than 3 parts per 100,000 of suspended matter, and to take up not more than 5 parts per 100,000 of dissolved oxygen, in 5 days at a temperature of 65° F." That an effluent of such high quality could be produced was shown by the record of the North Toronto activated-sludge plant in Toronto, Ontario. For the year 1936 the suspended solids in the final-tank effluent averaged 0.8 parts in 100,000, with a maximum average for 1 week of 2.8 parts in 100,000. The 5-day biochemical oxygen demand of the effluent averaged 1.4 part in 100,000 for the year, with a maximum average for 1 week of 2.4 parts in 100,000.

The method adopted for de-watering the sludge at Perry Oak was of interest because in the United States the trend in sludge drying facilities seemed to be away from drying beds and toward mechanical de-watering, as exemplified by the chemical-precipitation plant at Dearborn, Michigan, the new Calumet activated sludge plant at Chicago and the plain sedimentation-plant for the District of Columbia. Among the reasons for that trend were the slowness with which many sludges gave up entrained water and the consequent large area of drying beds required to de-water a given quantity of sludge, as well as the high moisture-content of the "dried" sludge, particularly the highly colloidal sludge from chemical precipitation or the activated-sludge process, whether digested or not.

The loading in lbs. of solids dried and removed per square foot of bed-area in a unit of time was probably the most useful expression of the work performed by a drying-bed area thus far developed although it had not been employed widely. Messrs. Rawn, Banta and Pomeroy¹ reported that at the activated-sludge plant of the Los Angeles County Sanitation Districts near Harbor City, California, sludge dried at the rate of 663 short tons per acre per year on open

¹ A. M. Rawn, A. P. Banta and Richard Pomeroy, *Civil Engineering*, vol. 6 (1936), p. 172.

sand-beds. That was equivalent to an annual average of 0.083 lb. Mr. Eddy. of solids per square foot daily. At that plant, primary sludge and excess activated sludge, seeded with about 20 per cent. by volume of digested sludge, were subjected to multiple-stage digestion before being discharged upon the sand-beds, where the sludge was usually dried to a moisture-content of about 50 per cent. The warm climate of southern California was naturally favourable to the use of open drying-beds.

Data relating to the operation of the glass-covered sludge-drying beds for 1 year at the North Toronto plant were shown in the following Table :

DATA RELATING TO THE OPERATION OF THE SLUDGE-BEDS AT NORTH TORONTO DURING 1935.

Month.	Total solids in sludge applied: per cent.	Volatile matter in solids of sludge applied: per cent.	Total solids in sludge as removed from sludge-beds: per cent.	Yield of sludge-beds in solids per square foot per day: lb. ¹
Jan. . .	7.08	49.0	16.5	0.032
Feb. . .	6.30	50.5	24.1	0.034
Mar. . .	6.21	50.1	22.7	0.052
Apr. . .	5.56	51.3	27.7	0.076
May . .	4.84	52.4	34.3	0.089
June . .	4.91	52.1	25.8	0.107
July . .	4.68	52.6	24.9	0.108
Aug. . .	4.39	52.1	20.3	0.104
Sept. .	4.16	52.1	20.6	0.074
Oct. . .	4.07	52.0	18.3	0.047
Nov. . .	3.92	52.3	16.8	0.031
Dec. . .	3.67	54.4	12.8	0.026
Average	4.98	51.7	22.1	0.065

¹ Weighted average, based on number of days sludge was on drying-beds each month.

The yield varied from 0.026 lb. of dry solids per square foot daily in December to 0.108 lb. in July, with a yearly average of 0.065 lb. of dry solids per square foot daily. It was important to note the seasonal variation in yield even where the beds were more or less protected from the weather. Those yield-figures had been derived by a method intended to give a fair measure of the work performed by the drying-area in any month, by taking into account the number of months or parts of months during which sludge had remained on the beds before removal. For example, if it were assumed that sludge applied to the beds in July was removed in September, instead of crediting to the month of September all the sludge removed in that month, it might be more accurate to credit a large portion of the drying of that sludge to the month of August and another portion to July, the respective portions being based on the percentage of the total drying-

Mr. Eddy.

period falling in each month. At the North Toronto plant, primary sludge and excess activated sludge were heated and digested in separate sludge-digestion tanks before being discharged upon the drying-beds. The latter were equipped for heating, and artificial heat was utilized whenever it appeared to be of assistance in drying the sludge.

In contrast with the work performed by the sludge-drying beds in Los Angeles County and North Toronto were the yields of vacuum filters which de-watered undigested sludge at the activated-sludge plants in Milwaukee, Wisconsin, and Pasadena, California. At Milwaukee, the yield of sludge-cake from the Oliver filters had varied from 0.014 to 0.056 lb. of dry solids per square foot per minute equivalent to from 20.2 to 80.7 lbs. per square foot daily. At that plant the moisture of the sludge applied to the filters had averaged from 98 to 99 per cent. and that of the de-watered sludge had ranged from 82 to 85 per cent. At Pasadena, sludge with an initial moisture content of 99 per cent. had been de-watered on Oliver filters to a final moisture-content of from 78 to 80 per cent., with an average yield of 0.016 lb. of dry solids per square foot per minute, or 23.0 lbs. per square foot daily. At both of those plants the de-watered sludge was dried to a moisture-content of approximately from 3 to 5 per cent. in rotary driers, and was sold as commercial fertilizer.

For final disposal of mechanically-de-watered sludge several new American plants had turned to incineration. That trend was doubtless due in part to the high moisture-content of the de-watered sludge. Among those which disposed of sludge by incineration were the Calumet plant at Chicago and the plant at Dearborn, Michigan, in both of which the digestion of sludge was omitted entirely. The de-watered sludge at Dearborn contained about 67 per cent. moisture when it was fed into the incinerator.¹

Dr. Engel.

Dr. F. V. A. E. ENGEL was particularly interested in the reference to the venturi flume and its adaptation as the most suitable measuring device in connexion with the West Middlesex main drainage scheme. Everyone would agree with the reasons given by the Author on p. 486 § for the preference for a venturi flume for the measurement of fluid flow in gravity sewers. A considerable amount of research had been done recently with regard to venturi-flume meters, and Dr. Engel² had been engaged for some time in investigating the hydraulic

¹ *Public Works*, vol. 67 (1936), No. 7, p. 42.

§ *Ibid.*

² F. V. A. E. Engel, "The Venturi Flume." *The Engineer*, vol. 158 (1934) pp. 104 and 131.

F. Engel, "Venturi-Kanalmesser. Die messtechnischen Eigenschaften in Abhängigkeit von den Strömungsarten." *Archiv für Technisches Messen* vol. 4 (1935), No. 45.

tures as well as the most suitable design of that type of meter. Dr. Engel. The maximum rate of flow through one of the six flumes shown in fig. 20 (facing p. 477 §) at the outlet from the grit-chambers was about 100 million gallons per day, and model tests were therefore the only means of establishing the discharge-coefficient, head-loss and other important features in the design, since no existing test-plant could deal with such quantities.

The model was geometrically similar to the prototype and consisted of a true copy of the grit-chamber, the venturi flume and the storm-water overflow-weir. After a careful investigation, the scale of the model had been chosen to be one-tenth of that of the full-scale plant. Rails were fitted for a point-gauge to take depth-measurements and numerous tapping-points inside the channel were connected to a series of gauge-glasses to determine the pressure-head at a number of sections along the axis of the channel. At each measuring-section there was a row of tapping-holes in the bottom of the flume leading into a common duct and thence to a gauge-glass, and there was a similar arrangement in the side walls.

The venturi flume had to work under free-discharge as well as under drowned-flow conditions, and for that reason it was necessary to have one tapping-section in the upstream part of the channel as well as a tapping-section in the contracted part, or throat, of the time-meter. The rate of flow through the flume was given by a relationship which was based on the Bernoulli theorem. The Bernoulli theorem, however, was only correct under ideal conditions, and great care had to be taken in using the results obtained from model-tests for determining the characteristic features of the prototype. Applying the Bernoulli theorem to the upstream section (suffix 1) and to the section in the throat (suffix 2), it was usual to state the relationship in the following way :

$$\frac{p_1}{\rho} + \frac{v_1^2}{2g} = \frac{p_2}{\rho} + \frac{v_2^2}{2g}$$

There were, however, several limitations and deviations from the Bernoulli theorem, which might be dealt with in the four following sections :

- (1) Dissipation of energy,
- (2) Viscosity-influence,
- (3) Velocity-distribution, and
- (4) Curvature of water-filaments.

Dissipation of energy was not taken into account in the relationship as given above. Across the two tapping-sections upstream and

Dr. Engel.

in the throat, the amount of dissipation of energy was assumed to be very small, of the order of from 1 to 3 per cent. The dissipation in that case was mainly due to friction, as the entrance was very smooth and gradually changing in area, as shown in *Fig. 20* (facing p. 477), thus preventing separation and contraction of the main water stream in the throat-entrance, which would introduce additional losses. The smooth surface and the large dimensions resulted in small frictional losses. To obtain similar conditions in the model the walls were made out of zinc sheet, and it had to be assumed that no considerable difference in relative roughness existed between the model and the prototype.

No reference was made to any viscosity-influence in the form of Bernoulli theorem as given above. On the other hand, viscosity could not be neglected, especially where the water-filaments were converging, which, as previous investigations of Professor A. Gibson had shown, had a stabilizing influence resulting in laminar or streamline-flow conditions existing far beyond the critical velocity. That point was of importance when considering the scale of the model. It was evident that the scale had to be such that the Reynolds number was high enough to work beyond the range of laminar or quasi-laminar-flow conditions, since results obtained in the lower ranges could not be applied to the prototype, which worked in a range of very much higher Reynolds numbers and therefore in a state of fully-developed turbulence. It had to be borne in mind that in the case of flume-meters, Froude's Law of Similarity had a predominant influence on the hydraulic characteristics. It was a known fact that having the same Froude number in both the model and the prototype prevented the Reynolds numbers from being the same, and that therefore a considerable discrepancy in the Reynolds Law of Similarity might exist. The comparatively low Reynolds number obtained in a small-scale model had a further influence, as a relatively thicker boundary-layer would exist in the model than in the prototype. That had the effect of decreasing the actual opening of the throat, and thus producing a greater differential head for a given rate of flow than that produced under similar conditions (regarding the Froude number) in the prototype for a similar rate of flow.

The difference in the Reynolds number in model and prototype would also produce a different velocity-distribution. Two French investigators (Coriolis and de Saint Venant) in the last century had shown that Bernoulli's theorem as given above was not complete as it neglected the influence of the velocity-distribution. The kinetic energy was actually greater than the kinetic energy based

mean velocity obtained by dividing the rate of flow by the cross-sectional area of the water-stream, and therefore it was necessary to introduce correction-factors on both sides of Bernoulli's equation the term which referred to the velocity-head. That correction-factor was greater than unity, but the information at present available on that subject was very meagre.

Another point which was often neglected in the application of the Bernoulli theorem was the influence of the curvature of water-filaments, which was particularly important in the case of flow over sills and through venturi flumes. Bernoulli's theorem was strictly applicable in cases where no curvature of water-filaments occurred; that was to say, where the water-filaments were parallel. In cases of great curvature or of convergency or divergency of the water-filaments, a considerable discrepancy could occur between a pressure-head measurement and a depth-measurement. The first reference to that effect which he had been able to trace was given by Messrs. A. Koch and M. Carstanjen.* The influence of the curvature of water-filaments in the case of venturi flumes had also been brought to his attention in a communication by Mr. A. M. R. Montagu, Inst. C.E.

It might be of interest to give some of the test-results which had been obtained in connexion with the investigations on the model of the main venturi-flume meters for the West Middlesex drainage scheme. Before going into details it was necessary to give some of the dimensions used. It was intended to consider two measuring-sections, one upstream of the contraction and one situated in the parallel-walled throat and about two-fifths from the entrance. The width-ratio of the flume-meter was approximately 0.273, for which the critical depth \dagger was about $0.674d_1$.

In the upstream section there was practically no difference between the actual depth and the pressure-head measured with the gauge-glasses. The discrepancy in the throat-section was, however, very marked. In *Fig. 47* (p. 480) the ratios of depth and pressure-heads in the throat section to those of the upstream section were plotted against the upstream depth (which, as previously stated, coincided with the upstream pressure-head). The diagram also showed a line indicating the critical depth. It was of interest to note that the major parts of the curves AA, BB, and CC were above the line of


* A. Koch and M. Carstanjen, "Von der Bewegung des Wassers und den bei auftretenden Kräften." Berlin, 1926.

\dagger Professor A. H. Jameson had given a relationship from which the critical depth might be easily obtained as a function of the width-ratio: "The Development of the Venturi Flume." *Water and Water Engineering*, vol. 32 (1930), 105.

Dr. Engel.

critical depth, a result which might be rather misleading. The venturi flume was actually free discharging, that was to say, variations in the downstream level had no influence on the upstream measurement. Therefore somewhere in the throat the critical depth was bound to have been reached. A further curve (DD) was shown in *Fig. 47* which referred to the depth-measurement taken at the outlet of the parallel-walled throat; that curve, over practically the whole range investigated, was considerably below the critical depth. It would not be a practical proposition to make the measurement at the throat always at the critical section, as its position varied with increasing rates of flow, from the entrance of the throat to its outlet. The reasons for the selection of the position of the measuring section in the throat in that particular case could not be dealt with in the present discussion.


Fig. 47.



The ratio of the total energy in the throat to the total energy upstream, as given by the Bernoulli theorem, was shown in *Fig. 48*. The curve AA referring to the depth measurement had been obtained by adding the velocity-head to the depth of the water-stream measured by the point-gauge. Similarly, the curves BB and CC referring to the gauge-glass measurement giving the pressure-head had been obtained by adding the velocity-head to the pressure-head measured. He had also made some calculations referring to depth-measurements at the outlet of the parallel-walled section of the throat, but as the curve followed curve AA very closely, it was not included in *Fig. 48*. That diagram was interesting in so far as it clearly indicated that a depth-measurement in the case of a water stream with curved filaments was incorrect, since it would indicate a gain in energy shown by values of the energy-ratios above unity.

curve BB (*Fig. 48*) seemed to indicate that the "true" arrangement was to measure the pressure-head in a case of curved water-filaments through a venturi flume which had no hump, by using a float-well with gauge-glasses connected to tapping-points in the side wall of the throat. For the side gauge, the amount of energy-dissipation across the convergent inlet did not exceed $2\frac{1}{2}$ per cent., whilst the bottom gauge seemed to indicate a dissipation of energy in the convergent entrance-section of the flume of up to $7\frac{1}{2}$ per cent., which in his opinion was an excessive value. In the case of the West Middlesex main drainage plant it was obvious that only a float-well connected to tapping-points in the side wall was a practical proposition. It might be mentioned that the Bernoulli theorem as given above could be written in an expanded form by including correction-factors

Fig. 48.



and new terms to take into account dissipation of energy, velocity-distribution, and the curvature of the water-filaments.

In his opinion, model-tests were of the greatest importance in investigating hydraulic structures, and especially in investigating measuring-devices such as weirs and venturi flumes. The numerous points dealt with previously might seem to complicate the issue, but having the knowledge of all the influencing factors, it was possible, by using correct dimensions and correct methods of measurement, to overcome the difficulties which arose. It was of interest to note that the results on the model for the Mogden purification-works were in excellent agreement with the well-known work of Mr. C. C. Inglis¹ on flume meters.

¹ C. C. Inglis, "Notes on Standing Wave Flumes and Flume Meter Falls." Government of Bombay, Public Works Dept., Technical Paper No. 15. Bombay, 1928.

Dr. Engel.

Some confusing statements regarding "critical-depth" meters which class broad-crested weirs and venturi flumes belonged, had been made in previous publications. It should be quite clear, therefore, that it was neither intended to measure in the section of critical depth nor was it necessary to obtain a coefficient equal to unity even a constant discharge-coefficient. The measuring-sections had to be selected to obtain the most reliable results over a wide measuring-range. Any variations in the discharge-coefficient could be easily taken into account, especially in designs in which the flow-movements were transformed into a variation of an electrical quantity. The electrical metering system gave a great flexibility especially with regard to incorporating any odd values of hydraulic coefficients.

In conclusion, he would like to point out that the expression "standing-wave flume" as used in the Paper was slightly confusing. In one case it referred (*Fig. 20*, facing p. 477 §) to a venturi flume which might work under free discharging as well as under drowned conditions, and in another it definitely referred to a measuring device which would work always under free-discharge conditions (p. 486). He had shown previously that even in a case of a drowned flume (that was, when the downstream level influenced the upstream conditions), a "standing wave" might occur, whilst over a wide range no standing wave would be observed at all. It was therefore suggested that, whatever might be the flow-conditions, the term "venturi flume" should be used, indicating that the type of meter under consideration was working in an open conduit with contraction similar in configuration to the plan of the well-known venturi meter for pipelines.

Mr. Osborne.

Mr. A. A. OSBORNE pointed out that on p. 469 § it was stated that Local Authorities were allowed temporarily to discharge excess storm-water into the system. By extending the population-growth (*Fig. 2*, p. 468 §) it appeared that the ultimate population of 2,000,000 might be reached by about 1954, in which case the expected excess storm-water referred to might require consideration in from 15 to 20 years' time. If that inferred that certain Local Authorities might ultimately be faced with the need for disposal of storm-water, complete clearance of existing sewage-works sites as mentioned (10) on p. 467 § might not be possible under those circumstances.

The considerable number of boreholes through water-bearing ballast mentioned on p. 470 § raised the question whether any appreciable variation due to lapse of time had been found between water-levels in the working shafts and the original water-levels.

corresponding boreholes, and whether any relation had been observed between such variations and the annual rainfall.

As a scheme of the magnitude of that under discussion involved careful consideration of small details of construction affecting the safety of the maintenance-staff, the general use of york-stone steps with a sloping handrail would be preferable to the fluted brickwork indicated on the side-entrance steps shown in Fig. 7, Plate 1, which, however, might not be typical. Again, the headroom in the short side-entrance gallery shown in Fig. 5 (p. 478 §) was shown as 6 feet 6 inches but a headroom of only 5 feet was provided in the long gallery in Fig. 7, Plate 1 for the same-size sewer; it was hoped that the special circumstances of construction referred to for the long-gallery manhole had not necessitated general adoption of a 5-foot headroom instead of 6 feet 6 inches in side entrances.

He would be interested in further information with regard to the type of joint used for the concrete pipes referred to at the top of p. 471 §, and whether ventilation-columns had been used over any of the air-inlets mentioned on p. 478 § where the sewer had little cover. How had the brick sewer been eventually safeguarded against the detrimental effects of sulphur-laden water on the 2 : 1 cement-mortar joints referred to on p. 482 §?

Mr. H. F. PAYNE observed that the smallest outside diameter cast-iron lining used was not given, but from the dimensions of the shield it would be approximately 5 feet. Some years ago he had been connected with the construction of a sewer in heading in London clay in which about 150 feet of 5-foot 6-inch diameter cast-iron lining had been used. The majority of the segments had been made from one mould, and due to some slight error in the positions of the bolt-holes it had been found that the lining when erected had developed a winding amounting to 90 degrees in the total length. Had any similar trouble been experienced on the West Middlesex works, and had any precautions been taken to avoid it?

The 12-inch diameter ventilators were described as inlets. Were any means employed to prevent them acting as outlets?

With regard to the formula for the destructive effect of flows in siphon drops, it might be of interest to record that at Dudley, in 1880, there had been constructed a cast-iron drop-pipe with a difference in level between the water-surfaces of 86 feet. The maximum discharge was about 15 cusecs, so that Qh^2 was 110,940. Up to 20 years ago, when he had left the district, the drop-pipe and bends had never required repair.

Mr. Payne.

Although not stated in the Paper, it was presumed that the sewage-level recorders were of the floating-ball type. If so, he would be glad to know if they worked satisfactorily without daily attention. The Portsmouth Corporation had recently tried one in a sewer and had found that it was continually stopping owing to deposit on the guide-rods. They had then installed pressure-bulb type instruments which were satisfactory.

Mr. Pearse.

Mr. LANGDON PEARSE, of Chicago, observed that the Author had presented an interesting and concise account of a large undertaking of particular interest to those engaged in sanitary engineering work in the United States because of certain differences in practice from British methods.

Size of trunk sewers. In the United States a number of cases showed interceptors designed to handle from 350 to 457 U.S. gallons per head per day on the ultimate population. The ratio of capacity to average flow varied approximately from 2 to 4. At Columbus, Ohio, however, an interceptor to handle from 600 to 2,110 U.S. gallons per head per day had recently been provided in a special situation.

According to the usual practice in the Sanitary District of Chicago, a base-flow was computed from data taking account of the average population, infiltration, and industrial and commercial use, rationalized by a study of the area. To the base-flow a factor was applied for variations in sewage-flow in the seasons and also throughout the 24 hours of the day. Such a factor had ranged from 1.10 to 1.60 on an individual sewer, averaging about 1.25 to 1.30. Next a factor of 1.20 was applied to cover increments of storm-water. In addition, a factor of safety was used to provide for ventilating unexpected or unusual movements of population, changes in industry, and for additional storm water. That had varied in some sewers from 1.375 to 1.5 at the outlet to 2.00 at the upper end. In general, at the outlet the combined factors amounted to from 2.1 to 2.25.

The outlet-capacity of the large interceptors varied, ranging from 0.0234 to 0.0526 cubic foot per second per acre, depending on the situation. The present flows ranged from 190 to 330 U.S. gallons per head per day. The area tributary to the larger plants of the Sanitary District varied from 15,000 to 39,000 acres. In the Sanitary District of Chicago, the trunk interceptors were planned for about 35 years ahead. The tendency for the water-pumpage to decrease might be accelerated somewhat in the near future, as universal metering was approached. The interceptors as planned might spill over about fifty-five times a year, including major storms occurring some six times a year.

Sewers. In the Sanitary District, the intercepting sewers

feet diameter and upwards were built of monolithic reinforced concrete in place of approximately 1 : 2.5 : 3.5 mix, with cylinders having a crushing strength of over 3,000 lbs. per square inch at 3 days. A semi-elliptical cross-section was found to be most practical for tunnel work. Most of the larger work was built in tunnel, under atmospheric pressure. In tunnel, a minimum section of about 4 feet by 5 feet internal dimensions was used. Steel lining was employed in place of timbering whenever work was done under compressed air. 1 : 3 cement grout was forced in between the masonry and the outside of the excavation at a pressure of 100 lbs. per square inch, through pipes spaced at about 10 feet centres. Reinforcing steel was used as required.

The detail of connecting large sewers to interceptors was important because of the energy to be dissipated. A form of hydraulic jump had been developed by the Sanitary District, through tests on models. The connexions required two controls on all large sewers. As the municipal sewers flowed partly submerged, a back-water gate was required. There was also two-float control to limit the admission to the interceptor, one float operating from the interceptor and the other from the incoming sewer. That permitted a local storm to discharge into the interceptor so long as its flow-depth allowed.

Sewer-construction. The rate of sewer-construction depended on the material excavated. In building large sewers in the clay prevalent around Chicago, a rate of progress of about 20 feet per 24 hours per heading was commonly made on sewers, even on those with as large an inside diameter as 17 feet. Labour-saving machinery was freely used, such as electrical haulage, excavation by electric shovels, and placing concrete by pneumatic conveyors. The use of air-spades had been very helpful in making tunnelling more economical. Elaborate precautions were taken to ensure the safety of the workers, particularly where compressed air was used. Fireproof shafts were required, with a stairway independent of the hoist.

Design of plant. The design of the sewage-treatment works at Mogden differed from American practice in the inclusion of a separating weir for storm water, secondary sedimentation-tanks, and storm-water tanks. The Sanitary District plants were designed to treat 50 per cent. of the average sewage-flow. A few works in the United States could handle as high as 200 per cent. of the average flow.

In the Sanitary District works, inclined bar screens were originally used, with 1-inch openings. After trying $\frac{5}{8}$ -inch openings, $\frac{3}{4}$ -inch openings were considered the best. The screenings were raked off automatically on to a travelling belt and delivered to a crusher, in which they were crushed and returned to the sewage. At the start,

Mr. Pearse.

such screens had been omitted from the Southwest plant. In the newer Sanitary District works, where sludge was to be handled by de-watering and incineration, the grit-chambers had been omitted. The grit was then deposited in the preliminary settling-basin with detention of from 10 to 35 minutes. In the United States, however, grit-chambers mechanically cleaned were generally growing in favour on the larger plants.

In the United States, preliminary settling-tanks ahead of activated sludge were usually short-period tanks. For the Sanitary District plants, from 10 to 35 minutes was considered ample. That provided enough fresh solids to mix with the excess activated sludge and to develop optimum conditions for de-watering on vacuum filters. The sewage dealt with was much lower in suspended solids than was the case in Great Britain. At Milwaukee, grit-chambers and fine screen ($\frac{1}{16}$ -inch by 2-inch slots) were used ahead of the aeration-tanks. The design-basis of major plants in Chicago was :

THE SANITARY DISTRICT OF CHICAGO: DESIGN BASIS OF MAJOR PLANTS.

Plant.	Population: estimated.	Flow in U.S. gallons.		Area served: square miles.	Suspended solids: part per million
		Total.	Per head.		
North Side ¹ .	1,100,000	200,000,000	182	115	137
Calumet ¹ .	450,000	136,000,000	300	95	176
West Side ² .	1,724,000	580,000,000	336	101	121
Southwest Side	1,300,000	400,000,000 ³	308	131	—

¹ Activated sludge.

² Imhoff tanks only.

³ Including waste from Packington.

⁴ Average for 1936.

In the United States, the common practice for sludge-removal in settling basins was to use either a rotating mechanism, such as the Dorr or Hardinge, or a straight-line endless chain carrying scrapers. Both circular and rectangular basins were employed. The tendency was towards larger basins in order to save construction-costs.

For the sewages in the Sanitary District, aeration-periods of hours had been allowed on a design-basis with an average of from 0.4 to 0.5 cubic foot of air per U.S. gallon of sewage, with a blower capacity based on a maximum flow. Operating tests on a large scale (65 million gallons per day) had shown that a period of 3 hours might suffice. As a rule, in the United States, it was the exception to find any provision for sludge-reconditioning; however, in the Calumet works of the Sanitary District, two tanks out of twenty

Two aeration-tanks could be used for re-aeration. The spiral-flow principle had been generally adopted because of its simplicity in construction. The width of the flow-channel at the North Side works was about 15 feet 8 inches, with two rows of plates. At the Calumet works, a width of 33 feet 6 inches had been used, with two rows of plates, but initially some of the aeration-tanks were being operated with one row of plates. In an experimental unit, there were indications that a 68-foot width was possible, with two rows of plates along each side wall. The Southwest plant had a channel-width of about 33 feet, with two rows of plates. Diffuser-plates, 12 inches square, were the standard. As coarser plates than previously were now specified, carborundum or alundum plates, 1 inch thick, were used. Formerly silica-sand plates, $1\frac{1}{2}$ inch thick (Filtros), were also available in the finer grades of porosity. Those plates were usually set in precast-concrete containers. Cast-iron containers had been abandoned years ago because of rust-conditions. Aluminium containers had been tried in a few plants.

At $\frac{1}{2}$ cubic foot of air per U.S. gallon of sewage, the Calumet plant used 3 cubic feet of free air per plate (12 inches square) per minute, with two rows of plates. Using one row of plates, 6 cubic feet of air were required per plate. The Southwest design was practically the same. The air was all filtered through oil-dipped cleaners before compression.

The regulation of the air to each individual diffuser-plate was not practised in the United States. In the Sanitary District designs, from thirty to seventy-two plates were controlled by a common globe-valve, but in the more recent designs each row was separately valved, from thirty to thirty-six being on one valve. By a system of testing and inspection every plate was rated and marked. In plants the size of those in the Sanitary District, plates closely alike within very narrow rating-limits were set in a given tank. The water-depth of the aeration-tanks was nominally 15 feet over the plates.

Return-sludge was allowed for on an average of 20 per cent. of the average flow. At the North Side and Calumet works, a maximum return was provided of 40 per cent. of the average, or 20 per cent. of the maximum. At the Southwest works, the maximum was 30 per cent. of the maximum sewage-flow. Whilst there might be a value in diluting the raw sewage with effluent on the stronger sewages in Great Britain, there appeared to be little need for that practice in handling the more dilute sewages found in the United States. The difficulties noted in continued drought were those connected with the behaviour of the sludge as the volatile content rose. Bulking might then be likely to occur. In the North Side and Calumet works, return-sludge pumps were installed. In the South-

Mr. Pearse.

west works, air-lifts on individual tank-units were provided, thus giving a localized control. The use of cross-baffles in the aeration channels seemed unnecessary in a design with four channels of total length of 1,600 feet. Out of one hundred and thirty-five plants in the United States, only one, of small size (that at Hagerstown, Maryland), had used a cross-baffle.

In the northern part of the United States, the custom had prevailed of housing over the operating-gallery, both to protect the operator during cold or stormy weather when regulating valves, collecting samples and reading meters, and also to make the controls readily visible. In the milder British winter climate, the omission of the housing was undoubtedly a saving in cost, but might interfere with the exacting control required in such a plant.

Final settling-tanks in the United States were usually of a type cleaned with a mechanical scraper similar to the primary tank. Steep hopper-bottoms were found only in very small plants. In this design, care was taken to avoid eddy-currents. An average rate based on mixed liquor, of 1,200 U.S. gallons per square foot of tank area per day was provided for, with a maximum of 1,950 U.S. gallons. At the North Side works tanks 77 feet square were used. In the Calumet plant tanks 91 feet square were used, with central feed and peripheral effluent-weirs. At the Southwest Works, tanks 126 feet in diameter were used. For a variant on the sweeping device at Milwaukee a multiple-inlet type of revolving arm ("Tow-Bro") was used, in place of squeegees. The type used at Mogden necessitated a larger number of units, fifty-two in all, and much deeper excavation than required by the United States practice of large shallow tanks, mechanically cleaned. Operating results indicated the value of larger units and fewer mechanisms to maintain. With mechanical cleaning, the Mogden bottom slope might be adequate. At the Des Plaines River works of the Sanitary District, however, a slope of 2 to 1 was not sufficient on pyramidal-bottomed tanks, the flatter mechanically-cleaned basins proving better.

Storm-water tanks were very rare in the United States and Canada. To Mr. Pearse's knowledge, there was only one plant so equipped in each country (namely Columbus, Ohio, and North Toronto, Ontario). It was possible that in the future, where stream flow conditions warranted, the use of storm-water tanks might become more common.

The operation of the Mogden project would be watched with much interest to ascertain whether the space allowed per head for sludge digestion proved adequate. The allowance of 1.3 cubic foot primary and 3.3 cubic feet secondary, or 4.6 cubic feet total, did not seem adequate for a mixed activated sludge, if the results on mixed sludge

in the Sanitary District were any criterion. The difficulty in digesting Mr. Pearse, activated sludge was to secure a dense sludge. The moisture-content had ranged from 94 to 96 per cent. with either heat-controlled or Imhoff-tank digestion.

For the Sanitary District, 5 cubic feet per head had proved inadequate for digesting mixed fresh and activated sludge. As a result, the programme had been developed for the Calumet and Southwest works of eliminating all digestion, taking fresh sludge with the excess activated, coagulating with ferric chloride and de-watering on vacuum filters, then mixing the wet cake with pre-dried material to produce a water-content of about 50 per cent., drying in a flash dryer, in superheated vapour, and incinerating the sludge by blowing into a furnace. The heat from the incineration served for drying. All the vapours passed through a temperature of 1,200° F., and all odours were eliminated. That offered a most compact and satisfactory method of sludge-disposal, leaving an inert mass of cinders. The plant was estimated to be more economical than digestion-plant for the Sanitary District conditions. If desired, material dried to 10 per cent. could be withdrawn from the drying circuit and sold for fertilizer. At such times, other fuel was required to replace the sludge withdrawn.

The study of the possible size of sludge-drying beds for the West Side and Southwest Side plants, aggregating over 100 acres of drying area, had convinced Mr. Pearse that on large projects some form of mechanical stripper was desirable, on special beds, loading direct to standard-gauge self-dumping gondola cars. For the Sanitary District, a project had been worked out, of which 27 acres had been built with the beds 80 feet wide, and units ranging from 800 to 1,300 feet long. Two types of stripping machines had been devised, running on concrete walls, self-propelled and electrically controlled. With each machine, a crew of five men could strip from 1,000 to 1,500 cubic yards of air-dried sludge in 8 hours, loaded in 30-cubic-yard dump-cars on a standard-gauge railway. The use of narrow-gauge track on sludge-drying beds was decreasing in general practice, except in small plants, and small caterpillar-tractors carrying saddle-back hoppers were proving popular. In United States practice, more sand and less gravel was used than at Mogden. In the Sanitary District, at the West Side, the beds were made with 3 inches each (from the bottom upwards) of from $\frac{7}{8}$ -inch to $1\frac{1}{2}$ -inch gravel, of No. 4 sieve to $\frac{7}{8}$ -inch, and of No. 8 to No. 4 sieve, topped by 5 inches of sand. The subgrade was level. The underdrains in general were 18 feet 6 inches centre to centre, surrounded by the coarse stone.

From the design standpoint on large works, operating experience

Mr. Pearse.

was very helpful. With the three large plants built in order—the North Side, Calumet and Southwest—the Sanitary District staff had had especial opportunity to observe the behaviour of the plant and its details. Even such matters as paint and non-corrosive metals had been studied over a term of years. As a result, the designs were developed to produce a low first cost and also low maintenance costs. The tendency was towards larger units and more compact designs. Flexibility was also very desirable. In the development of the de-watering and incineration procedure, before building the 40-ton-per-day Calumet equipment, over \$350,000 was spent in experiments and in two test-plants each of 20-ton-per-day capacity of a temporary character.

The operating results and costs of the Mogden plant would be awaited with much interest, as it was the largest British plant of its type. Mr. Pearse had been concerned with the design of the three largest plants of the kind in the world—namely, the North Side and Southwest plants of the Sanitary District, and the Wards Island Plant of New York City—and in each the problems had been somewhat different. Throughout, however, the question of sludge disposal had been important. The provision of additional area at a distant site in the West Middlesex scheme was wise, because of the possibility that both additional sludge-digestion volume and drying bed areas might be required.

He hoped that the Author would be able at a later date to present a further Paper dealing with the details of design.

Mr. Thrupp.

Mr. E. C. THRUPP, of Vancouver, had been the author of the scheme for the extension of the London water-supply by storage-reservoirs in the Kennet and Enborne valleys to maintain a larger summer flow in the Thames between Reading and the London water-intakes. One of the objects of that scheme had been to minimize the effect of summer pollutions above the intakes, including those mentioned in the Paper.

One of the most active promoters of the Isleworth half-tide-weir project had been his uncle, the late Mr. C. J. Thrupp, who had been for many years Chairman of the Twickenham Local Board. The writer had pointed out that there might be opposition arguments put up by some engineers who held that the maximum tidal flow to and fro was necessary to keep the navigable channel below a certain order. Partly on account of economy, and partly on account of those extreme arguments, the scheme had been framed for a half-tide weir. He had disagreed with those extreme views, and held that the loss of tidal volume would be quite insignificant. The Author mentioned that considerable erosion had been going on for 20 years at Isleworth Ait, just as it had at Twickenham in previous years. I

both cases it was due to the momentum of the ebb tide (acting in the Mr. Thrupp. bellmouthed lower reaches which had been improved by dredging below Greenwich) letting the river down to a lower level and giving a steeper surface-grade at low water than the natural ebb stream had before. The erosion at Isleworth proved conclusively that the reduction of tidal volume had done no harm whatever to the lower river, and so it would be quite in order to raise the Isleworth weir to high-water level, and still further to improve the river above. That led to the question of the desirability of constructing at least two weirs lower down the Thames. In his carefully-considered opinion it would be one of the finest possible improvements for London, and he believed that it would be done.

Whilst admiring the remarkable efficiency displayed in the design and rapid construction of the West Middlesex scheme, he could not regard it as the last word in the problem. It was an emergency scheme, well handled as such. The next 30 years would require revised ideas to approach finality. New supplies of water would have to be brought into the Thames watershed, and sewage-effluents might have to be carried right away to sea, possibly to the south coast, unless they could be purified by further aeration, and by 3 or more weeks' storage in 20-foot-deep reservoirs in successive alternating stages to reach a quality admissible to water-supply filter-beds. It would be of interest if the Author could state how far the works had succeeded in complying with the specified requirements of purity, and whether the remaining suspended and dissolved matter was of a character liable to give further trouble from bacterial activity when exposed to other contamination in the river. Another possible emergency might arise if the people in England were to follow the customs of the city residents of the United States and Canada, and insist on having a water-supply of over 100 gallons per head per day.

Mr. W. P. WARLOW observed that the economic diameter of the Mr. Warlow. primary digestion tanks was stated (p. 529 §) to be about 70 feet. Did that apply equally to the stirred and to the gasholder tanks? It did not, apparently, apply to the secondary tanks, which were 100 feet in diameter. Were the walls of the tanks designed to resist the full internal pressure of the sludge? The Author had rightly pointed out that partly-digested sludge was more easily pumped than either raw sludge or digested sludge. In view of that fact, it was presumed that the pipes provided for drawing off separated liquor from the primary tanks were not intended for use under normal conditions.

Mr. Warlow.

The arrangements made for heating the sludge in the primary tanks ensured very effective use of waste heat. The use of a heat exchanger appeared to be contemplated during hot weather for cooling the circulating water. Could that not be effected equally well by cutting out one or more of the boilers? In any event, was the Author satisfied that the digestion-process would be impaired if the sludge in the tanks became heated above the "optimum" temperature of about 80° F.?

The estimated gas-production of 0.625 cubic foot per head of population per day seemed highly conservative, and a figure of 1 cubic foot per day might perhaps have been anticipated from the performance of similar installations elsewhere. Had any precautions been taken to avoid loss of gas by leakage through the concrete roofs? Mr. Warlow was aware of two instances in which slight leakage had occurred, owing apparently to diffusion through concrete.


The value of the Paper to those concerned in the operation of sewage-works was greatly enhanced by Mr. Townend's observations in the course of the Discussion. In view of the growing tendency to utilize sludge-gas for power-production, Mr. Townend's statement to the effect that the value, at 2d. per therm, of the gas produced at Mogden would be sufficient to defray the whole of the annual cost of sludge-disposal was of general interest. That statement was, however, difficult to reconcile with information given in the Paper, and perhaps the Author would give further details. The cost of the sludge-main and the works at Perry Oaks was stated to be £232,800. If the cost of the primary tanks at Mogden and the land at Perry Oaks were added to that figure the total could not be far short of £400,000. The value of the gas would be about £20,000 per year, which would hardly meet the debt charges (apart from the Government grant), whilst rates, taxes and operation would amount to a further substantial sum, bringing the total annual cost apparently, to considerably more than £20,000 per year.

Mr. Wilkinson.

Mr. G. W. WILKINSON considered that as the prime consideration in most sewage-works was that of purification, some details of the aeration-tanks at Mogden, where the greater part of the process of purification was performed, might be of interest. *Fig. 49* was a typical cross-section through two channels of the "spiral-flow" units, and *Fig. 50* (p. 494) was a cross-section of a "longitudinal ridge-and-furrow" unit. The form of the channels was exactly the same except for the arrangement of the diffuser-plates. In both cases, the form of the cross-section of the channel was considered to be such as would give the maximum efficiency of circulation. The use of thin walls of reinforced concrete between the channels had

Mr. Wilkinson.

Fig. 49.



sulted in appreciable economies in the area of land required and Mr. Wilkinson. the cost of construction.

It was possible to return effluent to any of the aeration-units, and that had been found a great advantage. When, for instance, it was necessary to empty a unit for inspection or other purpose, the inlet-instock was closed and effluent pumped back, which displaced the mixed liquor, the latter being merely pushed forward to the next separating-tanks. In that way the activated sludge from that unit was kept in circulation in the plant. When the tank was emptied, the air-supply could be shut off without any possibility of sludge being deposited on the diffusers.

The amount and character of surplus activated sludge produced was a matter of some importance in the operation of activated-sludge plants. At Mogden, the quantity produced was about 1 per cent. of the dry-weather flow with a water-content of 98.8 per cent. which could be reduced, by 1 hour's settlement, to 97.6 per cent. The low figure of surplus-sludge production might be accounted for by the efficient preliminary settlement of the sewage before it reached the aeration-tanks, and also by the fact that purification was then taken to the nitrification stage, under which conditions matter produced by flocculation in the early stage of the aeration-process was subjected to some degree of aerobic digestion.

An inspection of the map of the district surrounding the Mogden purification-works would emphasize the revolutionary changes that had come about in the practice of sewage-disposal. Not many years ago it had been a *sine qua non* of sewage-disposal practice that the works should be erected as far as possible away from urban development, both on the grounds of æsthetics and also with the object of keeping the smell away from the towns. The site selected for the Mogden works, however, was the natural outfall to the river Thames for the greater part of the drainage district, and was for that reason all the more desirable. By means of the activated-sludge treatment, the purification of sewage was possible with complete freedom from smell- and fly- nuisance. No other method could have been applied with such great advantage to the peculiar requirements of the West Middlesex Drainage Scheme. Indeed, it might be said that the feasibility of the scheme was due to that fact.

The application of the activated-sludge process to the Mogden works represented the culmination in Great Britain of the progress made within the last 25 years, commencing with the pioneer work of such men as Dr. Gilbert J. Fowler, who had initiated the original experimental work leading to the discovery of the process, and of Mr. A. Coombs and the late Mr. Walter Jones, who had been concerned

Mr. Wilkinson, as engineers in translating the laboratory-experiments of the chemists into practical possibilities in full-scale plants.

Second only to the problem of producing a satisfactory effluent was that of sludge-disposal. That, also, had to be accomplished without nuisance, and it was in that respect that the application of the practice of sludge-digestion to the requirements of the scheme was noteworthy, quite apart from the economies accruing from the utilization of the resultant gas for the power-requirements of the works.


As was well known, the process of sludge-digestion had been evolved at the works of the Birmingham Tame and Rea District Drainage Board, and had subsequently been developed by Mr. J. D. Watson, Past-President Inst. C.E. To his work in that field especially, the adoption of the process to such advantage and on such a large scale at Mogden was a fitting climax.

The AUTHOR, in reply, observed that the details of the inverted siphon under the river Brent, asked for by Mr. Alford, were shown in *Figs. 51*.

The walls of the sludge-drying beds were 2 feet above medium level (p. 551 §) and the maximum depth of sludge on the beds could not therefore exceed that figure, but the other data requested by Mr. Bush were not yet available.

Conditions governing the design of backdrops were very varied and led to the adoption of a number of types. Both Mr. Bush and Mr. Payne referred to the advantage of cast-iron drop-pipes. Complete destruction of the kinetic energy of the falling sewage of the branch sewer appeared to be more desirable in some cases than in others, and as in so many places the headings and shafts necessary for construction had been available, the opportunity had been taken to install some more efficient form of backdrop than the ordinary type of cast-iron pipe backdrop.

Ventilation of all sewers, and more particularly large sewers, has always been a vexed question; that it could not entirely be divorced from public sentiment and imagination was proved over and over again by complaints which arose about smell from new sewers not yet brought into operation. The West Middlesex sewers had been no exception to that form of complaint, and in some cases complaints had been received since they had come into operation. In the vicinity of backdrops such complaints had no doubt been justified, but in the main, the principle had been adhered to that the more the vents the better the ventilation of the sewer, and the less the intensity of the smell at any one point. It was interesting in the



The Author.

connexion to read the Correspondence on a previous Paper ¹ where Sir George Humphreys showed that the experience in London had been that public opinion had influenced the decision to close main open vents, but that the wisdom of doing so had been doubtful. No means had been taken to prevent ventilation-holes in sewers from acting as both inlets and outlets.

The standard of purity required by the Act, and referred to by the late Mr. Harrison P. Eddy, would be recognized as the normal standard of the Royal Commission on Sewage Disposal as recommended by the Commission in relation to discharge into non-tidal waters—certainly not for discharge into tidal reaches of the Thames such as that at Isleworth. It was not in all respects that American and English practice in sewage-purification and disposal could readily be compared, but Mr. Eddy touched on the capacity of open-air sludge-drying beds, and there probably contrasts could be drawn, although differences in climate made comparison under the same conditions very difficult. In a few years' time, when the operation of the Perry Oaks works had been stabilized over a reasonably long period, the data available could be compared with the results obtained at other large works in Great Britain and in America.

Dr. Engel's observations formed a valuable contribution to the published information on the design of venturi flumes. Incidentally they afforded yet another proof of the whole-hearted co-operation of those manufacturers who were from time to time approached during design-stages and invited to help in the solution of difficulties arising out of the unusual circumstances of the work, or in the overcoming of constructional troubles.

As the volumes of storm-water accepted into the County Council sewers were generally no less than were the volumes discharged by the Local Authorities to their now-disused sewage-works, the operation of the scheme caused no change. All Authorities had been in the past to make some provision for disposal of storm-water other than the volumes discharged into foul sewers. Those provisions were unaltered, except that six times the dry-weather flow of sewage (and, as explained on p. 469, § even greater volumes) were now discharged to the county's sewers, and therefore the point raised by Mr. Osborne that old sewage-works sites might not be cleared but might be used for storm-water did not arise in practice. The sites were rapidly being changed for use for other purposes and in fact many had already been cleared and altered.

No records had been kept to co-relate the water-levels in tri-

¹ G. W. Humphreys, "The Main Drainage System of London." Minutes Proceedings Inst. C.E., vol. cciv (1916-17, Part II), p. 103.

§ *Ibid.*

yes and in working shafts. Generally speaking, the only opportunity available for noticing rest-level of ground-water on the site of a working shaft was when the shaft was being sunk, and not afterwards, since the water was kept down by pumping, and the ground-water level, as such, was lost.

Figs. 7, Plate 1 (following p. 618 §), was typical of side-entrance manholes in so far as brickwork steps were concerned. Those were found to be quite satisfactory in conjunction with handrails and safety-chains. The headroom of 5 feet shown in Fig. 7, Plate 1, is a special case, 6 feet 6 inches being the standard dimension.

All concrete pipes had ogee joints and were made with Portland-cement mortar, that applying also to the comparison mentioned at the top of p. 471 § and referred to by Mr. Osborne. In only a very few cases were ventilation-columns used over air-inlets, and they were necessitated by location of buildings very near to the sewer. The allowance of the sewer did not influence the question. The case of action of sulphur-laden water on cement-mortar joints of a sewer had been very carefully observed for a long period before the sewers were brought into use, and plans had been made for grouting behind the brickwork barrel of the sewer with aluminous cement, but, as the Paper omitted to state, it had been found that when the action had been going on for some months it stopped completely.

As all bolt-holes in the circumferential joints of cast-iron segment covers were slotted, it was an easy matter to keep the segments on the even keel, and therefore no winding occurred as Mr. Payne stated had happened in another case.

The sewage-level recorders referred to by Mr. Payne were assumed to have been all of the guide-rod type, but in West Middlesex all such were installed either in chambers or in cast-iron pipes, and were free to rise and fall as they could not be if they were made to slide on guide-rods submerged in sewage.

All engineers interested in the subject were bound to feel indebted to Mr. Langdon Pearse, of Chicago, for his contribution emphasizing differences between American practice and the West Middlesex work. Mr. Pearse had given much of his time and taken a great deal of trouble to contribute valuable comparative data calculated to help any engineer designing new works and wishing to weigh up the main differences between American and British practice. It should be remembered, however, in studying the notes, firstly that the consumption of water in the United States was very much greater than in Great Britain, resulting in larger volumes of weaker sewage, and secondly that in Great Britain all volumes of sewage and storm-water

The Author.

up to three times the dry-weather flow were purified to the same standard.

The cost of cross-baffles in the aeration-channels was trifling, and structurally their existence was useful. Furthermore, they made convenient gangways.

An answer to Mr. Thrupp's question about compliance with the specified requirements would be found on pp. 580 and 581 § in the remarks made by Mr. Townend. The results given there show that the standard of the effluent had been consistently higher than the Act required, and since Mr. Townend's remarks were made there had been a continuation of work of the same standard. The effluent discharged was non-putrefactive and the growth of fish-life in the Thames locally was attributable to the improvement in conditions in the effluent. Live fish were now to be found in the effluent conduits.

It would be incorrect to suggest that the economic diameter of both the stirred and the gasholder sludge-tanks at Mogden was the same, but practical conditions dictated that the twelve tanks should be of the same size. Beyond stating, therefore, in reply to Mr. Warlow that 70 feet was regarded as the economic size at Mogden, and 100 feet at Perry Oaks for a different class of tank built under different conditions at different depths, it was impossible to do justice to that question without going into detail not attempted in the Paper. The walls of the tanks were designed to resist the full internal pressure. Digesting sludge, with or without its supernatant water, was usually easier to pump than raw or fully-digested sludge, owing, no doubt to gas-content, and therefore as much supernatant water as possible was in fact drawn off in the primary tanks.

The temperature of the exhaust-gases had always to be reduced before discharge, and the consequent temperature of the water used for cooling them, being in a closed circuit, had to be similarly reduced. The heat-exchangers and the sludge afforded alternative means of effecting that control. In practice it had been found that the sludge temperature might profitably be kept well above 80° F.

A gas-yield of 0.625 cubic foot per head of population had been the minimum assumed. More had been anticipated, and provision had been made accordingly. Double roofs were provided to the stirred sludge tanks, but no provision was made to prevent diffusion of gas through the concrete.

In referring to Mr. Townend's remarks on the value of gas as compared with the annual value of the works and plant required to produce the gas, Mr. Warlow raised an arithmetical question.

Author thought, however, that Mr. Townend's point, dealing solely The Author. it did with the economics of that method of sludge-disposal, was dependent entirely on the value of the gas, which Mr. Townend for the sake of his argument put at 2*d.* per therm; if Mr. Warlow's arithmetical contention should be correct, it would be only right to assume an economic, and therefore considerably higher, value for the gas. As the Author understood Mr. Townend's argument, he sought to stress the great value of the gas given off, and thereby implied that conditions no doubt existed where the gas could be harnessed economically.

Paper No. 5103.

"Welded Joints in Pressure-Vessels."¹

By STANLEY FABES DOREY, D.Sc., M. Inst. C.E.

Correspondence.

MR. L. C. DIPPER noted that in Germany, Switzerland and France Mr. Dipper. the range of 22-26-28 tons per square inch ultimate tensile strength was preferred for steels used in the class of welded work under consideration, whereas in Great Britain the lower range usually specified was 26-30 tons per square inch, which the Author considered quite suitable. Was it to be inferred from that that Great Britain had had greater success in welding the higher-quality material, and if so, was that due to a better technique or to the use of a better class of electrode? Dr. J. Orr and Mr. W. Heigh, in a Paper before the Institute of Welding,² gave the impression that the German preference for butt-welds rather than fillet-welds was due in some measure to the lower quality of welding in that country. There would appear to be some connexion between that fact and the use of lower-quality material.

Regarding the presence of the martensitic zone in the case of austenitic welds, it would be interesting to hear how the hardness of that material was determined, bearing in mind the extreme narrow-

¹ Journal Inst. C.E., vol. 5 (1936-37), p. 621 (April, 1937).

² "Impressions of Welding in Germany." *The Welding Industry*, vol. v (1937), p. 251.

Mr. Dipper.

ness of the band (0.04 millimetre). If the material were true martensite he would expect a higher Brinell number, but in ordinary test might not the result be affected by a "cushioning" produced by the softer material beneath the martensite? If the numeral were correct, might that not indicate that the zone was partly troostite and sorbite?

Dr. Faltus.

Dr.-Ing. FRANK FALTUS, of the Skoda Works, Plzeň, observed that it was very satisfactory that the Author was absolutely in favour of welding, particularly of fusion-welding of boilers. His views were almost identical with the views taken in Czechoslovakia so far as to the efficiency of welded joints, the necessity of testing them, and the sufficiency of stress-relieving instead of full normalizing were concerned, the latter being specified in some cases.

In connexion with the procedure-control and testing he would give some observations based on the studies of his firm in high-pressure boiler-welding, and on some recent jobs successfully carried out in their Works.¹ Great importance was attributed in their Works to the testing of electrodes, which should, in their opinion, undergo just the same tests as specified for and applied to the parent-metal. His firm, therefore, asked their electrode-suppliers to submit to the separate test-certificates for every electrode-section of each cast, and particularly of all-weld-metal tensile- and impact-test specimens. They specified not only lower but also upper tensile limits to be closely adhered to (for example, from 42 to 50 kilograms per square millimetre) because they wanted the weld to suit the parent-metal as much as possible, and did not want it to form "hard spots" in the welded job. Hard steel, even if its elongation and impact test figures were satisfactory, tended towards formation of cracks in the weld during welding. They further specified a higher elongation (26 per cent. on a gauge-length of 4 diameters) for electrode-test than was usually specified for the inspection of the finished job. On the other hand, they considered that that test was unnecessary in routine-tests.

They fully agreed with the Author with regard to bend-tests. At the first glance the specimen (c) (p. 649§) seemed to comply fully with the requirement of equal testing-conditions for plates of different thicknesses. But that was not so. A weld joining together thick plates was in its top part far broader than a weld between thin plates and so it might easily happen that just the most important part

¹ There have been welded satisfactorily large high-pressure vessels with wall thicknesses of up to 76 millimetres, and even sections up to 200 millimetres thick.—F. F.

§ Page numbers so marked refer to the Paper. (Journal Inst. C.E., vol. (1936-37) (April, 1937).)—SEC. INST. C.E.

the joint, namely the transition from weld to parent-metal, could be made to a place, during testing, where it would be less strained (being most unaffected by the deformation). With reference to what had been said above, the free bend-test gave more exact results. His firm were well aware of the fact that it was difficult to measure the elongation of the outer fibres of a bent specimen, but a very important factor was contained in the prescription of 30 per cent. elongation. Electrodes, the tensile strength of which lay not too much above that of the parent-metal, gave an elongation of more than 30 per cent. without cracking of the weld when bend-tested through 180 degrees, but a representative weld-elongation could not be obtained with a weld having a high tensile strength, even when bend-tested through 180 degrees, because it was the parent-metal that contributed most of the necessary deformation. It might even happen that the fracture occurred outside the weld. A bend-test giving the specified minimum elongation therefore prevented the use of too hard electrodes which would form "hard spots" in the fracture.

His firm were also in agreement with the Author's assertion with regard to the value of impact-tests, but they would like to mention that, upon their suggestion, the Czechoslovak regulations for the testing of electrodes for steel structures had been modified in the following way: "Impact tests are to be carried out by means of five specimens, but the average of five best results is conclusive." That provided a possibility of excluding a false result occurring accidentally.

They did not attribute great significance to the density-test, as it was difficult to imagine a weld complying with all specified requirements, even those of X-rays examination, and failing only in the density-test. Their opinion was that the number of tests could be restricted as much as possible, only the most important ones being applied, and they would therefore recommend leaving out the micro-specimen tests.

They were very grateful to the Author for his open appreciation of the importance of X-ray examination, and also for his emphasizing the necessity of an exact interpretation of the radiographs. They considered it most important to place suitable measuring means such as a penetrometer on each radiograph. It was their opinion that the best advantages drawn from X-ray examination applied to the training of welders and to the development of new welding methods. They did not hesitate to declare X-ray examination indispensable for the purpose of those kinds of tests.

Mr. H. B. FERGUSON pointed out that the Author had given no indication as to the extra cost of manufacturing pressure-vessels to Mr. Fergusson.

Mr. Fergusson. the requirements of Lloyd's Class I or of the A.S.M.E. Code, and the average designing engineer was still somewhat vague as to whether it would pay to try to obtain as nearly as possible a perfect welded joint by the insistence on the adoption of one of those codes, with the extra cost of X-raying, mechanical tests, and macro- and micro-examination, or whether it would be cheaper to adopt thicker plate and a lower joint-efficiency, and to do away with those rigid specifications. He was able to assist in throwing some light on this problem, and he found that the extra cost in manufacture of constructing Class I pressure-vessels to one of those codes would involve an additional cost of from 9 to 27 per cent. on the total cost of the job, depending on whether there was a considerable weight of internal fixed fittings to the vessel which did not have to be X-rayed, such as a vessel filled with tubes, or whether the vessel consisted merely of a shell with dished and flanged ends. Even taking the high figure of 27 per cent. extra cost on the total value of the job, it would appear that the higher joint-efficiency which the designer could use should off-set the extra cost of X-raying the welds and complying with the mechanical, macro- and micro-rules of the codes.

It had naturally to be assumed that the works where the vessels were made to Class I Lloyd's requirements had had sufficient experience in that class of work to enable them to carry out the work without excessive welding-costs, as the removal of weld-metal in order to clear the exograph of any sign of lack of penetration or slag-inclusion was a very costly matter, apart altogether from the danger of ruining the plate adjacent to such faults by excess welding setting up additional stresses in the plate. In the event of having to chip out a weld to remove a fault, it should be obligatory for the manufacturer first to take a stereo-exograph to locate the depth of the fault and to see whether it should be attacked from the outside or from the inside of the vessel. With a little practice the depth could be ascertained to within $\frac{1}{16}$ inch, and such a procedure obviated, even in the worst cases, cutting through the weld to more than half the depth of the plate. The weld-metal could then be put back without danger of cracking. Actual experience went to show that welders who had spent a few months on welding 1- to $1\frac{1}{2}$ -inch thick plate subject to X-ray examination became so expert that, whereas when they commenced they showed some type of fault in every 3 feet or 4 feet of welding, they could easily do 20 feet of welding without a sign of any lack of penetration, slag, or flaws of any kind; when some fault was found on one of the exographs, it generally only consisted from $\frac{1}{4}$ inch to $\frac{1}{2}$ inch lack of penetration on one bead of welding only. In his opinion the silicon-content in the steel plate should

pt as low as possible, as otherwise there might be a tendency for Mr. Fergusson. e weld-metal to crack, especially with thick plate.

With regard to the preference for single-U over double-U welds, hile it was admitted that the single-U weld was the only practicable e where automatic welding was done, it would appear that on thick ate the double-U was decidedly better if the weld were done by and, as the very great stresses set up in thick plate by the weld-metal were considerably reduced and proportioned over the whole ickness of the plate, both inside and outside, and were not concentrated on the outside of the vessel. The double-U photo-macrograph (*Figs. 6*, facing p. 655 §) showed how necessary it was to build o the welding on the outside of the plate, and to chip and grind it ff. The photo-macrograph mentioned showed fine-grain structure the middle and columnar crystallization on the outside, due to ck of annealing by superimposed weld-metal, and it was Mr. ergusson's opinion that bend-tests would not give the same results that columnar crystallization existed on the outsides of the weld.

The Author mentioned the possibility of a crack, if in a certain osition, not being detected on an ordinary exograph picture taken erpendicular to the shell. As the danger in a pressure-vessel of a nall crack growing with time, especially if breathing of the vessel ook place, was of such great importance, it would be interesting to ave his opinion on altering the present method of taking X-ray ctures, and on adopting the same system as Mr. Fergusson did when king stereo-pictures; that was, giving two exposures on the same m at two-thirds the normal time of a single perpendicular exposure. he resulting stereo film was very clear, and gave immediately the istance-in of any intrusions, and it would be difficult, if not impos- ble, for any crack to escape attention. There was practically no tra cost involved except the few minutes extra of the operator's me in altering the angle at which the rays penetrated through the eld.

Dr. HERBERT HARRIS was in agreement with much that the Author Dr. Harris. ad expressed, and only in details—sometimes insignificant in impor- nce—did he find anything to criticize. On p. 625 § the Author eferred to the fact that in plate-assembly he found it unusual to rovide any shrinkage-gap. That was not a practice followed by r. Harris. It had to be borne in mind that the first layer of weld- etal was applied to relatively cold and frequently heavy plates; the eld-metal was severely quenched, and a high unit-stress could be duced in that first layer. The metal was therefore not in the best ondition to adjust itself to severe stresses. Again, it was not until the

Dr. Harris.

publication of a Paper by Mr. H. F. Hall¹ that an adequate explanation of high-temperature cracks in weld-metal had become available. Those experiments had shown that few steels had appreciable ductility in the temperature-range between the freezing-point and 1,300° C. Over a range of approximately 200° C. all steels would therefore seem to be very susceptible to cracking. In welding, therefore, care had to be taken to minimize the stresses imposed on weld-metal. The company with which Dr. Harris was associated had tackled that problem concurrently with that of distortion-control and accumulating experience was showing that by allowing a small shrinkage-gap and minimizing bending at the root of the weld high temperature cracks were infrequent; when they did occur they were not of a serious character, in that they were readily removed before the weld was completed. In connexion with the recommendation that plates should be stress-relieved after bending, but before welding, he had had such a proposal examined in practice, and as a consequence he was of the definite opinion that no advantage was derived thereby.

The Author referred at some length to the question of plate-material and "pending a definite lead" (as he put it), he gave on p. 637 § 1 a chemical and physical analysis of plate-material which Dr. Harris hoped was not intended to serve as a basis for a steel-plate specification. Manganese-concentrations up to and including 0.7 per cent. presented no difficulty whatsoever in welding, and it was quite unnecessary to restrict the sulphur and phosphorus contents further than to a maximum of 0.05 per cent. each, to do so would be to increase the plate-costs without deriving any advantage. As to the physical properties, he had adequate reason for believing that the steel-plate manufacturers would have considerable difficulty in supplying plates, of the considerable thicknesses being utilized at present, which could be said to approach at all closely the ductility figures cited by the Author.

Dr. Harris had discussed the question of fatigue-characteristics in a publication issued by his company. It was there reported that under actual tests to destruction the welded seams of complete boiler-drums were able to withstand fatigue-conditions better than those parts of the drums which had been accepted as perfectly satisfactory for many years, and further that recent tests of certain full-section welded joints by Professor B. P. Haigh had invariably shown fracture in the plate-material remote from the weld.

§ *Ibid.*

¹ "Strength and Ductility of Cast Steel during Cooling from Liquid State in Sand Moulds," Second Report (1936), Steel Castings Research Committee Iron and Steel Institute, p. 65.

He was very pleased to learn that as a result of experience the only Dr. Harris. authoritative specification in Great Britain was to increase the joint-efficiency of a Class I weld from 82 to 90 per cent. for design-calculations. Such concrete evidence of the increasing reliance that could be placed in welded joints was reassuring, and he ventured to suggest that with still further experience the time would come when a still higher joint-efficiency would be allowable for a Class I weld.

As the Author had pointed out, the Izod test was one about which opinion varied, but it was not irrelevant to point out that if the test were used as an indication of the life or safety of any pressure-vessel, which was surely the primary concern of a specification, then the implications of the test-figures should be the same, independent of whether the steel was weld-metal, rolled plate or forged steel. If the Izod test had proved useless in determining the life or safety of pressure-vessels made entirely from rolled plates or forged steels, there could be no reason to suppose that the test was to take on a suddenly-realized importance because weld-metal was involved. At the same time, there could be no doubt that the impact-test had very little in common with the fatigue-tests as the Author seemed to imply on p. 652 §; that was particularly true of weld-metal.

In connexion with the point of view that was often expressed that a low Izod figure indicated that an incipient crack would easily and rapidly extend, it would appear from his firm's experience of pressure-vessels that such a statement required amplification. Certainly the converse (namely, that a high Izod value indicated that an incipient crack would be propagated with difficulty) was not true. The basis for that statement was that it was not uncommon to find a weld-metal that had considerable porosity characterized by a high impact-value, and, as Mr. Lucas had shown, such heterogeneities facilitated the propagation of a crack by acting as "stepping stones."

With reference to *Fig. 5* (facing p. 654 §), he suggested that the intermediate microstructure was not of the actual fusion-zone, but was of that portion of the plate-material which had just begun to be affected by the welding procedure; the actual fusion-zone would be about $\frac{1}{16}$ or $\frac{1}{8}$ inch nearer the weld.

Mr. HENRY HEADLAND, of Arapuni, N.Z., observed that from the Mr. Headland. point of view of hydraulic machinery in water-power development, the Paper was of considerable interest because of the present-day tendency to substitute fabricated structures for complicated castings and to replace riveted joints by welding in such items as pipe-lines, breeching-pipes, spiral casings, and draught-tubes, which as a rule

Mr. Headland. were not so simple in shape as ordinary boiler-drums. Welded and air-vessels for governors were further applications which came within the category of pressure-vessels.

Apart from the essential feature of watertight joints, which were ensured by good penetration and freedom from porosity, welded spiral casing offered many important advantages over corresponding riveted structure. Effective butt-welding enabled the correct logarithmic shape to be obtained, and the gradual diminishing sections, by elimination of the laps, resulted in a smooth internal surface with a minimum of resistance and disturbance to the flow forming the intake-vortex. Butt-welding eliminated changes of thickness and concentration of stress at rivet-holes, circumferential seams, and the resultant symmetry and simplicity decreased the secondary stresses. In addition, the design was considerably simplified, producing a reduction in weight of up to 20 per cent. and the elimination of marking-out and drilling in the workshops. On the other hand, the setting-up time in the field was probably a little increased, and extra care had to be taken to avoid undue distortion, a feature which, however, was not altogether absent in a riveted spiral casing. Welding had the advantage that the continual noise of riveting and caulking was absent.


Access for riveting and caulking to many parts of spiral casing was difficult, particularly at the junction of the plates and the strengthening ring. In some recent tests on a large casing for a vertical machine it had been found very difficult indeed to get a structure of this type absolutely watertight without resorting to a certain amount of welding, which had to be carried out with a good deal of care in order to avoid the imposed loads being taken by the welds instead of the rivets. In vertical machines, it was important to avoid leakage, which would impose full static pressure on the surrounding concrete during operation, and would also involve difficulties when the finished structure was concreted in place under full pressure. The introduction of the butt-welded seam permitted the joint to have similar mechanical properties and capacity for deformation to those of the plates, with the additional advantage that the surfaces liable to corrosion were always accessible, whilst welds exposed to corrosion could always be made with an electrode specially suited to the conditions.

Metallurgical defects and slag-inclusions acted as points of stress concentration, and when located at or near the outside tension fibres they had a considerable effect on the strength of a butt-weld transmitting bending stresses. The importance of cleaning each run and following the proper procedure for eliminating the crater form at the beginning and end of a run could not be over-emphasized.

generally speaking, spiral casings were erected in the field, and were too large to be stress-relieved except by mechanical means such as dressing with a roughing tool and by the application of a suitable hydraulic pressure-test.


Many of the remarks made above in reference to spiral casings were also common to pipe-lines. In the case of lap-welds, it was a comparatively simple matter to test the joint by specially shaping the plates at the circumferential seam to provide a space for the introduction of pressure-water, whilst with those having butt-welds arrangements could usually be made to test the pipe-line in sections. In pipe-lines the superior strength against impact forces of welded

Figs. 12.



TEST-SPECIMEN N° 1: TOP OF PIPE.

Welds made in semi-vertical position
ultimate strength of plate, 32 tons/sq. in.



TEST-SPECIMEN N° 2: BOTTOM OF PIPE.

Scale: one-half full size.
Inch 1 1/2 0 1 2 inches.

over riveted joints was important when considering the stresses set up by water-hammer. For that class of work butt-welds were preferable for circumferential joints, and were essential for longitudinal seams, in that they were less liable to partial penetration than the lap-weld, which might result in a cavity being left in the corner between the legs of the fillet as well as undercutting. Butt-welds were also an advantage when preparing for sandblasting and painting.

The use of spiral seams in long cylinders under pressure was not mentioned in the Paper, and in the case of pipe-lines it was a problem in economics to decide whether spiral seams, which permitted a 20 per cent. reduction of plate-thickness with the same factor of safety, were justified when the increased costs of rolling and welding were considered. There were several pipe-lines in Europe where that system had been successfully adopted.

Mr. Headland. The Author referred to butt-welds between plates of different thicknesses, and in that connexion it might be of interest to quote results of some tests on joints between two plates, 0.75 inch and 0.4 inch thick, with the weld made as shown in *Figs. 12*. The tests had been made in connexion with a joint in a 12-foot diameter penstock with a working pressure of 75 lbs. per square inch, subject to pressure rises of 30 per cent. As the lower section of the pipe had been inaccessible for welding from the outside, the plates had been welded as shown, and, basing calculations on the $\frac{5}{8}$ -inch plate, the maximum stress was 5 tons per square inch, giving an approximate factor of safety of 6. Cutting the plates as shown had also enabled down-hand runs to be made in all positions. Two tests had been carried out on 32-tons-per-square-inch material with the welded joints made in the semi-vertical position. In both cases the specimens had

Fig. 13.




fractured at the junction of the weld and the $\frac{5}{8}$ -inch chamfered plate. *Fig. 13* showed the sequence of welding after tacking at 18-inch centres around the circumference, which method had been adopted to prevent undue distortion. In work of that type, it was important that a sufficient gap should be left at the root of the weld to ensure satisfactory initial runs of weld-metal. The relatively large mass of parent-metal compared with that in the weld had a quenching effect which might cause the weld-metal to be somewhat brittle and liable to cracking, and if that occurred the cracks would have to be cut out and not welded over. The pipe should be supported to avoid excessive distortion due to shrinkage of weld-metal, but it should not be so rigidly restrained that shrinkage-cracks could develop.

Air-vessels for oil-pressure governors were usually of medium size with comparatively thin walls, and, while being air-tight, were required to withstand working pressures up to 300 lbs. per square inch, with a test-pressure, which took the form of a non-destructive test, of twice the normal pressure. The tensile strength

as usually sufficient when there was no leakage from the vessel. Mr. Headland. The cylindrical shell was usually formed slightly elliptical with the major axis in line with the longitudinal seam, whilst the joints with the rounded ends were made with an adequate bevel on the V to permit proper penetration, and in such a position that excessive stresses were avoided. Butt-welds were preferred because, apart from bending stresses and the inferior strength of the lap-joint, they permitted easier fabrication and proper access for welding. The U-weld, whilst advantageous for X-ray examination, suffered from the defect that the first run of weld-metal had to be cut out and the edges of the plates specially machined, as they could not readily be prepared by oxy-acetylene cutting and

Fig. 14.



grinding. In welded vessels of that type pressure- and temperature-variations in operation resulted in longitudinal and circumferential breathing stresses, so that inferior welding might fail under such conditions.

Tests up to the value of the test-pressure on vessels of that kind with longitudinal or spiral and circumferential seams showed that the longitudinal and radial deformation followed the calculated values closely. In cases where the tests had been continued to destruction, the results had been consistent with those expected from theoretical considerations and tensile tests on the materials up to and beyond the yield-point. In one case the vessel cracked in the plate at right angles to the direction of the hoop-stress, starting from the centre of the hemispherical end up to half the length

Mr. Headland. of the cylinder, after which the fracture had branched into sections continuing the full length of the cylindrical shell. Although from the fact that the branching of the fracture had been due to secondary stresses, a satisfactory explanation of the failure would be interesting. The vessel burst, for practical purposes, at the calculated value.

Such tests indicated that, for ordinary static loading, non-welding methods of design were permissible, and when a good system of design-procedure-control was adopted the welded joint compared more favourably with riveting in regard to considerations of design, construction and cost. When fatigue-stresses were involved, the endurance-limit was more uncertain, and he noted that the range ± 11 tons per square inch had already been questioned. The endurance-limit of a riveted joint, and even of the plate itself, was almost equally uncertain, and it should be pointed out that the value of the fatigue-range of a welded joint depended to a large extent on the condition of the plate and the welded joint, as well as on the preparation to which it was subjected. The curves given in *Fig. 14* showed some typical test results.

Mr. Jasper.

Mr. T. M. JASPER, of Milwaukee, Wisconsin, observed that it might be said that the employment of ductile autogenous welding in pressure-vessel service was about 12 years old in the United States. It was introduced into the most hazardous service, namely, the cracking industry, the pressure-drums of which operated at 900 and 600 lbs. per square inch continuously. It was several years later that the general codes for vessel-construction had been developed to include that method of fabrication. The great advantage of welded construction then introduced had been its non-liability to leakage and the ability of the weld to resist shock, as well as its being of greater strength than that of the normal plate-materials used in the type of service referred to.

Without the very progressive attitude of the petroleum-engineers who were in need of some new method of construction, the introduction of welding would have been much slower. Because of their appreciation, their codes for the use of welded-construction were much more complete and easier to apply than any of the others which had been developed, on account of the great hazard of service and the longer period over which they had used welded drums in service. The joint code of the American Petroleum Institute and American Society of Mechanical Engineers could give the greatest help to those desirous of adopting something which would represent safe welded-vessel construction and operation.

The Author had given a very complete resumé of the general position in the United States, and Mr. Jasper would conclude

mentioning that welding had had the effect of improving the quality of the steel and increasing the number of steels available for pressure-vessel construction.

Mr. JAMES MITCHELL observed, with reference to the Author's remark on p. 623 § that "it is not a difficult matter to assign a definite figure for the efficiency of a riveted joint," that that result had only been achieved by the gradually-acquired skill of the workman, by careful inspection, and by rigid testing. The process described in the Paper as fusion-welding was really a variety of soldering, and considering the enormous number of uses to which soft or tin-soldering and hard or brass-soldering, were put, and the very great uniformity and reliability of joints so made, there seemed to be good reason for thinking that iron-soldering would, as the skill and experience of the operators increased and methods of inspection and testing were improved, become equally reliable and equally widespread. As pointed out in the Paper, such joints—as in soldering processes generally—presented drawbacks, owing to temperature-stresses, and to the differences which were apt to arise between the material of the main body of the plates joined, the solder, and the portions of the plates in its immediate vicinity. With regard to the reference on p. 659 § to the possibility of relieving the internal stresses in such joints by externally-applied static loading, it was probable that every riveted joint had, on completion, a complicated system of internal stresses, which were relieved in that way when the joint was stressed. In cases where there was no hardening or alteration of the constitution of the metal in the soldered joint and its neighbourhood, there would appear to be a good deal to be said for the relief of stress by means of hydraulic pressure, the pressure being increased as slowly as was practicable, so as to allow a sufficiency of time for the flow of the over-stressed metal. In all other cases, normalizing by heat would be the proper treatment.

Mr. V. E. PULLIN was particularly interested in the Author's remarks on the radiographic examination of welds, and to learn that he—very properly, in Mr. Pullin's view—attached such importance to that crucial method of test. It might be imagined from the Paper that the Author attached some importance to the A.S.M.E. assertion that a suitable penetrameter would ensure the detection of any flaw having a thickness of 2 per cent. of the plate. Mr. Pullin very much doubted whether the Author accepted that statement of the A.S.M.E. code, and he rather thought that he would hesitate to confirm it from his own experience. Mr. Pullin's own researches indicated that

Mr. Pullin.

the implied assurance that a 2-per-cent.-thick flaw would certainly be shown under the conditions laid down by the American Code is fallacious.

Mr. Weinrich.

Mr. A. O. WEINRICH, of Mannesmannröhren-Werke, Hückingen, agreed in general with the Author's comments so far as the question of plate-material was concerned; his firm were of the opinion, however, that the manganese- and silicon-contents could be higher than 0.15 and 0.20 per cent. respectively. For instance, they had ascertained that a steel containing from 0.8 to 1.0 per cent. of manganese and from 0.25 to 0.30 per cent. of silicon was perfectly weldable by both the water-gas and the electric fusion-welding processes. Furthermore, it was thought that the question of weldability of material for pressure-vessels had not yet been fully investigated, and it was to be hoped that there would be further development in that aspect of welding technique. It was of interest to note that in Germany there was a tendency towards a diminution of the carbon-content of weldable material, together with a simultaneous increase of alloying elements which had the effect of raising the tensile properties.

It might be stated that the German rules for welded pressure vessels imposed on the German manufacturer certain requirements regarding heat-treatment, and in consequence metallurgical developments in welding had been influenced in the direction of obtaining welds of special character in which heat-treatment might reasonably be omitted. The new German rules made allowance for the progress made in welding technique, in so far as heat-treatment was not required for pressures up to 8 atmospheres, with a tensile strength up to 42 kilograms per square millimetre and a stress up to 4.25 kilograms per square millimetre. When annealing treatment at 650°C. was carried out the welded seam was allowed a joint-efficiency of 0.8 with the proviso that the welded seam had to be subjected to a non-destructive test. In that way no doubt experience would be obtained, and eventually a relaxation of the existing rules would be possible. That precaution appeared to be necessary, in order to protect welding from reverses, the consequences of which could be foreseen.

A series of tests had been carried out in Germany with respect to stress-relief by static loading, which, in conformity with the statements of the Author, had the effect of modifying residual stresses and of removing the stress "peaks." However, there were certain difficulties encountered in that method of relieving pressure-vessels from residual stresses, which mainly occurred due to uneven thickness of the plates which could not be avoided in the plate-manufacture. As a consequence of that, neither the location of the expansion nor the extent of it at a determined static load was a fixed quantity. In that way there could arise critical plastic flow in or beside

ld-seam which, when using steel not resistant to ageing, might lead Mr. Weinrich. accelerated ageing of the material under the high temperatures prevailing in steam boilers.

The AUTHOR, in reply, pointed out that the use of mild-steel plates The Author. 22 and 24 tons per square inch tensile strength, referred to by r. Dipper, had long been common practice on the Continent in the manufacture of both riveted and welded pressure-vessels, and it had been the Author's experience that the highest class of welding work in Germany was any worse or better than that to be found in Great Britain.

In regard to austenitic welds, the martensitic zone had a lower carbon-content than that found in "cutting hard" martensite. That zone was certainly composed of material which might be said to be martensitic, but which might in fact be structurally composed of material in some intermediate phase-condition. In any case, the type of martensite produced as a result of the rapid cooling of low-carbon steels should obviously be placed in a different category from that associated with steels having a carbon content of from 0.8 to 1 per cent.

The method adopted by the investigators in testing the hardness of the martensitic zone in austenitic welds was the Martens scratch method, which entailed the scratching of the specimens with a loaded diamond attached to a moveable lever. The ratio between the load on the diamond point and the width of the scratch gave a hardness figure, which, by means of a factor sufficiently correct for purposes of comparison, could be converted to a Brinell number. The width of the scratch in the martensitic zone under notice varied between 0.01 and 0.012 millimetre, giving calculated Brinell numbers between 40 and 285. The width of a corresponding scratch in tool-steel martensite was 0.006 millimetre, giving a calculated Brinell number of 475.

He appreciated the remarks of Dr. Faltus, and could confirm the importance of ensuring, by regular testing, a supply of electrodes having a consistently high quality. In criticizing bend-tests, the precise reason for specifying a particular type of test had to be borne in mind, and the bend-test referred to by Dr. Faltus was not intended to demonstrate the quality of fusion between the weld-metal and the parent-metal, but rather to demonstrate the ability of deposited weld-metal, contained in that portion of the joint which was least affected by superimposed runs of weld-metal, to withstand deformation.

He was interested to note that the firm with which Dr. Faltus was associated had found X-ray examination indispensable in the manufacture of high-class welded pressure-vessels. X-ray examination

The Author.

had also been discussed by Messrs. Fergusson and Pullin, and it was interesting to note the figures given by Mr. Fergusson for the extra cost involved by the manufacturer in complying with the requirements of regulations such as those issued by Lloyd's Register of Class 1 Pressure Vessels; it was satisfactory to observe that the extra cost could be offset against the higher joint-efficiency allowed. Whilst the Author agreed with the adoption of stereoscopic technique in the X-ray examination of welded joints, especially in the case of thick vessels, it was a question of economics rather than of necessity and had to be decided by the manufacturers themselves. The method of X-ray examination adopted and advocated by Mr. Fergusson was excellent, but it would be appreciated that it was the function of inspecting authorities to specify in detail the adoption of any particular technique having special economic advantages. The Author agreed with Mr. Pullin that no special significance could be attached to the value implied by the A.S.M.E. Code in respect of penetrameters, but at the same time there could be no question that penetrameters should be used in order to provide some indication on the film that full penetration of the X-rays was being obtained. That was especially important in the case of welds which were dressed flush with the parent plate.

Dr. Harris had referred to the practice of allowing a shrinkage allowance at the root of heavy welds, and he agreed that the weld-metal obtained in the first run was severely quenched and was not in the best condition to adjust itself to severe stresses. That was precisely the reason why the first run of weld-metal should be entirely removed from the under-side of the weld, irrespective of whether or not any shrinkage-gap had been provided.

The question of weldability of steel plates, referred to by Dr. Harris and Mr. Weinrich, had become a subject for research under the guidance of a special committee set up by the Institute of Welding, and there was no suggestion that the mechanical and physical analyses of plate-material, detailed on p. 637 §, was intended to serve as a basis for steel-plate specifications. The figures referred to were not uncommon in practice, and material giving such test results had certainly been found entirely suitable for welded joints. Impact-tests had been discussed in some detail in the Paper, and the Author did not intend to imply that there was a definite relationship between impact- and fatigue-test values. What was suggested, however, was that a material giving satisfactory impact-values might not be found satisfactory under fatigue-conditions, but it was necessary in the first place to decide what was a satisfactory impact-value.

in that connexion it would be noted that Dr. Harris had brought The Author. out the point that a high impact-value alone was not necessarily a guarantee of a high quality of material. The Author was indebted to Mr. Jasper for his observations, and could confirm that the development of welding in the pressure-vessel industry owed much to the oil companies.

In reply to Mr. Mitchell, he pointed out that few would be prepared to agree that fusion-welding bore any resemblance to soldering, and to suggest that two such entirely different processes of making joints were analogous was undesirable. He could assure Mr. Mitchell that the skill required for riveting, and the inspection and testing procedure normally applied to riveted joints, did not approach the standard laid down for welding.

In regard to the relief of stress in welded joints by means of static loading, it was considered that there was insufficient evidence of the reliability of such a method, and in all cases of important welded pressure-vessels reliance should be placed on heat-treatment carried out in a properly-constructed furnace. The question of relieving residual stresses by means of static loading had also been mentioned by Mr. Weinrich, and the Author was interested to learn of the tests carried out in Germany, and of the difficulties encountered due to the uneven thickness of plates.

Mr. Headland put forward some interesting information regarding the welding of various structures such as spiral casings and large-diameter pipe-lines, and referred to a number of points which were dealt with in the Paper. He drew attention to the difficulty of obtaining a proper distribution of the load in the case of composite joints involving welding and riveting, and the Author was of the opinion that such joints should be avoided wherever possible. Spiral seams had found some favour on the Continent, but in general it could be said that the simplicity and reliability of the straight longitudinal seam, welded under careful procedure control, had led practically to its universal adoption in the manufacture of welded pressure-vessels. In the case of pipe-lines and long cylinders such as those referred to by Mr. Headland, there might well be special advantages to be derived from the adoption of spiral seams, and it was of interest to note that the system had been used in the construction of several pipe-lines in Europe.

The form of joint indicated in *Figs. 12* (p. 509) was not considered satisfactory in that no attempt had been made to reduce the thickness of the thick plate to that of the thin in way of the weld, and, whilst the results of the static tensile tests given by Mr. Headland appeared to be good, it should be noted that the ultimate fracture occurred at the junction of the weld at its weakest section, and it

The Author. was considered that fatigue tests on samples of that type would leave little doubt in regard to its deficiency.

In regard to butt-welds, the choice between the \vee and the \cup welds was a matter for the manufacturer. The Author had pointed out the advantages of the latter type, and in regard to Mr. Hesland's remarks, it might be said that, for high-class welding-work, plate-edges should always be machined prior to welding, and that in both types of joint the first run of weld-metal at the root of the weld was generally contaminated and should be removed by cutting.

Paper No. 5109.*

"Kincardine-on-Forth Bridge."

By JOHN GUTHRIE BROWN, M. Inst. C.E.

Correspondence.

Mr. R. D. BROWN wished to call attention to a very important question that was often overlooked in the design of swing-bridges : had any provision been made for the repair and renewal of the rollers, and of the upper and lower roller-paths ?

That question had arisen acutely on the Manchester Ship Canal, when it had been found necessary to repair or renew the upper and lower paths and the rollers of several swing-bridges. The swinging weight of those bridges had ranged from 640 to 1,800 tons, and the cost per bridge of the repairs and renewals of paths and rollers had varied from £11,712 to £30,589.†

In every case it had been found necessary to raise the bridge temporarily, and good foundations for the support of the lifting jacks had been found at no great depth. In the case of the Kincardine bridge, however, the foundations would be deep and costly. Some of the problems which would have to be solved in carrying out those repairs were :—

- (1) At which panel-points was it best to raise the bridge, (a) so that no local damage was caused to the structure, (b) so that the minimum reversal of stress in the members was caused, and (c) so that a minimum of additional structural steelwork need be provided ?
- (2) How could foundations be provided capable of sustaining the weight of the bridge-superstructure when it rested upon the lifting jacks ?
- (3) What provision could be made for guarding the bridge from accidental damage by shipping when poised upon the jacks ?
- (4) What provision could be made for traffic while the repairs were being carried out ? Which traffic would take precedence during the repairs—the traffic using the bridge or the traffic using the waterway ?
- (5) What method of repair could be adopted so that the time required might be reduced to a minimum ?

* Journal Inst. C.E., vol. 5 (1936–37), p. 687 (April, 1937).

† R. D. Brown, "The Raising of Barton Swing-Aqueduct and the Renewal of Paths and Rollers." Selected Engineering Paper No. 67, Inst. C.E., 1929.

Mr. Brown.

It was easy to dismiss those problems and to leave their solution to some later stage, but it was obvious that the expenditure of a small sum at the time of building would make provision for those requirements and would avoid the spending of a large sum in the future. In the case of accidental damage, or of damage due to enemy action, it would be possible to repair the bridge in a fraction of the time that would otherwise be required.

The Author.

The AUTHOR, in reply, stated that Mr. Brown had very properly drawn attention to the importance in designing swing-bridges of keeping in view the repairs and renewals that might arise in future.

Particular attention had been given in the design of the swing span of the Kincardine bridge to provide duplicate means of operation wherever possible, so as to prevent a complete breakdown occurring. For the same reason the design was arranged so as to permit repairs and renewals to the rollers and tracks to be carried out with simplicity and expedition.

Should an extensive overhaul of the swing span be necessary in the future, then it would be essential to carry it out with the span in the position open to river-traffic. In that position the structure would be adequately protected from shipping by the timber fendering which would also be available to assist in supporting the bridge when required.

With the bridge closed to road-traffic, vehicles would require temporarily to use the Stirling bridge, as had been the case before the construction of the bridge at Kincardine. No such alternative was available for shipping, however, which had therefore to receive uninterrupted use of the river during repairs to the structure.

CORRESPONDENCE
ON PAPERS PUBLISHED IN
JUNE 1937 JOURNAL.

Paper No. 5085.¹

“The Reconstruction of the Chester—Holyhead Road
near Penmaenmawr, North Wales.”

BY CECIL LEE HOWARD HUMPHREYS, T.D., M. Inst. C.E.

Correspondence.

Mr. T. W. MORAN observed that, apart from the major engineering **Mr. Moran.** difficulties, there had been the ever-present element of danger, which had been increased by the proximity of the existing road above and the railway-line below. The two diversions had improved the traffic-conditions around the headlands out of all recognition, and it was to be hoped that at some future date further widening might be done east of Penyclip and east of Penmaenbach, as certain parts of the road were much too narrow for the volume of traffic that passed during the summer.

The question of leakage through the tunnel-lining, referred to on pp. 70 and 80 §, was a recurring difficulty in vehicular tunnels in water-bearing strata, a very minute quantity of percolation being sufficient to disfigure the interior finish. He rather doubted if continuous concreting would provide a completely watertight lining, as construction-joints were not the only sources of infiltration. If water were present in the rock whilst concrete was being deposited, some porous patches would be almost inevitable, and subsequent pressure-grouting was not always effective in sealing them. There was also the question of the initial shrinkage of the concrete on drying out, which would amount to about $\frac{1}{2}$ inch in 100 feet. The extrados of the lining would be completely restrained by the rough rock-face, whilst the intrados would be relatively unrestrained. The concrete at the intrados would cool off and dry out fairly rapidly, and contraction-cracks would probably occur unless joints of some sort were provided.

Temperature-cracks (pp. 77 and 80 §) were another possibility,

¹ p. 28, *ante*. (June, 1937.)

§ Page numbers so marked refer to the Paper.—ACTING SEC. INST. C.E.

Mr. Moran.

and from observations made elsewhere he would anticipate that the seasonal range of temperature on the North Wales coastal road was quite sufficient to cause hair-cracks. The temperature-conditions of the Mersey tunnel (to give only one example) were much more stable, but surface crazing was visible in the interior finish, particularly near the entrances; that might be due to the interior surface being subjected to greater fluctuations of temperature than the extrados of the lining. The probability was that the hair-cracks which admitted percolation through a concrete lining were due to the combined effect of initial shrinkage and subsequent cold-weather contraction, rather than to the effect of either taken separately. The temperature of the mix at the time of placing the concrete was an important factor in both cases. A familiar feature of concrete-construction was that concrete placed in warm weather was much more liable to develop contraction-cracks than concrete placed in cold weather.

He had had some experience with various forms of cement rendering for the purpose of providing a watertight finish in tunnels, but he had come to the conclusion that any rendering would fail in course of time, either from cracking under secondary stresses or from becoming subjected locally to the full hydrostatic pressure. On p. 70 § the Author indicated that the best solution lay in the use of an interlining, and with that Mr. Moran fully agreed. During the past 2 years he had examined that aspect of tunnel-construction at some length in collaboration with Mr. C. B. H. Colquhoun, M. Inst. C.E., and as a result a special type of cavity lining had been evolved. That consisted of an interior secondary lining spaced about 1 inch from the primary lining, so as to leave a cavity all around for natural drainage. The secondary lining was formed of reinforced "Gunited" concrete and was designed as a self-supporting arch, carrying no load but its own weight. It rested upon longitudinal skewbacks projecting from the primary lining, and was not dependent upon hangers which might corrode away. Frequent openings were provided in the skewbacks to lead away any moisture which might seep through the primary lining, and adequate provision was made for relative movements, and for the relief of all secondary stresses. When further experience had been gained in the use of secondary linings, it was quite probable that an overall reduction in the duration and cost of tunnel-construction might be obtained, as under existing circumstances the measures required to secure complete watertightness in the primary lining were often both tedious and costly.

A feature of the diversion works as a whole was the way they blended naturally into their setting, and that applied not only to the

viaduct and tunnels, but also to the subsidiary work, such as the Mr. Moran.
facing of the rock cuttings.

With regard to the Author's remarks on the lighting of the Penmaenbach tunnel (p. 71 §), he had noticed a somewhat similar effect elsewhere. In the daytime, the motorist might experience an almost instantaneous change from brilliant sunshine to diffused artificial light, which was rather disconcerting. During the past 2 or 3 years several new forms of lighting had been introduced (for example, sodium- and mercury-vapour discharge-lamps), which gave excellent results for street illumination. It would be of interest to have the Author's views on their suitability for the illumination of vehicular tunnels.

Mr. H. F. WILMOT, commenting on the Author's remarks concern- Mr. Wilmot.
ing the concrete lining to the tunnel, observed that construction-joints, but not necessarily expansion- or contraction-joints, were generally considered from various viewpoints. In concrete-work, the description "contraction-joint" was much more accurate than "expansion-joint," since the stresses in the concrete on setting were far more severe than those normally encountered due to temperature-variation. Such joints were essential only where the work was "free"; stresses then developed without restraint, and they naturally tended to relieve themselves at a weak spot, with the result that unsightly cracks occurred.

Where work was constrained, however, as when forming a lining over such an ideal surface as a rough rock-faced tunnel-excavation (and of plutonic rock at that), it was clear that no cumulative movement could take place, and therefore the stress in the concrete remained evenly distributed over the whole of the tunnel-lining, relieving itself where it could by developing hair-cracks, which were harmless and were not unsightly.

That should be the underlying principle also for all road-surfaces. Provided that the foundation was thick and well enough anchored to ensure that the surface-stresses were distributed uniformly, no contraction-joints should be necessary. That clearly presupposed that the wearing surface was adequately attached to the foundation, and applied especially to concrete surfaces. An acknowledgement of the principle should have evolved cross-trenches at intervals to form "cross-beams" with haunches in the foundations of roads, and by so doing would have reduced the overall thickness of ordinary mass-foundations, and incidentally would have tended to cheapen the construction of new roads. Its success would be certain.

Types of surface-construction had been evolved to distribute

Mr. Wilmot.

the temperature-stresses uniformly over the foundation, but he did not know how far they had achieved recognition ; their success was bound ultimately to depend on the degree to which the foundation achieved rigidity, in order to give them the necessary constraint.

The Author.

The AUTHOR, in reply, observed, with regard to the water present in the rock, that while concrete was being deposited there was not enough water, in his opinion, to cause porous patches.

With regard to shrinkage of the concrete, it was quite possible that some hair-cracks were inevitable, but observation actually showed that the real trouble lay in the construction-joints. Had those joints not existed he was of opinion that the amount of water which would have shown on the surface would have been trifling.

Regarding the illumination of vehicular tunnels, he was of opinion that the most satisfactory form which had yet been devised was that which was used in the Mersey tunnel, where the lights were set in deep recesses covered with ground glass, so that glare was eliminated while a high general intensity of lighting was obtained. He would have liked to adopt a somewhat similar system for the Penmaenbach tunnel, but it was not considered that the length of the tunnel warranted the expense, and it was also felt that the form of construction of the tunnel did not lend itself so readily to the use of deep fittings set into the concrete.

Paper No. 51131.

"The Flow of the River Severn, 1921-36."

by Professor STEPHEN MITCHEL DIXON, O.B.E., M.A., B.A.I.,
M. Inst. C.E., GERALD FITZGIBBON, B.A., B.A.I., and MICHAEL
ANTHONY HOGAN, D.Sc., Ph.D., M. Inst. C.E.

Correspondence.

MR. A. A. BARNES, from his knowledge of the gauging-site, regretted Mr. Barnes. that the Authors had not considered it worth while to correlate surface water-slopes at the site with the discharge-measurements. They stated on p. 94 § that "as the channel is neither uniform nor straight, and the bed-slope is irregular, no attempt can be made to compare the observed relations between surface-slope and discharge with any of the formulas for calculating the discharge of open channels." That statement was true in regard to the total length of $\frac{1}{2}$ miles from the Severn bridge gauge to the Bewdley bridge gauge, but at the site itself there existed a straight and uniform reach about 400 yards long with a relatively smooth rock bottom, the gauging-section being in the centre of that portion (p. 85 §). He had visited the site on five occasions during July and August, 1937, and he had been able to obtain the exact water-slopes for the low summer stages. Depth had been taken on each occasion down to the water-surface with a steel tape at ten points in a length of 1,000 feet, the datum points being very accurately-levelled flat-topped nails driven horizontally into overhanging tree-trunks; it had been found possible on calm evenings to register the water-level to $\frac{1}{16}$ inch. The results were given in Table A, and when plotted produced the water-surface slopes *i* given in the last line of Table XI. Unfortunately, no floods had occurred during July and August, 1937, and the range covered was slightly over 1 foot (from 5.40 to 6.42 feet on the standard gauge at the site); sufficient information had, however, been obtained to prove that the site was ideal for a study of water-slopes, and that the fact made the absence of a complete series of readings all the more regrettable.

A formula developed by Mr. Barnes which had not yet been published made it possible to calculate the discharge-curve from the above water-slopes so far as those had been taken. It would be

† p. 81, *ante*. (June, 1937.)

§ Page numbers so marked refer to the Paper.—ACTING SEC. INST. C.E.

Mr. Barnes.

seen that the temperature of the water had been observed in each case, so that having the values of A , m , and i (denoting the cross-sectional area, the wetted perimeter and the surface-slope respectively), the velocity v , and thence the discharge, could be calculated from the formula:—

$$\log \log \frac{vm\rho}{\mu} = \log N + \beta \left[\log \log \frac{g}{2} \cdot m^3 \left(\frac{\rho}{\mu} \right)^2 i \right]$$

$$\text{or} \quad \log \log R_m = \log N + \beta (\log \log B_m)$$

$$\text{or} \quad \log \log (\text{Reynolds No.}) = \log N + \beta \{ \log \log (\text{Barnes No.}) \}$$

in which N was the coefficient of roughness, and the accompanying

TABLE XI.—READINGS IN FEET OF WATER-LEVELS AT THE GAUGING-STATION

Temperature of water: °F.		65	68	63	65	66
Date		21 Aug., 1937.	15 Aug., 1937.	11 July, 1937.	16 July, 1937.	17 July, 1937.
Point.	Distance from gauge: feet.					
A	+531	5.414	5.653	5.713	6.338	6.464
B	+259	5.405	5.647	5.697	6.313	6.436
C	+183	5.402	5.634	5.696	6.307	6.428
D	+139	5.408	5.636	5.699	6.313	6.431
E	+106	5.399	5.631	5.690	6.300	6.425
F	+31	5.401	5.632	5.693	6.300	6.427
Gauge	0	5.40	5.63	5.69	6.30	6.42
H	−102	5.393	5.623	5.687	6.289	6.409
J	−260	5.393	5.613	5.681	6.279	6.395
K	−354	5.387	5.614	5.670	6.277	6.394
L	−494	5.388	5.614	5.671	6.265	6.386
From plottings	+500	5.416	5.651	5.713	6.337	6.459
	−500	5.384	5.609	5.667	6.263	6.382
Fall in 1,000 feet		0.032	0.042	0.046	0.074	0.077
Surface-slope i		0.000032	0.000042	0.000046	0.000074	0.000077

index $\beta = 1.2580 - 0.4343N$. Due chiefly to some very accurate work with surface-slopes by Mr. W. N. McClean on the Mucomir at the outlet to loch Lochy, it was possible to state that the value of N for that type of river was 0.71, and therefore that $\beta = 0.95$. It should be observed that the above basic equation could be represented by a straight line $y = \log N + \beta x$, and it was found, in spite of the very different values of m and i in the two sets of experiments, that all of Mr. McClean's fifteen observations and the five on the river

vern lay exactly on one common straight line when plotted with Mr. Barnes. above co-ordinates. The value of $\log v$ could therefore be calculated by taking the correct values of $\log p/\mu$ for the observed temperatures of the water, as given in Table XII, and by denoting $g/2$ by 1.2067. The results so obtained were given in Table XII, whilst in order to allow the Authors to compare those calculated discharges with those found by them with current-meters, the figures had been reduced to a common average temperature of 50°F. , for which $\log p/\mu$ was 4.8837. For higher gauge-readings the values of A and m were already known from the section, so that

TABLE XII.—DISCHARGES CALCULATED FROM OBSERVED READINGS OF m , i , AND TEMPERATURE.

Date : 1937.	Gauge : feet.	Area : square feet.	m : feet.	i	Water tem- perature : $^{\circ}\text{F.}$	$\log p/\mu$: seconds/ square feet.
1 Aug.	5.40	578	4.05	0.000032	65	4.9454
5 Aug.	5.63	613	4.27	0.000042	68	4.9629
1 July	5.69	622	4.32	0.000046	63	4.9334
6 July	6.30	710	4.86	0.000074	65	4.9454
7 July	6.42	728	4.97	0.000077	66	4.9513

Gauge : feet.	At observed temperatures.				At 55°F.			
	$\log B_m$	$\log R_m$	v : calculated feet per second.	Q : calculated cusecs.	$\log B_m$	$\log R_m$	v : calculated feet per second.	Q : calculated cusecs.
5.40	0.92558	0.73055	0.667	386	0.91917	0.72447	0.647	374
5.63	0.93686	0.74126	0.828	508	0.92883	0.73365	0.797	489
5.69	0.93665	0.74108	0.871	542	0.93163	0.73629	0.850	529
6.30	0.95552	0.75900	1.286	913	0.94954	0.75331	1.248	886
6.42	0.95832	0.76166	1.345	979	0.95181	0.75547	1.302	948

When further values of i could be obtained the complete discharge-curve could be calculated by means of the above formula. It would be of interest to compare the curve with that given by the current-meter observations, seeing that the set of ten water-levels for each value of i could be taken by one man in only 35 minutes with no equipment beyond a steel tape, as compared with probably $2\frac{1}{2}$ hours at least with several observers for one complete set of current-meter observations.

His levellings had disclosed the fact that a serious error existed in the standard gauge-post at the site. That post was in four lengths of cast iron set in concrete and graduated in tenths of a foot, but due

Mr. Barnes.

to some unknown cause the tops of the posts did not form a continuous scale. They should read 8, 10, 13, and 16 feet, but the actual heights were as follows :—

Gauge post : feet.	Datum level : feet.	Error.
8-00	8-000	Taken as standard.
10-00	9-972	$\frac{1}{2}$ inch low.
13-00	12-773	2 $\frac{1}{4}$ inch low.
16-00	15-852	1 $\frac{1}{2}$ inch low.

The posts did not seem to have sunk or to have been disturbed in any way, and hence it had to be supposed that a permanent error of 2 $\frac{1}{4}$ inches had always existed for levels between 10 feet and 13 feet, and that the highest post had also always been low. He wondered how that would affect both the upper portion of the stage-discharge curve and the relation between water-levels at the gauging-site at Bewdley as shown in *Fig. 6* (p. 95 §).

Mr. Griffith.

Mr. W. M. GRIFFITH was surprised that it should have been considered necessary to select a river site for the purpose of studying the best method of measuring and recording discharges. His experience indicated that the best method would depend on the river, the site, the local conditions, the purpose for which the discharges were required, and the staff available to obtain the necessary data. To select a site where the conditions were ideal and presented few difficulties than was normally met with did not appear to provide the most valuable data on the point under investigation.

An executive engineer holding charge of an Irrigation Division in the United Provinces of India would normally, as a matter of routine, be responsible for computing the daily flow of from twenty to thirty different channels carrying discharges ranging from perhaps several thousand cusecs to, say, 10 cusecs. To obtain the necessary data, daily readings of gauges were taken, and at most one discharge per channel per month was observed by a subordinate. To compute the discharges from those data the engineer had a draughtsman who usually had but a slight knowledge of hydraulics and a head clerk who had none. The channels themselves, unlike the site selected on the river Severn, had erodible beds, which were constantly changing, so that the discharge was not a fixed function of the water-level and might vary for the same water-level by anything from 5 to 30 per cent in no great length of time, due to silting or clearance. The problem presented some difficulty, but a method had been adopted which gave good results provided that the data were correctly reported.

Mr. Griffith had at one time been responsible for gauging and Mr. Griffith. computing the daily discharges of the Sarda river at Tunakpur, a te some 3 days' march from headquarters, in the Terai jungle. he river-velocities were too high to allow of the use of a boat, and he only method of crossing the river was on an elephant, which at times had to swim. That river-bed changed its section annually in the flood-season, but it was possible to obtain a reasonably correct stage-discharge curve for the winter flow from the few discharges it was possible to observe in each season. One year in which only one discharge had been observed presented some difficulty, but it had been found possible by careful reasoning to prepare a reasonably correct stage-discharge curve for computing the daily records of flow for that year from the daily gauge-readings which had been recorded. The problem of the best method to be adopted often depended very largely on the purpose for which the gauging was required. For example, if the information were required for computing the total annual run-off for the purpose of comparing it with the rainfall, a record of the daily discharges was necessary, but for that purpose it was not necessary to know the discharge on any one day with great accuracy, provided that the sum of the daily totals was reasonably accurate. If, then, the method adopted were an approximate method giving uniformly a plus or minus error on the three hundred and sixty-five observations of the year, a great deal of the error would balance out, and the annual total would be more accurate than the daily discharges.

On p. 90 § the Authors noted, with reference to *Fig. 4*, that the curve of cross-sectional areas was convex to the depth-axis. The area-curve would theoretically only be a straight line if the sides of the river were vertical or parallel, and were not inclined. Actually as drawn that area-curve was shown as a straight line from about gauge-level 15.0 to gauge-level 19.0. It was not clear how that curve could be obtained, as the sides in that range could hardly be vertical in the light of the Authors' reference to the river overflowing its banks into the shallow areas on either side, and also in view of the change in slope of the hydraulic-mean-depth curve, which indicated a rapidly widening cross-section within that range. Further elucidation of that point would be welcomed.

The Authors noted that the velocity-curve was concave to the depth-axis. It was possible to define the characteristics of that curve rather more completely, as the velocity-curve would approximate to the equation $V = C\sqrt{D - d}$, where V denoted the mean velocity, D denoted the gauge-reading, d was approximately the gauge-

Mr. Griffith. reading at which the velocity became zero, and C was the coefficient for the gauging-site. Judging from *Figs. 4 and 5* (p. 91 §) the value of d was about 5.25, so that the equation might be written

$$V = C\sqrt{D - 5.25}, \text{ or } C = \frac{V}{\sqrt{D - 5.25}}.$$

To find the value of C one value of D and one of V were required. Taking a value of $D = 15.0$, the velocity for that value of D (scaling on *Fig. 4*) was found to be approximately 4.4 feet per second. The equation might then be written

$$C = \frac{4.4}{\sqrt{15.0 - 5.25}} = 1.41,$$

so that the equation to the velocity-curve would become approximately

$$V = 1.41\sqrt{D - 5.25}.$$

The equation for the stage-discharge curve followed directly from that of the velocity-curve, and the stage-discharge curve would therefore approximate to the equation

$$Q = 1.41 \cdot \Delta \sqrt{D - 5.25}$$

where Q denoted the discharge and Δ denoted the sectional area at any gauge-reading D . If values of Δ were scaled from *Fig. 4* and substituted in the above equation the resultant curve would be seen to approximate fairly closely to the value of the stage-discharge

TABLE XIII.

Gauge-reading, D : feet.	$(D - d)$: $(D - 5.25)$: feet.	Cross-sectional area, Δ : square feet.	Calculated discharge, $Q = 1.41 \cdot \Delta \cdot \sqrt{D - 5.25}$: cusecs.	Value of Q_1 scaled from stage-discharge curve, <i>Fig. 5</i> : cusecs.	Difference: cusecs.	Percent of difference
Col. 1.	Col. 2.	Col. 3.	Col. 4.	Col. 5.	Col. 6.	Col. 7.
18.0	12.75	2,600	13,100	13,665	-565	-4.3
16.0	10.75	2,200	10,200	10,600	-400	-3.8
14.0	8.75	1,860	7,760	8,000	-250	-3.1
12.0	6.75	1,520	5,580	5,500	+ 80	+1.4
10.0	4.75	1,215	3,770	3,600	+ 170	+4.2
8.0	2.75	900	2,105	2,050	+ 55	+2.6

curve in *Fig. 5*. Table XIII was given to illustrate that result. Col. 4 gave the discharge Q , calculated by the equation

$$Q = 1.41 \cdot \Delta \cdot \sqrt{D - 5.25},$$

values of Δ (col. 3) being scaled from the cross-sectional-area curve, Mr. Griffith. Fig. 4. Col. 5 gave the discharge-values Q_1 as scaled from the stage-discharge curve, Fig. 5. The difference and percentage of difference as given in cols. 6 and 7.

That example was given as one method of obtaining an approximate stage-discharge curve if only one observed discharge were available. The work described by the Authors was in effect that of rating a gauging-site, at which, owing to fortunate circumstances, the discharge was an unvarying function of the water-level. Under such circumstances, time and opportunity permitted a very accurate rating. Those were ideal conditions which were unfortunately seldom met with in practice at sites where the discharges were required to be known.

When the function altered slowly, due to gradual silting or scour of the bed, it was possible to prepare a normal stage-discharge curve based on average conditions. Values from that curve could be corrected by a percentage factor obtained by periodic discharge-observations. That was the method adopted by the irrigation engineers referred to above. The method would give reasonably correct results provided that the discharge was fairly stable, but it was unreliable if the discharge varied greatly in the interim of the periodic discharge-observations. Where the water-level varied greatly, or where the function changed rapidly and irregularly, the method failed. It also failed where tidal flow affected the water-level, or if the water-level were affected by sluice-regulation below the site, or if the discharge ceased to be a function of the water-level.

He was responsible for gauging the river Great Ouse and its tributaries, and he found that at none of the sites where a record of the daily discharges was required to be known was the discharge a stable, or with one exception even a computable, function of the water-level, on account of:—

- (a) tidal action in the lower reaches,
- (b) the effect of dams and sluices and the rapid growth of weeds in the upper reaches.

That fact had made the problem difficult, but by obtaining daily at the gauge sites both the gauge-reading and the timing of a surface-float, it had been found possible to compute the daily discharges of the river Ouse and its tributaries at ten such sites for the past 2 years with sufficient accuracy to supply the necessary information required for designing proposed improvements to the drainage-system.

The method of computing a river-discharge from the timing of surface-floats was old, but was not well understood and was little used in England, mainly, he believed, on account of lack of accurate

Mr. Griffith.

knowledge of the relationship existing between surface- and mean velocity, and of knowledge of how and under what conditions the relationship changed. The Authors, in using floats for computing the discharge, had assumed that the relationship would hold only for a width of 10 feet across the section, and therefore timed from thirty to sixty floats across the section, which was laborious. It was, however, not illogical to assume that the relationship would hold at least approximately constantly across the section as vertically, because the velocity varied more consistently and regularly across the section than horizontally. Accepting that, it was clear that the timing of one float should give the required information for computing the mean velocity, provided that the relationship be known.

If the float were timed on the line of maximum surface-velocity, the relationship between its timing and the mean velocity then should be consistent for any water-level, and that relationship could be found by rating observations if time and opportunity permitted. Bazin had evaluated that function in his well-known formula

$$\frac{V_m}{V_s} = \frac{1}{1 + \frac{25.4}{C}},$$

where V_m denoted the mean velocity and V_s denoted the maximum surface-velocity, but his evaluation was empirical, based on a series of sixty-one gaugings, and although his value was governed by the hydraulic mean depth, there was evidence that it was not fundamental but was only approximately true within limits, and for a normal symmetrical section. That fact had been recognized, and in using that relationship the normal practice was to divide an irregular section into two or more regular sections by imaginary vertical planes, and to accept Bazin's relationship of $\frac{V_m}{V_s}$ for each

those sections separately. That practice necessitated running floats in each of the sections to compute the net resultant flow.

For the gauge-readers of the Great Ouse Catchment Board to have to run more than one float in the cross-section presented difficulties. The necessity of running more than one float only arose in time of flood when the river spilled over its banks, because it was always possible to find a site where within its banks the river had a regular and fairly symmetrical section. That fact, however, did not help matters, as the correct assessment of the flood-discharges was more important than that of the normal discharges.

In the course of a Paper ¹ published by The Institution in 1927

¹ "A Theory of Silt and Scour." Minutes of Proceedings Inst. C.E., vol. 2 (1926-27, Part 1), p. 246.

had claimed as a hydraulic law that in a flowing section having a Mr. Griffith. stable perimeter the mean velocity in the vertical plane would vary across the section approximately as the square root of the depth.

Accepting that law, it was possible to calculate the values of the maximum surface-velocity in those additional sections in terms of that of the normal section, and so to save the necessity for running more than one float, even in flood-times when the section became irregular. The method was, in effect, an amendment of Bazin's ratio, to suit irregular as well as regular sections.

Discharge-observations taken in those flood-sections had proved that the assumption was justified provided there was reasonably parallel flow, and that by that amendment it was possible to calculate with reasonable accuracy the discharge of an irregular flood-section from the timing of one float run in the line of maximum surface-velocity in the normal main river-section.

Check discharges taken by current-meters at the G.O.C.B. sites showed that the method referred to above of gauging discharges by a single float gave reasonably accurate results, provided that the maximum surface-velocity was accurately assessed by the float, and

that the main error was not in computing the value of $\frac{V_m}{V}$, but in gauging the surface-velocity by the float. Some results, shown in Table XIV, would illustrate the point.

TABLE XIV.

Serial No.	River and site.	Maximum surface-velocity as observed: feet per second.		Difference.	Percentage of difference.	Remarks.
		By meter.	By float.			
1	River Ouse at Brownhill Staunch.	1.96	2.29	0.33	14.4	—
2	River Ouse at Bedford.	1.66	2.01	0.35	17.3	—
3	River Ouse at St. Neots.	2.30	2.60	0.30	11.50	—
4	River Little Ouse at Thetford.	1.25	1.66	0.41	24.6	Discharge run partly blocked by weeds—results unreliable.
5	River Nar at Wormegay high bridge.	1.65	1.64	0.01	0.6	—

Mr. Griffith.

One of the principal errors in float-velocity observations was the due to the effect of wind on the float. Another possible error appeared to be the effect of surface-tension; he was at present investigating that matter, and Messrs. George Kent, Ltd., were making a small portable anemometer to his own design, by means of which it was hoped to eliminate a large part of that error. Having eliminated the variable error, it was hoped to find a means of reducing the error due to other causes.

Some observations made in the tidal river indicated that Bazin's relationship would hold for the ebb-tide, but would give too low a result for the flood-tide. That matter was also under investigation, and he hoped to be able to embody the results in a general Paper on measuring discharges by a single surface-float at a later date.

Mr. Lacey.

Mr. GERALD LACEY, of Roorkee, India, observed that it was of interest to note that, despite the fact that the meters were accurately rated, the discharge by the cup-type meter was, taking an average, 1.5 per cent. greater than that by the screw-type meter. If it were correct to state that the true discharge lay between the two types of observation, the fact was of considerable value. In India the use of current-meters in measuring canal-discharges was steadily increasing. It was evident that in future, when discharges were quoted, the type of current-meter should be mentioned, and it also should be stated whether each section was integrated or whether the single- or two-point method was adopted. It would also be of interest to know whether, when velocities were measured at one point, comparatively remote from the bed (say at 0.60 of the depth), the two different types of meter still displayed the same discrepancy.

In the United Provinces in India, and also in the Bombay Presidency and Sind, adjustable velocity-rods were still largely employed in canal-discharge observations. He had evolved an improved telescopic type which was employed in the United Provinces, whilst in Bombay and in Sind a modified type known as the Lacey-Dapin rod was employed. The rods were formerly known as Cunningham rods, but their use could be traced to an earlier date than Colonel Cunningham's classic experiments on the Ganges Canal, bundles of rods having been used in gauging the Tiber more than a century ago, and poles having been used in Holland. The advantage of rods was that they gave with considerable accuracy the mean velocity in a vertical, and thus saved computation. Also, since rods swept throughout the selected run, they were not constantly exposed to eddies which might characterize one point at a cross-section of a river.

The reference to surface-float observations was of interest. It was evident that in sudden floods the only records available might

float-observations; *Fig. 5* (p. 91§) showed that two out of the three Mr. Lacey. floods had been estimated in this manner. In India it frequently occurred that the only means of computing a river flood-observation was by means of one or two solitary central surface-observations; on occasion record floods had been reported, and found their way into hydraulic literature, when as a fact the floods had merely been estimated from cross-sections, an estimate of the flood-plane from floating debris stranded near high water mark, and a guess as to the correct value of Kutter's rugosity coefficient.

In India for many years to come reliance in river flood-discharges would of necessity be placed on central surface-velocity observations. In *Fig. 19* (p. 111§) the Authors had plotted values of the float-coefficient for different gauge-readings. A large number of float-observations had, however, been taken at different sections. With a fairly regular section it should be possible to correlate the central or maximum surface-velocity with the mean velocity. He would be grateful, provided that the data were available, if another diagram showing the central surface float-coefficient could be given. In his experience the central surface-velocity on a day without a high wind gave very consistent results. When the banks were topped to such an extent as to involve a reduction in the hydraulic mean depth, the discharges for the bank portions would require to be separately computed.

Mr. DAVID LLOYD suggested that the Authors should differentiate Mr. Lloyd. between discharge as a rate and discharge as a volume, which were used synonymously, whereas in places volume discharged, embracing true run-off and seepage, was implied. Discussing the annual period, the Authors (following American practice in snow-regions) selected that commencing on the 1st October, giving as their reason that ground-water storage would then be a minimum. It followed that for purposes of annual comparison the Authors assumed that all the yearly minima were of similar value; in other words, that the yearly low-level of the water-table had a uniform value. Was, however, that assumption likely to be true? It would be of interest if the Authors would indicate the basis of that deduction, since data of water-level tables indicated saturation (a constant zero) at the end of February; also, in general, that was the period of commencement of sub-average flow. Those points had weight with an investigator of problems of discharge from catchments of under 50,000 acres.

The hydrograph of the flood of 6-22 February, 1928 (*Fig. 3*, p. 99 §), presented a rapid decline. It might follow that it would be difficult to support a view that appreciable run-off from the preceding

Mr. Lloyd.

period had been carried over into the period commencing on the 21st February, and it was bound to be concluded that that hydrograph was not typical of winter months. Perhaps the Authors would amplify their statement (p. 105 §) that negative loss "was due to the discharge of rain that had fallen in the previous month." Some hydrologists would regard that negative loss as condensation and would find reason to believe it due to occult rainfall, at least in part. Undoubtedly there was on the average a time-lag between rainfall and discharge. The special feature of the flood of May-1 June, 1924, was its gradual decline, and it would appear that about $1\frac{1}{2}$ inch of run-off had been carried into June. Such a carry-over would not be consistent with a definite (see p. 105 §) relation between run-off and rainfall for that month. It was therefore suggested, as the included hydrographs were of floods of dimensions likely to affect a monthly relation, yet not typical, that it would be of value to ascertain an average hydrograph in order to adduce the average lag between rainfall and run-off. Alternatively, it seems possible to calculate the average lag by mathematical treatment proceeding from the histogram of the drainage-area (derived by equating water-travel lines) similar to discharge-expressions recently elaborated for stream-flow by Mr. R. T. Zoch.¹ It might then be possible to correlate monthly rainfall and discharge in the period of lag.

There was no doubt that the causes which combined to produce the variations in loss were vitiated on a large river drainage-area by the time-lag, but the data obtained at a smaller catchment were not so affected, and appeared capable of analysis. Such a correlation-analysis supported the hypothesis that loss was a function of several meteorological elements. Professor R. A. Fisher's methods of inductive inference showed that there might be several simple relations involved. Would the Authors not consider that the prospect of ascertaining the true relations was in danger of being befogged by the plethora of speculation or prejudice regarding the water-year and augmented monthly flows? All such speculation was directed towards establishing spuriously the fact that loss was a function of rainfall alone, when plainly it was a joint function of several elements as was demonstrated in the case of the Vyrnwy catchment-area.³

Mr. Williams.

Mr. G. BRANSBY WILLIAMS observed that the description of the

§ *Ibid.*

¹ "On the relation between Rainfall and Streamflow." *Monthly Weather Review*, vol. 64 (1936), p. 105.

² "Statistical Methods." London, 1930.

³ D. Lloyd, "Rainfall and Loss over the Vyrnwy catchment-area." *Quarterly Journal Roy. Meteor. Soc.*, vol. 62 (1936), p. 219.

methods of measuring the flow adopted would be of value to those Mr. Williams who had to make similar investigations elsewhere. Since it was often impracticable, however, to make use of instruments such as those described, and the rates of discharge of rivers had then to be ascertained by simpler means, it would have been useful for such cases if the gauging-station could have been placed where there was a sufficient reach of river of uniform section to enable a comparison to be made of results obtained from formulas for velocities based on surface-gradients and cross-sections of channels.

The Parliamentary Joint Committee on Water Resources and Supplies, in their recent Report, had recommended that the Catchment Boards set up under the Land Drainage Act of 1930 should be given the duty of gauging rivers on their tributaries as well as on the main stream. It was to be hoped that that recommendation would be followed and that gauging-stations would be set up in various parts of the Severn catchment, in order that the relationships between the area and the nature of the catchment and the yearly off-flow and intensities of flood-discharges might be more completely investigated than had been hitherto possible in Great Britain. Such investigations would obviously depend for their completeness on self-recording rain-gauges placed at various points on the catchment. The Paper did not state what gauges of that type were situated above Bewdley, nor if steps were being taken to supplement them where necessary.

The application of the remark on p. 98 § that if, in the storm of the 31 May-1 June, 1924, $3\frac{1}{2}$ inches of rain had been discharged in 1 day, the peak of the flood would have been 180,000 cusecs, was a little difficult to follow. In the first place an average of $3\frac{1}{2}$ inches of rain did not fall on the catchment on that occasion, and in the second, even if it had, it would have been a physical impossibility for more than a portion of the total off-flow to have been discharged in 1 day. The period of concentration at Bewdley appeared to be somewhere about 36 hours, and obviously the total period taken by the rainfall to flow off was bound to be much more than that. The storm referred to was worth some study. It had been caused by a secondary depression of a thunderstorm type after a spell of hot weather. The distribution of the rainfall was shown in *Fig. 30* (p. 538). No part of the catchment seemed to have received more than 4 inches, but there were two small areas immediately to the north and south of it which had had more than 4 inches. On the catchment the average was just under 3 inches, or $\frac{1}{12}$ inch per hour during the period of concentration (if that were taken as 36 hours). With 100 per cent. run-off the maximum rate of discharge would have

Mr. Williams.

been 87,700 cusecs. Actually it had been 14,600 cusecs, or 16·6 per cent. of that figure. A total quantity of 11,360 million cubic feet was represented by 3 inches of rain, and according to the hydrograph the run-off was 5,580 million cubic feet, which agreed with the Authors' figure of 48 per cent. of the whole fall. The small percentage was probably due to the fact that the storm was immediately preceded and followed by spells of hot dry weather. The hydrograph indicated, in fact, just what might be expected to occur in the storm. The rain had fallen in a period considerably shorter than the period of concentration and had been heavier on the lower part

Fig. 30.



DISTRIBUTION OF RAINFALL ON SEVERN CATCHMENT ABOVE BEWDLEY
IN STORM OF 31 MAY-1 JUNE, 1924.

of the catchment than on the higher. Part of the flood-water from the lower parts had had time to run off before that from the high parts had arrived, and as the increasing tributary-area had been compensated for by a diminishing rate of rainfall, the discharge had remained constant for a considerable time.

In February, 1928, the opposite conditions had occurred. The rainfall on the mountains on the periphery of the catchment had been very heavy and continuous, whilst on the low lands it had been little above normal. Consequently the flood had depended mainly on the off-flow from the high land, and when that had ceased the rate of discharge in the river had fallen abruptly.


The peak of the probable maximum annual flood at Bewdley seemed to be about 9,500 cusecs. The information in the Paper would appear to show that the peak of the probable 15 years' flood

was 18,000 cusecs. The two figures were in the same ratio as he had Mr. Williams found to apply to the Thames catchment. *Fig. 31* showed graphically the intensity of probable floods on that catchment in relationship to the periods between them, and also showed the curve for W. E. Fuller's formula, which was $Q_{\max} = Q(1 + 0.8 \log T)$.

If the Thames curve were taken to apply to the Severn the probable 50 years' flood at Bewdley would be 22,500 cusecs and the 100 years' flood 25,300 cusecs.

He had been able to collect a good deal of information regarding off-flow/rainfall ratios in different parts of the world; *Fig. 32* (p. 540)

Fig. 31.




showed the limits within which the curves for annual off-flows for uplands catchments in the British Isles usually fell, as well as curves for the Thames, Lee, and Severn at Bewdley, the latter plotted from the data in *Fig. 17* (p. 107 §). As might be expected, it was below the lower curve for the uplands catchments, and above the Thames curve.

It would have been of interest to have had a diagram showing a longitudinal section of the river from its source. It had been held by investigators that the profile of a river became parabolic, and that when it broke through one or more well-defined ridges it formed a series of parabolas; the Severn had cut its way through the Wenlock-edge-Wrekin ridge formed by the band of Lower Silurian rocks, which cropped out at that point next to the New Red

Mr. Williams.

Sandstone strata forming the floor of the wide valley extending from Shrewsbury to the Mersey. A very large lake with a top-water area of over 50 square miles could be constructed by building a dam there, impounding water up to a level of 200·00 O.D. The lake clearly did not come within the bounds of practical politics but a comparatively low dam would form a reservoir with a high flood level of 173·00 O.D. and 15 miles long, with a maximum water spread of over 16 square miles and a capacity of 6,000 million cubic feet. If the normal top-water level were maintained at 168·00 O.D.

Fig. 32.



about 4,000 million cubic feet of storage could be utilized for stream regulation, which would enable a minimum flow of 700 cusecs to be ensured below the dam. From the information supplied in the Paper it appeared that the minimum flow at Bewdley had been 300 cusecs in 1922-23 (stated to be an average year), and 260 cusecs in 1929-30 and in 1933-34. If the portion of the reservoir above 168·00 O.D. were retained for flood-control, by suitable operation of the control sluices the peak discharge of the 100 years' flood could be reduced by 33 per cent., and the 15 years' flood could be practically eliminated. The effect of the reservoir would naturally grow progressively less towards the mouth of the river, and for complete control it would need to be supplemented by other reservoirs, but the benefits obtained

from its construction would be substantial. He was not in a position to express an opinion as to how far those benefits would be worth the cost entailed. The most important items would be the acquisition of the land and buildings that would be submerged, and the diversion of several miles of the joint line of the L. M. & S. and G. W. Railways.

Mr. H. F. WILMOT observed that the extraordinary accuracy obtained from the three methods of gauge-reading over a period of 3 months could naturally only be achieved when spread over a long period of time, and then only for a steady-flowing river whose daily discharge showed no sudden peaks. Even in that case, however, there was no guarantee, either mathematically or practically, that the law of averages was operating evenly when only one reading of the gauge per day was taken, and therefore a slight lack of certainty was possible with regard to results deduced from such readings. The gauge was presumably placed within a stilling device to enable accurate water-levels to be read. Although probably wholly unnecessary, it would be of interest to have one gauge on each side of the river to check whether the pulsations of a river in flood gave irregularities on either side, which, read on a single gauge, would give either too high or too low a reading according to the time of taking it. Comparative charts from automatic records would be of interest but the duplication of apparatus would be too costly.

With regard to the calibration of current-meters, it would be interesting to know over what width of channel there was absence of interference from the sides; for example, a width of 2 feet was obviously inadequate. That would depend partly on the speed; but at any rate for high speeds 4 feet 6 inches seemed somewhat on the small side; any resulting inaccuracy would probably be small, and would give too low a rating.

For the calculation of the hydraulic radius in the case of a river-section where there was berm-flow, it had always been more practical to regard the flow as of two distinct types, and therefore the cross-section as composed of two different types, the main normal section, and the berms, and to calculate the value of each separately, as suggested by Mr. H. J. F. Gourley on p. 150 §. That appeared to give satisfactory results.

The AUTHORS, in reply, observed that a number of interesting questions had been raised which could not be answered without considerably more investigation, and they commended those questions to future investigators.

The decision to adopt a year commencing on the 1st October had been taken after a detailed consideration of the available information

The Authors.

relating to British conditions, and it was satisfactory to note that the Inland Water Survey had adopted the same year. The fact that much useful information could be obtained from a close analysis of a smaller catchment was not denied, but it had to be remembered that the main object of the research was the measurement of the discharge of the river.

On the basis of Mr. Bransby Williams's diagram for the intensities of probable floods (*Fig. 31*, p. 539), the flood of 1886, which was estimated to have reached a peak of 32,000 cusecs, at Bewdley was bound to be reckoned as very exceptional. It showed, however, that even the 100-year flood might be exceeded at any time. The special characteristics of the longitudinal section could not be brought out on a diagram of reasonable size, but the Authors would draw attention to the section printed on p. 21 of the Royal Geographical Society Report.¹

Some experiments already published² showed that the ratio established in the Imperial College channel only differed from that of the William Froude tank (30 feet wide by 12 feet deep) by less than $\frac{1}{2}$ per cent. The commonest source of error in rating current-meters in a small channel was due to wave-action when the speed of towing was approximately equal to the velocity of a wave in the channel. The width was also of importance, but recent investigations³ in Germany had shown that for a width of 1.5 metre (4.9 feet) the effect was very slight, and for widths in excess of 2.5 metres (8.2 feet) no effect could be detected.

The Authors were indebted to Mr. Barnes for pointing out the discrepancies between the upper portions of the scale at the gauging section. That observation showed the importance of frequent checking of gauges founded on material other than solid rock. The lowest portion of the scale was fixed to a steel channel driven down to the rock, but the other portions were founded on concrete blocks sunk in the bank, and had evidently settled since the last observations were made nearly 4 years ago. For that reason it was not considered that the stage-discharge relations in the Paper were likely to be affected, but the error of the scale would need to be corrected in any future work. As the daily discharges were based on the Bewdley scale they would not be affected.

The fundamental difference between current-meter discharge

¹ The Investigation of Rivers, Final Report. Royal Geographical Society, 1916.

² M. A. Hogan, "River Gauging." Department of Scientific and Industrial Research, London. H.M. Stationery Office, 1925.

³ W. Henn, "Grundlagen des Wassermessung mit dem hydrometrischen Flügel." *V.D.I.-Forschungsheft* No. 385, 1937.

measurement and slope-discharge calculations was that in the former The Authors. the observations were confined to one cross-section and in the latter a long stretch of river had to be used. Uniformity of cross-section and straightness of the channel were desirable in current-meter work to avoid errors due to oblique velocities, but were not essential. In slope-measurement a length sufficient to yield a perceptible slope had to be taken, and it was assumed that the area, velocity, and wetted perimeter remained the same throughout. Variations in cross-section caused variations in slope and loss of energy due to the consequent acceleration and retardation of the flow. The common slope-discharge formulas took into account the roughness of the bed and sides, but in applying any slope-formula to a natural channel the variations in cross-section should also be allowed for.

During the dry summer of 1921 the Authors had taken many cross-sections of the river adjoining the gauging-section, and had concluded that the variations at low to medium flows were such as to cause an energy-loss comparable with that due to the roughness of the bed and sides. Since the two sources of loss of energy varied with the velocity there would be a relation between the slope and the discharge for any one stretch of river, but until some method for discriminating between the two sources of loss was discovered it would be impracticable to apply that relation to any other stretch of river.

Mr. Barnes had measured the surface-slope over a length of approximately 1,000 feet close to the left bank where there were over-hanging trees. It was interesting to speculate whether similar results would have been obtained on the right bank, because the line of maximum depth and discharge was closer to the left bank. The slopes varied from 32 to 78 parts in 1,000,000, but taking into account the nature of the measurements there was a possible variation of ± 5 parts in those results.

No doubt when Mr. Barnes published his proposed log-log formula full details would be given of the data on which it was based, but at first sight the influence of viscosity appeared to be over-emphasized. As was well known, the influence of viscosity in pipe-flow varied inversely with the roughness, and in a rough pipe the flow was independent of viscosity. The effect of viscosity was shown up by changes in the flow consequent on changes in temperature, and in some experiments ¹ on very smooth large concrete pipes, where the influence of viscosity should have been most marked, Mr. Barnes had found the maximum variation due to a 19° F. change in temperature

¹ Discussion on "The Law of Flow through Disc-Orifices in Pipe-Lines," and "The Discharge of Pipes lined with Concrete or Bitumen," by A. A. Barnes. Trans. Inst. W.E., vol. xxxviii (1933), p. 186.

The Authors.

to be less than 4 per cent. From studies of curves of vertical velocity distribution in the Severn, it seemed that the surface had to be considered as approaching the fully rough condition, and that consequently there should be little or no viscosity-effect. With a variation of 15° F. about the mean temperature the formula gave a variation of ± 4.5 per cent. in the discharge; that was to say, the flow for a given gauge-reading should be 9 per cent. greater in summer than in winter. The discharge-measurements taken at various times throughout the year afforded no evidence of a systematic variation of that nature. It would be interesting to know the reasons which led Mr. Barnes to assume that the resistance of the channel at Bewdley would be the same as that for the Mucomir channel. A comparison between the calculated discharges and the stage-discharge curve based on current-meter measurements appeared to indicate a systematic divergence as the depth increased.

Gauge-reading: feet.	Discharge: cusecs.		Difference: per cent.
	Measured.	Calculated.	
5.40	380	386	1.6
5.63	500	508	1.6
5.69	525	542	3.2
6.30	870	913	4.9
6.42	940	979	4.1

It should be noted, however, that the divergence between the calculated and measured values was of the same order as the estimated error in the slope-observations. An error of $\frac{1}{16}$ inch in the slope corresponded to about ± 4 per cent. in the calculated discharge at 6.42 feet gauge.

Mr. Griffith's difficulty with *Fig. 4* (p. 91 §) was to be attributed to the small scale of the diagram; the actual figures were as follows:

Gauge: feet.	Cross-sectional area: square feet.
15.0	2,060
16.0	2,230
17.0	2,410
18.0	2,600
19.0	2,820

It would be seen from those figures that there was, in fact, a very

definite increase in width as the gauge-reading increased. A similar difficulty affected Mr. Griffith's determination of the gauge-reading for zero velocity, because for $d = 5.25$, the velocity was approximately 0.5 foot per second, with a discharge of 305 cusecs.

Both Mr. Griffith and Mr. Lacey referred to the use of the single surface-floats. In a straight drainage-channel or canal it might be possible to locate the position of maximum surface-velocity with some degree of accuracy, but the Authors' experience on the Severn was that the maximum surface-velocity altered its position with the stage of the river. Also, even if the position of the maximum velocity were known, there remained the difficulty of ensuring that the float entered the water there. On re-examining the surface-float results it was found that the value of the maximum surface-velocity varied irregularly, and it was not possible to connect those variations with the depth as had been done in *Fig. 19* (p. 111 §) for the average float-velocity. Taking the average of the group of about ten floats run close to the point of maximum surface-velocity in seventeen discharge-measurements, it was found that the average coefficient to be applied to the float-velocity to obtain the average velocity for the cross-section, and thus the discharge, was 0.66. The scatter of individual observations ranged from 0.52 to 0.84 with a single float, but if a number of floats were run and the average taken the range of coefficient was from 0.55 to 0.76. Thus the results for a single float would give the discharge within ± 25 per cent., and for a group of floats within ± 16 per cent. That error was considerably greater than the ± 4 per cent. obtained when from thirty to sixty floats were distributed across the width and an average coefficient varying with the depth was taken as mentioned on p. 110 §.

Paper No. 5069.¹

"The Open-Frame Girder."

By GERALD SALMON GOUGH, M.A., Assoc. M. Inst. C.E.

Correspondence.

MR. E. H. BATEMAN observed that the Author had presented an interesting method for obtaining approximate solutions for the problem of the open-frame girder with parallel chords of uniform stiffness. Approximations of that type were, however, now unnecessary, since

§ *Ibid.*

¹ p. 247, *ante*. (June, 1937.)

Mr. Bateman, the exact solutions of the elastic equations could be obtained by the method of remainder distribution which he had recently introduced for solving simultaneous equations of the type which arose in the analysis of that problem.¹ The exact solutions could be obtained just as easily as the Author's approximations, and moreover Mr. Bateman's method enabled variations in the stiffnesses of the chord-sections to be included in the calculation just as simply as variations in the stiffnesses of the web-members.

Following the method of analysis developed in his own Paper the equations connecting the moments M_1 , M_2 , etc., at the left-hand ends of the chord-sections were easily seen to be of the form

$$0 = -k_{n-1} \cdot M_{n-1} + (k_{n-1} + 6l_n + k_n) \cdot M_n - k_n \cdot M_{n+1} + \frac{1}{2} \cdot k_{n-1} \cdot S_{n-1} \cdot L_{n-1} - \frac{1}{2}(3l_n + k_n) \cdot S_n \cdot L_n$$

where L_1 , L_2 , . . . denoted the lengths of the first, second . . . chord-sections ;

„ l_1 , l_2 , . . . denoted the values of L/EI for the chord-sections ;

„ k_0 , k_1 , k_2 , . . . denoted the values of L/EI for the vertical sections ;

„ S_1 , S_2 , . . . denoted the shears in the first, second . . . panels.

That equation, which was analogous to Clapeyron's equation of three moments for a continuous beam, might for convenience in reference (and in default of a prior claim to title) be denoted Bateman's equation of three moments for an open-frame girder, in which the upper and lower chords were parallel, and of which corresponding sections of the upper and lower chords had the same stiffness. The equation could be derived by the method of analysis used by the Author, or by any other method which commended itself to those who did not share Mr. Bateman's opinion of the advantages of analysis by the least-work system.

In the problem of the seven-panel girder, for which the Author gave approximate solutions by alternative methods, together with the results of an exact solution (the details of which were not given), the coefficients in the three-moment equations had the following values :—

$L_1 = L_2 = L_3 = \dots = L$, and the ratios of $l_1, l_2, l_3, \dots : k_0, k_1, k_2, \dots$, might be written 1, 1, . . . 1 : 1, 1, 1·2, 1·6, 1·2, 1, 1

¹ E. H. Bateman, "The Stress Analysis of Continuous Frames." *Journal I. Struct. E.*, vol. xiv (1936), pp. 398 and 471.

— "Remainder Distribution in the Analysis of Indeterminate Structures." *Engineering*, vol. xciii (1937), p. 571.

² "The Open-Frame Girder." *Journal Inst. C.E.*, vol. 1 (1935-36), p. 6 (November, 1935).

With unit loads at the second, third and fourth panel-points, which Mr. Bateman was the case described by the Author as "half-span loaded," the shears had the following values:—

$$S_1 = 15/7, S_2 = 8/7, S_3 = 1/7, S_4 = S_5 = S_6 = S_7 = -6/7.$$

Entering those values in the three-moment equation, seven equations were available for the determination of seven unknown moments, thus

$$0 = 8M_1 - M_2 - 4.286L$$

$$0 = -M_1 + 8.2M_2 - 1.2M_3 - 1.329L$$

. . . etc.

The coefficients in those equations, together with the solution of the equations by remainder distribution, were set out in the following Table:—

M_1	M_2	M_3	M_4	M_5	M_6	M_7	$L/1000$	R_1	R_2	R_3
8	-1						-4,286	-486	-26	-4
-1	8.2	-1.2					-1,329	-129	-13	—
	-1.2	8.8	-1.6				357	-3	-3	-2
		-1.6	9.2	-1.6			2,086	646	18	4
			-1.8	8.8	-1.2		1,114	-86	26	2
				-1.2	8.2	-1	1,200	0	-10	-2
					-1	8	1,286	-114	-34	-3
500	200	-50	-200	-200	-200	-200	First partial solution.			
60	20	-10	-70	—	—	10	Second „ „			
3	2	—	-2	-3	1	4	Third „ „			
563	222	-60	-272	-203	-199	-186	Final solution.			

In the Table the coefficients of $L/1,000$ had been used instead of the coefficients of L , in order to avoid the tabulation of fractional solutions and remainders. The partial solutions were given to one significant figure only, and they were obtained as follows: the first partial solution for M_1 , given as 500, was obtained by dividing -4,286 by 8, the coefficient of M_1 in the first equation, and changing the sign; that value of 500 was then used in the second equation together with the initial remainder of -1,329, thus:—

$$\{500 \times (-1) - 1,329\}/8.2,$$

which gave 200 (to one significant figure); when the first series of partial solutions had been estimated in that way, those solutions were used in the original equations to calculate the remainders tabulated under R_1 ; those remainders were then used to estimate a second series of partial solutions; the process was repeated until the initial remainders had been sufficiently distributed, and the final solutions

Mr. Bateman. were found by summing the corresponding partial solutions. The abbreviated and improved form of the remainder-distribution method had first been published by Mr. Bateman in a Paper read at the Nottingham meeting of the British Association on the 22 September, 1937.

Thus the values of the seven moments M_L at the left-hand ends of the chord-sections were :—

$$0.563L; 0.222L; -0.060L; -0.272L; -0.203L; -0.199L; -0.186L;$$

the values of $SL/2 = M_L - M_R$ for each section were :—

$$1.071L; 0.571L; 0.071L; -0.429L; -0.429L; -0.429L; -0.429L;$$

and the values of M_R , the moments at the right-hand ends of the chord-sections, were :—

$$-0.509L; -0.349L; -0.131L; -0.157L; -0.226L; -0.230L; -0.243L.$$

The Author.

The AUTHOR, in reply, observed that Mr. Bateman expressed the opinion that a method of approximating to the stress-distribution in an open-frame girder was unnecessary, as the equations could easily be solved by his method of remainder distribution. To the Author that was not obvious. For any structure which was not simply supported there was a difference between the requirements of the designer and of the checker. The former had to arrive at suitable cross-sections from the loads and the working stresses. At present that could only be achieved by a process of trial and error, for which, it might be supposed, quite rough preliminary calculations might be very valuable. The checker, on the other hand, knowing his cross-sections, could and should be precise. For him the full set of simultaneous equations was suitable, and they could be solved by Mr. Bateman's or any other method. It seemed that there might well be room for distinct approximate and precision methods. Further, the Author would not presume to express an opinion as to which was the better or quicker of two methods, one of which he knew and the other of which he would have to learn. In any case he preferred to have more than one line of approach available.

The exact solution in the Paper was obtained by direct solution of the simultaneous equations, a simple process which did not appear to require comment. The equation obtained by Mr. Bateman did not appear to be of particular importance.

LATE CORRESPONDENCE
ON PAPER PUBLISHED IN
JUNE 1936 JOURNAL

Paper No. 4989.¹

“Corrosion of Iron and Steel.”

By Sir ROBERT ABBOTT HADFIELD, Bart., D.Sc., D.Met., F.R.S.,
M. Inst. C.E., and SIDNEY ARTHUR MAIN, B.Sc.

Correspondence.

Dr. CARL BENEDICKS, of Stockholm, thought that, in the very Dr. Benedicks. large amount of valuable information presented in the Paper, a striking point was the regularity of the results obtained, as shown in Figs. 4, 5 and 6 (pp. 25 § *et seq.*), between the observations under aerial, half-tide, and total-immersion conditions obtained at Halifax, Auckland, Plymouth and Colombo. That induced him to attempt to explain the climatic influences in more detail.

Meteorological Data.

Dr. A. Ångström had provided the following data showing the range of temperature at each place, the maximum and minimum values of the relative humidity, with their averages, and the rainfall,

¹ Journal Inst. C.E., vol. 3 (1935-36) p. 3. (June, 1936).

§ Page numbers so marked refer to the Paper.—ACTING SEC. INST. C.E.

Dr Benedicks. the localities being arranged according to the average annual temperature:—

Location.	Average annual temperature: °C.	Range of temperature, $T_{\max} - T_{\min}$: °C.	Maximum relative humidity: per cent.	Minimum relative humidity: per cent.	Average relative humidity: per cent.	Yearly rainfall: millimetres.
Halifax	6.2	12.6	86	77	82	1390
Plymouth	10.5	9.7	88	75	82	1080
Auckland	15.2	8.5	82	73	78	1110
Colombo	26.8	1.7	81	73	77	2240

Although the above temperatures were air-temperatures, they were bound sensibly to apply also for sea-water.

General Wastage under Total-Immersion Conditions.

It was natural to expect the general wastage to increase considerably with temperature under total-immersion conditions that was to say, in the order in the above Table. The action of the local elements, now almost universally accepted as the essential factor in corrosion, was actually known to increase with temperature (the electrical conductivity increased considerably with temperature). The average-wastage figures observed for ordinary steels and iron were, however:—

Halifax	0.51 millimetre.
Plymouth	0.48 "
Auckland	0.43 "
Colombo	0.49 "


That was shown by *Figs. 4* (p. 25 §) and by *Figs. 12* (a) and *13* (a). Thus, there was actually no increase in wastage at all (or even slight decrease) with increasing temperature. On account of the increase in conductivity of the electrolytes on temperature increase (2 per cent. per degree), 0.51 millimetre at Halifax would correspond to 0.72 millimetre at Colombo. The difference considerably exceeded the possible experimental errors.

That remarkable fact proved that there was necessarily some foreign factor, besides corrosion itself, which influenced the general wastage of the totally-immersed specimens. It was not possible to state definitely the character of that foreign factor, but he thought it likely that the cause of the constant wastage was to be found

the formation of an essentially protecting or inhibiting layer on the Dr. Benedicks's surface of the specimens immersed.


It was well known that sea-water contained considerable constant amounts of salts of magnesium (about 0.4 per cent. of MgCl_2) and calcium (about 0.2 per cent. of CaSO_4). During corrosion, caused by the action of the local elements, hydroxyl ions were formed at cathodic portions, making the liquid alkaline there, and precipitating hydroxide of magnesium (and possibly also of calcium) besides hydroxide of iron. The hydroxides would soon change into carbonates (whereby calcium carbonate might also be precipitated), and they would form a coating, protecting the metal to some extent

Fig. 12.



STEEL.

Fig. 13.



IRON.

TOTAL-IMMERSION CONDITIONS.

against continued corrosion. He had had the opportunity of studying in detail several cases of corrosion of Swedish sulphite-pulp boilers, and he had been able to establish that the possibility of using iron or mild steel plate in the boilers in presence of so reactive a substance as sulphite lye was entirely due to the fact that a protecting coating, essentially consisting of calcium carbonate, was successively formed. If that coating were allowed to form for too long a time without being removed, it would finally become so thick that, although adhering strongly, cracks would appear, permitting the coating to scale off locally. At such points extremely strong corrosion occurred until the pressure of the hydrogen formed on corrosion counteracted further attack.

Thus the formation of a thin and partially-protective coating in ocean water seemed to some extent to be supported by actual experience. The temperature would necessarily influence the speed with which that coating was formed, the coating forming more rapidly the higher the temperature, but the actual attack of the metal would be about the same, irrespective of the temperature, provided that the water had practically the same composition as in the open ocean.

Dr. Benedicks.

The assumption that such action occurred would explain the interesting uniformity of wastage independent of temperature. He could see no other probable explanation¹.

Pitting under Total-Immersion Conditions.

He would next consider the fact that a protective coating such as that referred to above would always present local defects. At a point thus unprotected, considerable local corrosion would set in; the renewing of the protecting coating there seemed rather improbable. Such local corrosion, or pitting, would necessarily be expected to increase strongly with temperature. *Figs. 5* (p. 26 §), *12* (b) and *13* (b), for ordinary steels as well as for rolled irons, showed that a very marked increase of pitting with rise in temperature occurred under total-immersion conditions.² Further, the sequence of the localities actually plotted in *Figs. 5* was found to coincide with the sequence of the temperatures of the different localities.

Pitting at Half-Tide: Iron Compared with Steel.

It was now necessary to consider the corrosion in the half-tide experiments.

If it were supposed that the specimens, when in air, dried immediately and completely, the general wastage would be just one-half that under total-immersion conditions, but such a supposition was very far from being true. On account of the presence of salts in solution the surface of the specimens would, even when not immersed, locally be in contact with a salt solution, and would thus locally corrode, or pit. That pitting-corrosion would be much stronger than for the immersed specimens, on account of the free access of oxygen and probably also on account of a higher salt-concentration.

Such pitting was clearly dependent on two factors:

(i) As remarked above, the speed of pitting would increase with a rise in temperature; that would tend to render the pitting a maximum at Colombo.

¹ It might be assumed that the uniformity of corrosion of totally-immersed specimens was due to the temperature of the sea being almost the same at the localities discussed, but in view of the fact that at Halifax the winter temperature of the sea was about 0° C. and the summer temperature about 12° C. while at Colombo the temperature of the sea varied between 25° C. and 30° C. during the whole year, that explanation was excluded. The sea temperature in fact, was one of the main factors determining the air temperature.


² The increase appeared still more regular if the localities at which tests had been made were plotted at distances apart proportional to the actual temperatures rather than at equal distances apart.

(ii) The amount of solution occurring causing corrosion would be much more considerable at a place of low temperature, especially if combined with a high relative humidity, than at a place of high temperature, especially if combined with a lower humidity. Consequently, that factor would cause the pitting to be a maximum at Halifax (average temperature 6.2°C ., average humidity 82 per cent.), and much more pronounced than at Colombo (average temperature 26.8°C ., average humidity 77 per cent.). The great range of temperature at Halifax (12.6°C .) would also contribute to the pitting.

With regard to the observations of pitting for ordinary steels, as shown by *Figs. 5* (upper part), and *14* (b), it would be seen that the maximum theoretically expected for Colombo was very prominent, as well as the maximum for Halifax. For the rolled irons, as shown by *Figs. 5* (lower part) and *15*, the occurrence of the above two maxima was also clear.


It was noticeable that the pitting of steel was in every case considerably stronger than that of iron; that difference was especially marked at the highest temperature (Colombo). The same difference

Fig. 14.



STEEL.

Fig. 15.



IRON.

HALF-TIDE CONDITIONS.

between steel and iron was to be seen for the pitting under total-immersion conditions (*Figs. 12* (b) and *13* (b)); steel was much more corroded than iron at Halifax, Plymouth, and Auckland, whilst at Colombo practically the same value was obtained. Further, the total wastage of steel under half-tide conditions was much higher than that of iron (*Figs. 14* (a) and *15* (a)). Under aerial conditions no definite statement could be made (*Figs. 16* (a) and *17* (a)).

The fact that the steel specimens generally were more corroded than those of iron might be explained by the assumption that the surfaces of the steel specimens were less smooth than those of the

Dr. Benedicks. iron specimens; in view of the great care given to the experimental preparations, however, that seemed very improbable. Steel, therefore, appeared to be more corrodible than iron. From the standpoint of the theory of local elements that was precisely what was to be expected. In both cases the carbon dissolved in the ferrite was bound to be sensibly the same (about 0.03 per cent. of carbon dissolved). The difference, therefore, would be solely that the steel contained much more of the free-phase cementite, possessing a "nobler" electrolytic potential than ferrite, and consequently causing a more effective action of local elements in steel than in iron.

At the start of half-tide corrosion, the difference between steel and iron would not be considerable, but after continued exposure the surface of the steel would grow more and more rough, whilst the surface of iron would be less altered. It would therefore be seen that the stronger pitting of steel, as shown by *Figs. 14 (b)* and *15 (b)*, and also its higher general wastage (*Figs. 14 (a)* and *15 (a)*), seemed to be theoretically satisfactorily explained. It might be added that in sulphite lye, steel was attacked considerably more than iron.

General Wastage under Half-Tide Conditions.

In the half-tide tests the corrosion would take place almost exclusively at the points where liquid was retained; that was to say, it would occur mainly at a rate proportional to pitting. Hence the general wastage at half-tide could be expected to be approximately proportional to the pitting.

If *Figs. 4* (upper part) or *Fig. 14¹ (a)* were compared with the curve for pitting (*Fig. 14 (b)*), it would be seen that that conclusion was not well verified, in so far as the wastage at Halifax was much less than would be supposed from the pitting there.

In his opinion, the reason of that would be found in the atmospheric conditions at Halifax. On account of the great amount of rain (1,390 millimetres) falling there during the year, and also due to fogs, which exerted a moistening and washing influence, the major portions of the surface of the specimens were bound to be washed purified from salt, the effect being to reduce the general wastage considerably; that would not necessarily reduce the pitting effectively, as salt might persist in the pits. It might be objected that at Colombo the amount of rain in a year was much greater (2,240 millimetres) than elsewhere; that rain fell, however, during


¹ *Figs. 4* would have to be redrawn so as to give the same sequence of localities as *Figs. 5*; that was to say, the sequence of temperature. In order to avoid that, *Fig. 14* had been drawn.

much shorter period, so that the effective washing action might be much less. Taking that fact into consideration, the difference between the general wastage and pitting at half-tide was not difficult to understand. It might be added that a certain protecting coating might also be formed during half-tide tests, but it was bound to be much less protective than if formed quietly under total-immersion conditions.

General Wastage and Pitting on Aerial Tests.


The pitting in aerial tests increased fairly regularly with increasing temperature for both steel and iron (*Figs. 5, 16 (b), and 17 (b)*). That seemed quite natural in view of the rate of attack increasing with temperature, but, on the other hand, it proved that, even at the hottest locality, liquid remained on the surface of a specimen. That seemed to him to indicate the presence of a certain amount of salt, which was natural at any locality situated in the vicinity of the ocean, as were the four sites selected. At a place like Delhi, how-

Fig. 16.



STEEL.

Fig. 17.



IRON.

AERIAL CONDITIONS.

ever, situated far from the coast and from salt-deserts, it was very improbable that liquid would remain on the surface of an iron object like the well-known pillar, and thus the general wastage would be expected to be very small, as compared with that of Colombo. A further point was that the rain falling in the south of the Himalayas probably contained some nitric acid, which tended to form an oxidized preserving coating on an iron object.

The general wastage, on the whole, could be reasonably compared with the pitting, as shown by *Figs. 16 (a) and 17 (a)* (compared with *Figs. 16 (b) and 17 (b)*). The general wastage at Plymouth, however, was evidently much greater than that at Auckland, which could not be expected from the temperatures. The fact that the relative humidity at Plymouth (82 per cent. average) was greater than at Auckland (78 per cent. average) might appear to explain that

Dr. Benedicks, anomaly; further, it seemed natural to assume that the air at first place was more polluted by traces of sulphuric acid than at second, due to a greater industrial use of coal.

At Halifax the depth of pitting of iron was found to be zero (*Fig. 17 (b)*), whilst some pitting occurred in steel. That difference might be explained by the greater smoothness of the irons, already mentioned. Some further reason, however, seemed necessary to explain the lack of pitting at Halifax. Such a reason might be found in the frequent occurrence of rain and fog at Halifax, which would effectively wash away the salt-particles existing everywhere near the sea-coast. If the surface was smooth, no pitting would therefore, arise.

The Influence of Scale.

As emphasized by Dr. U. R. Evans (p. 615†), it had been found that a mill-scale led to pitting, although on the average it had no appreciable influence on the corrosion as a whole. It might be appropriate, however, to remember that the influence of scale was necessarily two-fold. A mill-scale coating possessed electrolytically a much "nobler" character than iron or steel; as long, therefore, as the scale-coating was a continuous one, it would preserve the material against attack and would reduce the general wastage to an extremely low figure. As soon as cracks became appreciable, however, strong pitting would result, since the action of local elements between the scale-free portion and the surrounding scale-coating was necessarily a very strong one. Scale would, therefore, at first give a very low corrosion-loss, but later a very high one. Those influences might compensate each other, so that no appreciable influence resulted.

The "noble" character of the scale was probably connected with the fact mentioned by Dr. H. B. Footner (p. 617†), that paint, which adhered satisfactorily to a free iron surface, possessed a poor adhesion to surfaces covered with scale; that point had generally been overlooked. Thus, the well-known ineffectiveness of painting on a scale-bearing surface was not essentially due to a loosening of the scale, but to a loosening from the scale. That was a very interesting observation, which clearly needed some explanation. At present very little was known regarding the adhesion of a substance to another substance, or the wetting between a liquid and a solid. It was almost certainly the case, however, that the adhesion of wetting was good in any case where a chemical reaction took place.

For example, he had discovered that, in vacuo, pure molten iron

† Journal Inst. C.E., vol. 3 (1935-36) (October, 1936).

did not wet an aluminium-oxide crucible, whilst molten steel did. Dr. Benedicks. The reason was bound to lie in the fact that the carbon of the steel reacted with the crucible walls, at least to some extent, whilst between carbon-free iron and the crucible walls no appreciable reaction took place. If it were assumed that the more intense the reaction taking place, the stronger was the adhesion, it followed that the linseed oil of the paint, containing acids (in the form of isolinoleic acid) which partially attacked the iron, caused a strong adhesion. The iron oxide ($\text{FeO} + \text{Fe}_3\text{O}_4$), however, having a more "noble" character, was probably considerably less attacked, so that the adhesion might be much lower. If an addition could be made to the oil so that the iron oxide was slightly attacked, a good adhesion would probably result.

Corrosion-Fatigue.

Mention was made on p. 10 § of what was known as "corrosion-fatigue." There was no doubt that a corrosive liquid, which, as pointed out above, wetted the metal, might, if the metal were stressed, easily penetrate through grain-boundaries or small cracks, thus considerably reducing the strength of the material. He was convinced, however, that the true corrosive action of the liquid was unnecessary; if the surface of a stressed solid were surrounded by a liquid which merely wetted it (without appreciably attacking it) that was bound to be sufficient to cause a very considerable lowering of the strength of the material. A good example was given by glass strips, which had been scratched with a diamond under constant pressure; it was found that the breaking load of the strip, when the specimen was wetted with distilled water or other liquid, was diminished to less than 50 per cent. of the value obtained on a dry specimen (that was to say, with air as the outer medium in contact with the surface of the specimen).

Summary.

The preceding analysis of the data enabled certain conclusions to be drawn which might be summarized as follows:—

- (1) Very approximately, the depth of pitting, in total-immersion as well as in aerial tests, increased roughly in proportion to the air temperature.
- (2) The half-tide tests showed that on that influence of temperature on the rate of pitting, there was superimposed an opposite effect, which was weak at high, and strong at low, temperatures. That effect, no doubt, was the easy condensation of water at low tempera-

Dr. Benedicks. tures, which was naturally the primary cause of corrosion. On account of the presence of salt, the occurrence of much water, at low temperatures, caused a very strong pitting in half-tide tests.

(3) The most striking fact regarding general wastage under conditions of total immersion was that it did not increase with increasing temperature, as might be expected. The cause was doubtless that a protecting coating would rapidly be formed on iron or steel surfaces in sea-water, the formation of the coating being comparable with what was known regarding certain protecting coatings occurring in industry.

(4) The effect of humidity in accelerating corrosion might under certain circumstances be the opposite to that stated in (2) above. A large amount of rain and fog during a great part of the year was bound to have the effect of cleaning the surface of the specimens, so counteracting corrosion; that was especially true in the tests at Halifax. That cleaning action, however, scarcely appeared to remove the salt existing in the pittings formed.

(5) The fact that the aerial and half-tide wastage at Plymouth was more intense than that at Auckland might be due to the higher relative humidity at Plymouth, but might possibly also be due to a less pure atmosphere there.

(6) Carbon steel was generally more corroded than iron, which was what was to be expected.

(7) From the foregoing the essential character of the results observed on iron and carbon steel seemed to be fairly well explained by considering the known meteorological factors, on the theory of local elements. The only special assumption made was the formation of a protecting coating in sea water (Conclusion 3), and eventually of a less pure atmosphere in Plymouth (Conclusion 5). No individual differences in the action of the sea water, nor any other unknown factors, were necessary.

(8) An explanation was put forward for the reason why paint adhered better to iron than to iron oxide.

(9) It was pointed out that "corrosion-fatigue" was merely a special case of a general effect, implying that the strength of a material was effectively lowered by the presence of a wetting liquid medium surrounding the material.

The Authors.

The AUTHORS, in reply, observed that a communication from such an eminent authority as Dr. Carl Benedicks would, they were sure, be appreciated and would be studied with considerable interest by those following the work of the Sea Action Committee. Of particular interest was the explanation afforded for the remarkable degree of uniformity of the wastage by corrosion of steel and iron totally immersed in the sea under the various climatic conditions, even

though, as Dr. Benedicks rightly pointed out, the temperature of the sea as well as that of the air varied to a great extent between the different stations.

There were several factors connected with sea-water which might make its action different from that of simple salt solutions in the laboratory. Instances of the action of "inhibitors" in comparatively small proportions in modifying the attack of corrosive agents were many, whether through their chemical action or by the formation of protective films; the possible action in the latter way, which Dr. Benedicks suggested, of the magnesium and calcium salts which existed in sea-water, should therefore receive consideration, based as it was on their observed action in other directions. How far the formation of a film from those constituents might co-operate with, or be hindered by, the presence of molluscs was naturally a point to be taken into account.

A further interesting suggestion was with regard to the maxima of pitting action found under half-tide conditions, both in the hot climate at Colombo and the cold one at Halifax, and there seemed much to be said for the idea that greater condensation under the latter conditions could be equally effective in causing pitting as the higher temperature and generally drier condition of the steel in the former. In that connexion, the Authors had indicated a further factor as likely to have been operative in causing excessive pitting under half-tide conditions at Halifax, namely, the presence of oil for a period, an idea which seemed to be borne out by the results of the 10-year specimens, which did not show the same excessive pitting.

Regarding the relative corrosion of the rolled irons and the ordinary steels, such superiority as the former possessed was considerably modified when comparison was confined to specimens which had been exposed with their rolling-scale removed. Under such circumstances, whilst the irons were slightly but distinctly superior to the steels in general wastage, they were inferior in respect of pitting. Thus, referring to Tables IX to XII (pp. 73-76 §), whilst the general average of the wastage of the irons was 0.579 millimetre, that of steels A and C was 0.617 millimetre; the corresponding figures for pitting were 1.38 and 0.92 millimetre respectively.

The Authors were glad to have Dr. Benedicks' observations on the question of the Pillar at Delhi, and his further confirmation of their conclusion that its excellent state of preservation was to be attributed to favourable climatic conditions rather than to any special corrosion-resisting properties of the iron of which it was formed. Those engaged in the intensive study now proceeding on

The Authors.

the protective influence of paints would no doubt also welcome the suggestions made by Dr. Benedicks regarding the factors affecting the adhesion of paint to a scale-bearing surface.

The causes of the peculiar behaviour known as "corrosion-fatigue" were still obscure and were for the present largely a matter of conjecture; whilst it was natural to suppose that corrosive action was bound to be at work, that, as Dr. Benedicks rightly pointed out, was by no means certain. The subject was a most interesting as well as important one, and as suggested, research in physical science in other directions might, well be brought to bear on the problem.

Paper No. 5084.

“Experiments on the Flow of Water in Pipe-Bends.”

By HERBERT ADDISON, M.Sc., Assoc. M. Inst. C.E.

(Ordered by the Council to be published in abstract form.)¹

THE experiments described in the Paper were begun in the hope of resolving some of the doubts that, in spite of the information recently published on the subject by The Institution,² still remained. The bends used were of square cross-section, of 6-centimetre (nominal) side, and 12-centimetre (nominal) mean radius, and they could be built up together with lengths of intervening 6-centimetre-square straight pipe into various systems of continuous and reversed curvature (*Figs. 1*, p. 562). The complete system was laid in a horizontal plane, and the mean water-velocity through it ranged between about 2 and 5 metres per second. In one set of experiments the bends and straight pipes were of brass, smooth-machined over the entire internal surface, and in the other they were of unmachined cast iron.

The various arrangements used are shown in Table I (p. 563); thus in series 3, ACDBF(LR), the water flowed in turn through inlet-bend A, two straight sections C and D, outlet-bend B, and outlet straight section F. The first bend is a left-hand bend and the second a right-hand, and this is indicated by the letters LR appearing in brackets at the end of the code expression of the arrangement of pipes. The mean values of the ratio $\frac{\text{apparent energy-loss}}{\text{velocity-head}}$, or the coefficient of loss, relate to mean velocities of from 3 to $3\frac{1}{2}$ metres per second, and were computed as follows:—At each of the measuring planes aa, cc, etc. (*Figs. 1*), there were five pressure-orifices spaced

¹ The MS. and drawings can be seen in the Institution Library.—ACTING SEC. INST. C.E.


² A. H. Gibson, T. H. Aspey and Fred Tattersall, “Experiments on Siphon Spillways.” Minutes of Proceedings Inst. C.E., vol. 231 (1930–31, Part 1), p. 203.

Powys Davies, “The Laws of Siphon Flow.” Minutes of Proceedings Inst. C.E., vol. 235 (1932–33), p. 352.

Note.—The Paper on “The Flow of Water through Rectangular Pipe-bends,” by Powys Davies and S. V. Puranik (*Journal Inst. C.E.*, vol. 2 (1935–36), p. 83, February, 1936), had not been published when the Author's experiments were made.

as shown, and from the observed pressure-head at each orifice the mean pressure-head at the measuring plane was computed. The apparent energy-loss between any two measuring planes was taken as the difference between the mean heads at those planes. The last column of Table I was obtained by adding to the observed losses in the bends the observed loss in the intervening straight

Figs. 1.



pipes when these were tested as a complete straight system without bends.

From Table I it appears that:—

- (1) rough cast-iron bends or systems usually have much greater coefficients of loss, in equivalent conditions, than smooth brass bends;
- (2) changing the "hand" of one bend of a system from right hand to left hand or *vice versa* has little definite effect on the overall loss in the system, though it may considerably influence the apparent loss in the individual bend;

TABLE I.—ANALYSIS OF HEAD-LOSSES.

Reference number of series.		Arrangement.	Number of experiments utilized.	Mean values of the ratio $\frac{\text{apparent energy-loss}}{\text{velocity-head}}$.			Sum of separate losses.
				In inlet or upstream bend.	In outlet or downstream bend.	Total loss in system.	
BRASS	12	ABF(LR)	3	— 0.0	0.081	0.167	0.372
	2	ACBF(LR)	4	— 0.019	0.124	0.227	
	3	ACDBF(LR)	4	— 0.026	0.142	0.277	
	4	ACDEBF(LR)	4	— 0.029	0.122	0.381	
	6	ABF(LL)	5	— 0.067	0.091	0.131	
	7	ACBF(LL)	5	— 0.055	0.116	0.208	
	8	ACDBF(LL)	5	— 0.054	0.111	0.269	
	9	ACDEBF(LL)	5	— 0.057	0.118	0.374	
	BRASS	13	EBA(LR)	3	0.150	0.186	
14		EBCA(LR)	3	0.087	0.220	0.486	
16		EBCDA(LR)	4	0.085	0.272	0.594	
15		EBCDFA(LR)	4	0.081	0.327	0.759	
17		EBA(RR)	6	0.035	0.288	0.432	
18		EBCA(RR)	6	0.088	0.271	0.489	
19		EBCDA(RR)	6	0.085	0.317	0.605	
20		EBCDFA(RR)	6	0.089	0.363	0.767	
IRON		28	EBA(LR)	6	0.289	0.211	0.674
	27	EBCA(LR)	6	0.169	0.219	0.706	
	26	EBCDA(LR)	6	0.170	0.348	0.854	
	25	EBCDFA(LR)	7	0.172	0.494	1.061	
	21	EBA(RR)	6	0.139	0.269	0.581	
	22	EBCA(RR)	6	0.179	0.238	0.665	
	23	EBCDA(RR)	6	0.154	0.369	0.826	
	24	EBCDFA(RR)	6	0.162	0.493	1.041	
							0.830

- (3) the coefficient of loss of a bend may be greatly influenced by its position in the system, and therefore it is not permissible to estimate the total loss in a system by adding to the losses in the bends the measured loss in the straight elements.

Examination of the effects of the joints in the system, and of the error involved in taking the mean pressure-head to represent the energy at each measuring plane, showed that these were normally too small to invalidate the above conclusions. The influence of the mean velocity in the system on the coefficient of loss was found to depend on the smoothness of the material and on the arrangement of the bends. The value of the exponent n in the expression

$$\text{head-loss in system} = \text{constant} \times (\text{mean velocity})^n$$

varied from 1.89 for arrangement EBCDFA(LR), brass, to 2.01 for arrangement EBA(LR), iron. When the system approximated to a long, smooth, straight pipe, therefore, the overall coefficient of loss diminished slightly as the mean velocity increased, but the coefficient of loss was independent of the mean velocity when bends predominated in the system, and the pipe-walls were rough.

After the experiments summarized in Table I were finished, a few further tests were made to find the effect of the outlet conditions on the performance of the downstream bend; thus, instead of allowing brass bend A, when forming part of the system GBCDEA(LR), to discharge into the 6-inch outlet-pipe, it was connected to an open-top tank. This, however, had no sensible effect on the coefficient of loss, which merely diminished from 0.327 to 0.311. On the other hand, when brass bend B was the downstream bend of the system ACDEB(LR), it had the following values of coefficient of loss: with 6-centimetre square section F downstream, 0.122; discharging directly into 6-inch outlet-pipe, 0.159; discharging directly into open-top tank, 0.093; with short flared section G downstream, and then discharging into open-top tank, 0.095. It appears, therefore, that the flared outlet of bend A, in which the section is increased from 6 centimetres square to 10 centimetres square in a length of 3.2 centimetres, although downstream of the measuring length, is responsible for more than half the loss in the bend.

Paper No. 5104.

“A Proposed Formula for use in Traffic Surveys, Particularly
Applicable to the Construction of Branch-Line Railways in
India and Similar Countries.”

By WILFRED ERIC RANDALL GURNEY, M. Inst. C.E.

*(Ordered by the Council to be published in abstract form.)*¹

IN estimating the dividend prospects of a proposed railway, it is generally admitted that, after the completion of an engineering survey, all the factors required can be known with sufficient accuracy except the estimated gross earnings of the projected line, unless a railway is to be constructed for a definite purpose such as to serve a new harbour or a mining area, and in certain other cases. The majority of railways in India and in countries with similar development to India are, however, not constructed to serve an area with any particular industries or to shorten the route to some important centre, and thereby to enable the constructing company to compete more favourably with a rival railway system. They are constructed simply because the area they are to pass through is not served by any other nearby railway, and is sufficiently large and populous to make a branch-line construction through the area a reasonable proposition. In such cases it is found that there is considerable difficulty in estimating satisfactorily the gross earnings of the future line and, consequently, in deciding whether the project is a paying proposition or not.

It was recognized in India some 40 years ago that the dividend prospects of such lines depended more or less on the density of population of the country through which the projected railway was to pass, and, since then, it has been customary in India to take the density of population of the country traversed into consideration in making traffic surveys for new projects. Motor-cars and motor-buses have, however, in recent years reduced railway earnings considerably, and made it necessary to estimate the dividend prospects of a proposed railway with greater accuracy than formerly. Moreover, buses have increased the effective range of a railway

¹ The MS. and drawings can be seen in the Institution Library.—ACTING SEC. INST. C.E.

station, and roads running at right angles to existing railways and served by motor buses act more or less as feeder lines and bring in traffic. Parallel and nearby roads on the other hand take traffic away from them. Formulas which in the past gave sufficiently accurate results can no longer be relied on to do so.

The Paper describes an empirical formula for calculating the earnings of a projected railway, obtained after comparing the actual earnings of some forty representative stations on the Great Indian Peninsula Railway with the area of land served by each station; the population-density in the area; the average price of land; the average cost of labour; the mileage and direction of the roads in the area; the size of the largest town served and its distance from the station; the type of town served, and so on.

The figure for coaching earnings is obtained by taking the population of each town and village in the area served by a station and multiplying these figures by a number, which for towns of over 20,000 inhabitants would be 6, for towns between 10,000 and 20,000 inhabitants 5, for towns between 5,000 and 10,000 inhabitants 4, for towns between 2,000 and 5,000 inhabitants 3, and for villages of under 2,000 inhabitants 1. For all towns and villages within 1 mile of a metalled road but over a mile from the station the above figures should be doubled. The figures thus obtained are marked on a 1-inch map against the various villages and towns, and the area served by each station is sub-divided into sub-areas by drawing circles with a common centre at the site of the railway station or proposed station with radii of 1, 2, 4, 6, 10, 15 and 25 miles respectively. Where, however, a road leads away from the railway station, the radius of each circle, as it cuts the road, is doubled so as to allow for the value of the road in encouraging traffic on the railway.

The population-factor for each sub-area is then calculated separately, any portions of a circle or of its projection along a road which may come within a shorter distance of any other station either on the proposed railway or on any existing railway being omitted. The population-factor in each sub-area is multiplied by the following factors:—

1st ring,	0—1 mile radius	× 3
2nd „	1—2 miles „	× 2
3rd „	2—4 „ „	× 1½
4th „	4—6 „ „	× 1
5th „	6—10 „ „	× ½
6th „	10—15 „ „	× ¼
7th „	15—25 „ „	× ⅛
Allowance over 25 miles		× ⅙

The total figure thus obtained represents the population-factor

of the station which is being considered, and, in order to obtain the probable coaching earnings, this factor is first multiplied by Rs. 0.7 (Rs. 1 = 1s. 6d.) which is an average figure of coaching earnings per unit of the population-factor obtained from the actual coaching earnings of a number of stations on the Great Indian Peninsular Railway, and the result is multiplied by one of the following coefficients depending on the nature of the station :—


1.4 for stations at which mail and express trains stop.

1.2 for stations which serve a district or divisional headquarters or the capital of a native state.

0.7 for a military station or railway colony where the earnings are found to be lower, due, presumably, to the cheap tickets and free passes issued; wayside stations with no metalled cart roads leading up to them; and all stations on branch lines.

To the above figures must be added the earnings from any special coaching traffic expected which is not dependent on the

Fig. 1.



normal population of the area, such as pilgrim traffic. Where large towns are connected by roads with the proposed railway, the existing motor traffic should be estimated and the value of it deducted from the earnings of these stations, as given by the formula. It should be noted that, in the construction of a branch line, the area served by the existing railway will be reduced by the area served by the new railway; this will result in decreased earnings from some of the stations on the existing line, but the loss should be more than counterbalanced by the earnings from the new stations.

Goods traffic may be divided into traffic from special industries and general traffic. The revenue from special industries, such as coal and other mines, stone and lime quarries, cement factories, cotton mills, etc., must be estimated separately. The general goods earnings can be obtained from the following formula :—

$$\text{General goods earnings} = P \sqrt{\frac{L}{100}} [0.1 + R], \text{ where } P \text{ denotes}$$

the population-factor of the station as given for coaching earnings, L denotes the average cost of land per acre in the area served by the station (roughly as given in the estimated cost of land for the proposed railway), and R denotes a coefficient depending on the number of miles of metalled road in the area served by the station. *Fig. 1* shows a curve utilized for obtaining this coefficient, and is based on figures worked out for a selected area on the G.I.P. Railway.

The Author claims for the formula not only that it gives a more reliable means of calculating the gross earnings of a project than those usually adopted in India, but also that it is, as far as he knows, the only formula that has been proposed by which the location engineer can calculate the effect on traffic earnings of altering the alignment and position of stations.

Paper No. 5125.

“Some Canadian Wharf-Structures of Steel Sheet-Piling.”

By ROBERT FERGUSON LEGGET, M. Eng.
Assoc. M. Inst. C.E.

*(Ordered by the Council to be published in abstract form.)*¹

THE Paper describes six wharf-reconstruction projects, carried out in widely differing parts of the east of Canada, which utilized interlocking steel sheet-piling as the main permanent unit of construction. It commences by commenting upon the attention now being devoted to that type of structure, known variously as the bulkhead or flexible type of retaining wall, and in the description of the six works, each of which has some special feature by reason of its location, reasons for the selection of this material and details of the cost are given.

As all the works described in the Paper were carried out for the Department of Public Works, Canada, a brief description of this interesting branch of the Dominion Government is presented. In more recent years many of the original duties of the Department have been delegated to other agencies (several going under provincial jurisdiction in 1867) and a summary of this development is given.

Reconstruction of Protection Jetties at L'Anse au Beaufils, Quebec.—At l'Anse au Beaufils, on the southern coast of the Gaspé peninsula, is a small enclosed fishing harbour. Its entrance is protected by two jetties, parts of which were completely demolished by a phenomenal storm in October, 1933. At that time, forty fishing boats were sheltering in the harbour, and reconstruction of the entrance had therefore to be completed before the break-up of the sea-ice in the following spring.

For this reason, and because of the economy of the requisite design, the use of interlocking steel sheet-piling was adopted for the reconstruction operations, which were successfully completed in the time available. A light section of piling (weighing 18.50 lbs. per square foot, with a section-modulus of 7.82 inch³ units per foot of wall) was driven as two walls on either side of what remained of the

¹ The MS. and drawings can be seen in the Institution Library.—ACTING SEC. INST. C.E.

wrecked timber-cribwork jetties, only parts of which had to be removed. The walls were tied together by a system of tie-rods, connecting the continuous walers consisting of two channel sections. Copper-content steel was used for the work. Some comments are made on certain practical aspects of the exposure of steel-piling walls to the action of the sea.

Reconstruction of Wharf at Pointe au Pic, Quebec.—At Pointe au Pic, 86 miles below Quebec City on the north shore of the river St. Lawrence, is an important wharf serving both summer and winter traffic. Of substantial timber-cribwork construction, its substructure had deteriorated to such an extent that rebuilding became necessary, and in 1934 a contract was awarded by the Department for this work. Advantage was taken of the opportunity to enlarge the head-block of the wharf, and by the use of steel sheet-piling this was done with a minimum of disturbance of the old cribwork. The design adopted contemplated future dredging at the site of the wharf, and due to this feature, and the large tidal range, the use of 75-foot piles of a heavy section (weighing 48·74 lbs. per square foot, with a section-modulus of 55·1 inch³ units per foot of wall) was necessitated. Driving was wholly in compacted sand, and, although hard, it caused no difficulty. The driven piles were secured to concrete anchor-walls by a tie-rod system, rods being attached to alternate piles with no continuous waler. Rock filling was used, and a tar-macadam finish provided for the wharf surface.

Reconstruction of Wharf at Fredericton, New Brunswick.—A wharf on the Saint John river, which consisted of an old timber-cribwork structure, was in such a condition that immediate reconstruction was imperative. A simple cross-sectional design utilizing steel sheet-piling fitted well with local conditions, and, was adopted, as it involved little disturbance of the old structure and proved to be most economical. A light section of piling was driven in a continuous wall immediately in front of the old structure, and tied back to concrete anchor-blocks by steel tie-rods connecting to a continuous channel waler. In elevation, the wharf has an interesting sloping profile to render it available for use at all stages of the river.

Reconstruction of Wharf at Port Hope, Ontario.—Wharves constructed of timber cribwork had in the course of time deteriorated so seriously that reconstruction was necessary, and in 1931 a start was made, utilizing steel sheet-piling (weighing 24·98 lbs. per square foot, with a section-modulus of 15·80 inch³ units per foot of wall) driven as a simple wall in front of the old structure and tied back, through a channel-waler system and tie-rods, to a series of concrete anchor-blocks. The work contained one unusual feature in that for a part of the total length of wall there was insufficient unconsolidated

material overlying solid rock to give the necessary toe-hold. Cast-steel blocks were therefore secured to the bottom of every fourth pile, through holes in which a drill cored out holes in the rock into which steel dowels were inserted by divers and grouted into place.

Construction of Wharf at Oshawa, Ontario.—Construction of a new wharf-wall in the harbour of Oshawa presented special problems in that the site of the wharf extension was dry ground at an average elevation of several feet above lake water-level. By utilizing a design featuring a bulkhead wall of steel piling (weighing 31.74 lbs. per square foot, with a section-modulus of 25.35 inch³ units per foot of wall) it was possible to drive the piling and to complete the superstructure and anchorage system, backfilling up to final grade before carrying out the necessary dredging in front of the new wall. The design adopted has a further interest in that it features a relieving platform which shields the wall of steel piling from the full active pressure of the fill it retains. The economies of the design adopted are discussed.

Reconstruction of Wharf at Keewatin, Ontario.—This was another old timber-cribwork wharf. The lake-bed at the site consists of a glaciated granite surface under a deposit of river silt and saw-mill debris. No toe-hold could therefore be obtained, but a bulkhead-wall design was evolved utilizing two channel-waler supports, one being under water. The latter was fitted to the piling, arranged in panels, before being lowered into the water, and in this way the entire main wall of the wharf was successfully rebuilt without the aid of divers. The design is described in detail, and the possibilities which it presents are discussed.

In an Appendix a short note is added regarding the main aspects of design work for bulkhead walls.

Paper No. 5128.

“Roads and Road Transport in Tanganyika Territory.”

By WILLIAM HARLEY McLUCKIE, M. Inst. C.E.

(Ordered by the Council to be published in abstract form.)¹

General Description.—Tanganyika Territory lies on the east coast of Africa between 1 degree and 12 degrees south of the equator. It has an area of 365,000 square miles and a population exceeding 5,000,000. The principal activity is agriculture, and in recent years gold-mining has become important. The climate varies considerably and the Territory is not generally well watered. Its surface contains several large lakes and mountains. Other notable features are the long continuous scarps which cross the direction of transport to the Indian Ocean and restrict the possible alignments for railways. The scarps and mountains necessitate severe gradients for some of the roads.

The railway system consists of two unconnected metre-gauge single lines of a total length of 1,377 miles running westwards from the coast, one near the northern boundary, with a branch connecting with the Kenya and Uganda Railway, and the other centrally through the Territory to lake Tanganyika, with two branches running north, one of which reaches lake Victoria.

Apart from town and village roads and tracks the total length of the road system is 13,984 miles. Light motor transport over the greater part is considerable in the dry season, whilst over more than 4,000 miles comparatively heavy transport, with 2- and 3-ton lorries, is possible in the dry season and light motor transport practically throughout the year. 6,807 miles of village roads and tracks serve purely native purposes.

Construction and Maintenance of Roads.—The Paper describes generally the work of surveys, which are carried out principally to locate and demarcate the best routes between termini and to obtain information necessary to organize construction and order bridge materials from Britain. Existing maps are meagre in detail and considerable preliminary reconnaissance on foot is necessary. Ridge alignments are sought generally. The Territory is well covered with bush and the clearing which is necessary for construction is carried out to a width of 50 feet. Machinery has not been found economical in clearing or in removing ant-heaps. The cost of

¹ Type-litho copies of the full Paper can be obtained on loan from the Loan Library of The Institution; a limited number of type-litho copies are also available, for retention by members, on application to the Acting Secretary.

clearing has varied between £2 and £12 per mile, and the cost of reducing ant-heaps has reached £7 per mile.

Information is given concerning the formation and drainage of the roadways which are 16 feet in width and raised 6 inches above the general surface-level. Superelevation and widening are provided on curves with radii less than 600 feet. On steep side-sloping ground the formation is constructed with a cross-fall of 1 in 16 to the hillside. Road-grading machinery has not been used extensively and its use cannot replace more than one-quarter of the labour force normally required. The cost of formation and drainage varies upwards from £20 per mile, an average figure, inclusive of all earthworks, being about £55 per mile. Masonry and concrete culverts are most economical where suitable materials and foundations are available; but round corrugated-iron culverts are used most generally, their flexibility in soft and swampy ground being advantageous.

Many of the rivers flow only in the wet season and then rise and fall with such rapidity that the use of drifts is at present not unsatisfactory and is much more economical than bridging. Bridges are now constructed in accordance with standard types prepared by the Crown Agents for the Colonies, but in the past various types were used. Natural conditions permit considerable use of short spans and piers which are most economical, but the erection of larger spans has not been difficult.

Murum gravel, decomposed rock and the material from ant-heaps are used for surfacing when such is essential, and 3-inch layers, repeated when necessary, are generally applied, though on occasion thinner layers have been found to provide the stability desired. Surfacing, 6 inches deep, has cost about £200 per mile, the greater part of the cost being due to transport of material.

In recent years average earth-road construction-costs have been as follows :—

Earthworks	£60 per mile
Structures	£90 „
Staff	£70 „
Plant	£20 „
Contingencies	£10 „
Total	£250 per mile

During the last 10 years approximately 1,500 miles of road, including 8,500 linear feet of bridges, have been constructed.

European supervision at a rate of 1 per 200 natives employed is generally required, though on occasion good foremen can supervise 500 men. The largest requirement of plant is light motor transport, an average of one lorry to 200 natives being required. Natives are paid from 6*d.* per day upwards and their wages amount to 35 per cent. of the whole cost. Materials and plant cost a similar pro-

portion. Roughly 100 natives are required to construct 1 mile of road per month. Maintenance is carried out by labour employed continuously over the principal roads at a strength of 1 man per mile and at a cost of £10 per mile per annum.

Expenditure on and Revenue from Roads.—Information is given of the expenditure incurred on roads which is provided from general revenue and from loans. In all 4 per cent. of the total expenditure of the Territory and 29 per cent. of the expenditure on public works has been expended on roads. Revenue derived from the road system is obtained from licences for vehicles and customs duties on vehicles, their fuel and spare parts, and it is stated that the portion of the general revenue derived from road use has provided for the greater part of the expenditure from revenue, and at the present time is exceeding the annual amount required.

Highway and Traffic Laws.—General powers for the construction and use of roads are provided by a Highway Ordinance, which also provides for the use of the roads to be restricted and prohibited during the wet season. A Traffic Ordinance governs the condition and use of vehicles on the roads and limits their maximum weight and axle-weight on main roads to 10 tons and $2\frac{1}{2}$ tons respectively, and on district roads to 3 tons and $1\frac{1}{2}$ ton respectively. A Control Ordinance prohibits the use of vehicles carrying goods on roads competitive with the railways.

Road Transport.—Within the last 10 years light motor transport has replaced the porters and ox transport formerly used, the number of lorries and cars having increased five and twelve times respectively. The intensity of traffic is increasing by 33 per cent. annually and at present averages 15 vehicles per mile per day over the principal roads. The road cost per ton-mile is probably less than $\frac{1}{2}d.$, whilst it is stated that the costs of twenty-two selected Government vehicles during 1935 averaged $4.35d.$ per ton of carrying capacity per mile, and in advantageous circumstances could be reduced to the vicinity of $3d.$

Reference is also made to future road development and to road and rail competition, and it is stated that as both the railways and the roads have been provided at the expense of the State, the co-ordination of traffic on them is in the public interest. The whole question of competition has been the subject of an expert investigation recently and a Report on the co-ordination of transport in Kenya, Uganda and the Tanganyika Territory, by Brigadier-General Sir Osborne Mance, has been issued recently. At present the position is not as acute as it was during the years of depression.

ADDITIONAL ORIGINAL COMMUNICATIONS

RECEIVED BETWEEN THE 1ST APRIL, 1935, AND THE
31ST AUGUST, 1937.¹

AUTHORS.

- Addison, Herbert. No. 5,081.—Supplementary Notes on Flow Through Model Sluices.
- Ahmed, S. B. No. 5,147.—Theory of Earth-Pressure as Applied to Retaining-Walls.
- Barnes, A. A. No. 5,067.—Fluid Flow: Part I. The New Dimensionless Ordinate. Part II. The Law of the Eddies.
- Benson, W. J. No. 5,142.—The Sub-Soil Water-Table of the Punjab.
- Binnie, A. M. No. 5,141.—The Standing Wave in a Uniform Horizontal Channel of Rectangular Cross-Section.
- Blench, Thomas. No. 5,115.—Turbulent Flow in Channels.
- Blench, Thomas. No. 5,140.—Energy Theory of Turbulent Flow of Liquids.
- Blofield, G. C. No. 5,083.—Reconstruction of the Mocreeta and Timboy Bridges, Argentine North Eastern Railway.
- Buckton, E. J., and Fereday, H. J. No. 5,150.—The Reconstruction of Chelsea Bridge.
- Burls, G. A. No. 5,133.—A General Graphical Solution of the Problem of the Rough Inclined Plane.
- Burns, R. V., and White, C. M. No. 5,127.—The Protection of Dams, Weirs and Sluices against Scour.
- Cherre, V. No. 5,134.—Revolving Sluice-Gate (System V. Cherre).
- Colebrook, C. F., and White, C. M. No. 5,137.—Reduction of Carrying Capacity of Pipes with Age.
- Cornish, R. J. No. 5,092.—The Discharge of Small Submerged Sharp-Edged Orifices.

¹ Available for reference in the Library; includes Papers awaiting publication.

AUTHORS.

- Cox, C. L., and Dunbar, Arthur. No. 5,037.—Sanitation Schemes in Lagos.
- Currie, R. M. No. 5,095.—A Waterworks Pumping-Plant in China.
- Davies, D. Tudor. No. 5,119.—The Construction of Port Sudan Harbour.
- Davies, H. V. No. 5,131.—A Simple and Efficient Type of Sewage-Disposal Works for Small Communities, with Special Reference to the Performance of the "Pruss" Biological Filter when dealing with a Septic Tank Effluent at Bloemfontein, South Africa.
- Donkin, Thomas. No. 5,079.—The Effect of the Form of Cross-Section on the Capacity and Cost of Trunk Sewers.
- Dunkley, F. G., and Fancutt, F. No. 5,112.—The Engineer and the Paint Technologist.
- Ellis, S. J. No. 5,143.—The Total-Heat-Entropy Diagram for Diphenyl.
- Ellson, George. No. 5,146.—Dover Train-Ferry Dock.
- Elsden, Oscar. No. 5,100.—Investigation of the Outer Approach Channels to the Port of Rangoon by Means of a Tidal Model.
- Fancutt, F. No. 5,111.—Painting as it Affects a Railway Engineer.
- Ferguson, Clyde. No. 5,135.—A Note on Foundations.
- Follenfant, H. G. No. 5,052.—A Pre-cast Reinforced-Concrete Underline Railway Bridge.
- Fortune, L. E. No. 5,030.—The Reconstruction of a Small Sewage-Disposal Works.
- Gelson, W. E. No. 5,126.—Some Experiments on Locomotive Springs, with Reference to Bridge Impact Allowances.
- Gibson, A. H. No. 5,110.—An Experimental Investigation of the Effect of Bridge Piers and Other Obstructions on the Tidal Levels in an Estuary.
- Gumersall, G. J. No. 5,053.—Mathematics of the Multiple Portal, as Applied to Wind Calculations for large Power-Stations and Mill Buildings.
- Higgins, A. L. No. 5,129.—The Adjustment of Traverse Surveys.
- Hiley, Alfred. No. 5,093.—Some Considerations on the Bearing Capacity of Foundations and Sub-Soil Values.

AUTHORS.

- Hodgson, the late J. L., and Clark, G. M. No. 5,132.—Fluid Flow through Nozzles and Orifices: I. The Compressibility Factor. II. Borda's Mouthpiece.
- King, James McE., and Fox, S. G. No. 5,107.—Recent Works for the Relief of Traffic Congestion in Newport.
- Knight, B. H., and Knight, Rena G. No. 5,130.—The Weathering of Igneous Rocks used in Civil Engineering Work.
- Knight, R. G. No. 5,121.—The Subsidence of a Rockfill Dam and Remedial Measures at Eildon Reservoir, Australia.
- Lacey, J. M. No. 5,044.—A Problem in Hydraulics.
- Lea, F. C., and Whitman, J. G. No. 5,080.—The Failure of Girders under Repeated Stresses.
- Leliavsky, Serge. No. 5,098.—Shearing Stresses in Gravity Dams.
- Lisle, C. F. J. No. 5,082.—The Flow of Water in Short Channels.
- Mann, E. E. No. 5,077.—Factors of Safety.
- Mawson, J. H. No. 5,114.—The Assessment of Compensation Water.
- Moubayed, G. M. No. 5,118.—Land Drainage Pumping-Scheme of the Northern Delta of Egypt.
- Muirhead, J. Thorburn. No. 5,116.—Structural Precautions Against Air Attack. The Broader Aspects of the Problem.
- Newhouse, Frederic. No. 5,136.—Training of the Upper Nile.
- Nichols, H. J. No. 5,075.—The Silver Jubilee Bridge at Broach.
- Pike, J. P. No. 5,071.—The Setting-Out of the Mumbles-Brynmill Section of the Swansea Main Drainage Scheme.
- Pippard, A. J. Sutton. No. 5,145.—An Application of the Principle of Superposition to certain Structural Problems.
- Ravenhill, D. W., and Wilson, Guthlac. No. 5,094.—The Reconstruction of the Inchcape Bridge, B. N. & W. Rly.
- Rennie, James. No. 5,090.—Crookston and Cardonald Drainage Area.
- Robertson, James. No. 5,066.—Line and Level in the Setting-Out of a Tunnel.
- Ross, A. D. No. 5,086.—The Creep of Portland Blast-Furnace Cement Concrete.
- Saunders, J. R. W. No. 5,102.—An Analysis of the Steam Consumption of a Factory with an Output of 20,000 tons of Explosives per Annum.

AUTHORS.

- Sawaya, H. N. No. 5,063.—Remodelling and Extension of the Suez Dry Dock at Port Tewfik.
- Sherrard, H. M. No. 5,149.—Main Road Developments in New South Wales.
- Smith, J. Gall. No. 5,051.—Application of Superelevation of Highway Curves.
- Sutton, J. W. No. 5,117.—Sea-Defences at Admiralty Pier, Dover.
- Thrupp, E. C. No. 5,124.—Prediction of Auroras and Earthquakes.
- Tookey, W. A. No. 5,148.—Combustion Efficiencies of Gas and Oil Engines.
- Vokes, F. C. No. 5,088.—The Design and Operation of the Coleshill Sewage-Disposal Works of the Birmingham Tame and Rea District Drainage Boards.
- Vollmer, G. F. No. 5,144.—Contract Unit Prices—Pre-War and Post-War : A Comparison.
- Wilmot, H. F. No. 5,064.—A New Design of Cellular Type for High Retaining-Walls.
- Wooltorton, F. L. D. No. 5,139.—An Investigation into the Subject of Foundations in the Black Cotton and *Kyatti* Soils of the Mandalay District, Burma.
-

ENGINEERING RESEARCH.

SIR ALEXANDER GIBB'S ADDRESS TO THE BRITISH ASSOCIATION.

THE Institution notes with pleasure that its President, Sir Alexander Gibb, has been chosen as this year's President of Section G (Engineering), of the British Association. The subject of his Presidential address was "Research in Engineering."

Engineering, in its early days regarded as an art, passed through a period of empirical practice to its final stage of applied science. That it was a science was still not sufficiently recognized, nor that without research were progress and improvement possible. The encouragement of research and the advancement of useful knowledge were among the objects of the foundation of The Institution in 1818.

The President briefly traced the history of research showing how very recent was its development. The Imperial College of Science, South Kensington, owed its origin to a financial surplus from the Great Exhibition of 1851. The Royal Society, subjected in its early days to much derision, received from the Government in 1850 an annual grant of £1,000, which was increased in 1877 to £5,000 a year, for research in science generally, but original research continued to be mainly left to the individual at his own expense. In 1899, as the result largely of an agitation originating at meetings of the British Association, the National Physical Laboratory was founded. In 1902 the British Engineering Standards Association was established by the co-operation of the Institution of Civil Engineers, the Institution of Mechanical Engineers, the Institution of Naval Architects, and the Iron and Steel Institute. The need for a wider organization linking more definitely science and engineering research and industry led to the establishment, in 1915, of the Department of Scientific and Industrial Research under the control of a Committee of the Privy Council, whilst in 1918 the National Physical Laboratory became part of the newly-created Department, which was now the common focus all the research carried out in the country. That was largely accomplished by the encouragement of the formation of Research Associations, self-governing bodies formed on a national basis in various industries and working in co-operation with the Department, which gave financial support on a scale dependent upon the income otherwise provided. Of equal importance was the work carried on under the ægis of the great scientific Institutions. Valuable research work was carried out by the research departments of the Universities,

and finally the more important and wealthier business firms had their own private research laboratories. Whilst those were independent units, they could work in contact and correspondence with the Department of Scientific and Industrial Research, if they so desired.

The President then traced the growth of the parallel research organizations in the United States, where the National Academy of Science, founded in 1836, was the counterpart of the Royal Society; the National Research Council, formed in 1916, compared with the Department of Scientific and Industrial Research, and the National Bureau of Standards, formed in the first few years of the century, corresponded to the British Standards Institution. A particular form of American research institution was exemplified by the Mellon Institute. That had a limited membership in which one representative only of each class of interest was admitted, and resulted in a broadening of the basis of research. In Canada the National Research Council was carrying out a wide programme of practical research.

The financing of research originally devolved upon the individual, and later much assistance had been and was still being given by public-spirited benefactors. The cost should, however, be borne by those who benefited, namely the community and industry, and that the latter was now appreciative of the value of research was exemplified by the increase of 40 per cent. in 3 years in its support of research associations, which in 1935-6 totalled £232,468. Even so the position was not yet satisfactory, full use not being made of the facilities offered by the Government.

There was no general national plan for research as obtained in totalitarian States. It was the more necessary, therefore, that democratic countries, too, should organize and co-operate more closely than before. Groups of unrelated, often competitive, bodies could not be really effective, and in the President's opinion it was inevitable that sooner or later every research organization would have to be linked in some way to a central controlling body. Only thus could hopeless overlapping and waste of energy, time and money be avoided.

No less necessary was some form of centralization in respect of publications. The vast numbers of publications dealing with research and the innumerable channels through which the results of a research were broadcast made it a matter of extreme difficulty to obtain the latest information on any particular subject. There should be a clearing-house of engineering information which would collect, collate and make immediately available all new data discovered. If such an organization on a world-wide basis were impossible, the establishment of at least a clearing-house system in co-operation with the Department of Scientific and Industrial Re-

search could not be impossible, and the expense involved would be relatively small. The Department with its research associations was the ideal nucleus for such a service, but engineering had to work out its own scheme.

At the moment the two outstanding questions in the engineering world were the co-ordination of effort and the promotion of intensive research.

THE INSTITUTION RESEARCH COMMITTEE.

Sub-Committee on Reinforced-Concrete Structures for the Storage of Liquids.

This Sub-Committee, the formation of which, under the Chairmanship of Mr. Halcrow, was announced in the Journal for November, 1935,¹ was appointed to prepare recommendations for a Code of Practice for the design and construction of reinforced-concrete structures for the storage of liquids. At an early date the Sub-Committee was sub-divided into four Panels dealing with :—

- (1) General considerations,
- (2) Materials,
- (3) Design,
- (4) Construction.

Meetings of the Panels have been held at regular intervals and good progress has been made.

The Design Panel, however, found that information was lacking concerning the behaviour of bituminous joints such as may form the horizontal sliding joint at the base of a reservoir wall or a vertical contraction or expansion joint between sections of the wall. Whilst it was felt that, in the present state of knowledge, no specification for bituminous materials could be included in the recommendations for a Code, it was agreed to be desirable that tests should be carried out to throw some light on the mechanical behaviour of such material.

Arrangements have accordingly been made for the carrying out of tests designed to afford some guidance on this matter, and Professor R. G. H. Clements has kindly undertaken to carry out such a research of a few months' duration at the City and Guilds College. It is proposed, in particular, to study the sliding of a bituminous joint subjected to normal pressure so as to determine the equivalent friction of the joint and to obtain information concerning the behaviour of bituminous jointing materials in a joint subject to alternate expansion and contraction.

¹ Journal Inst. C.E., vol. 1 (1935-36), p. 44 (November, 1935).

It should be mentioned that there is ample scope for a comprehensive research into the behaviour of bituminous and other jointing materials for water-retaining structures. Such a research would, however, be costly and of considerable duration. It was for this reason, and in order to permit the Sub-Committee to conclude its work, that the above-mentioned tests alone were decided upon.

REPORT OF THE BUILDING RESEARCH BOARD FOR THE YEAR 1936.

Developments of outstanding interest mentioned in the Report, which has recently been published, are the coming into operation of the Fire-Testing Station at Elstree and the new Heating Laboratory at the Building Research Station. A note on the Fire-Testing Station appears on p. 584.

An interesting retrospect of the Station's activities since its construction in 1935 has been included. The Director traces the evolution of the organization to its present sub-division into three main sections: research, inquiries and special investigations, and library and publications. Under the last-mentioned heading, the monthly publication of Building Science Abstracts has been developed. Of particular interest to engineers are the researches into the properties of concrete. An early investigation into the permeability of concrete indicated the need for a series of fundamental investigations in which attention could be concentrated on one variable at a time. The first step was the construction of a laboratory in which temperature and humidity conditions could be controlled within close limits. Then an investigation into methods of testing Portland cement was begun and a standard 1 : 3 mortar-cube test was developed. By subsequent improved methods uniformity of results is ensured by vibration. A search for an ideal aggregate-grading showed that within practical limits the strength was independent of grading provided that the same water/cement ratio is used and that the concrete is thoroughly consolidated. This led to the study of workability and culminated in the standardization of a compacting-factor test.

Research on reinforced concrete led to the drafting of the Code of Practice for the Use of Reinforced Concrete in Buildings. Many problems raised during the course of this work, such as redistribution of bending moments in reinforced-concrete frames, bending in reinforced-concrete columns, and cracking in reinforced-concrete structures, have since been investigated.

Other sections of particular interest deal with the work of the

Steel Structures Research Committee and the research on pile-driving. The work on soil-mechanics is described from its commencement with the work of Professor C. F. Jenkin on dry sand, culminating in his revised wedge theory, to the present work on clays and other soils which is being carried out in conjunction with The Institution.

The work during the year includes a method of cleaning building stones by means of a water-jet, thus avoiding disadvantages inseparable from the use of chemicals. Work is continuing on the weathering and other properties of asphalts and bitumens. Research on cements includes a study of the carbonation of unhydrated Portland cement, special cements for large dams (jointly with The Institution), pozzuolanas, curing of cast-concrete products, asbestos cement, and so on. Stability of foamed slag as an aggregate has been studied. Other materials studied are limes and plasters, clay building-materials and paints, whilst a study has been made of the effect of frost on building materials.

Research on structures and on strength of materials includes a study of eccentrically-loaded reinforced-concrete columns, and the prevention of cracking by pre-tensioning of reinforcement. It is found that less than two-thirds of the nominal pre-tension is effective owing to creep of the concrete. Research is being conducted into concrete road-slab design, and has emphasized the weakness of the corners of slabs. The relation between grading of aggregates and workability of concrete has been studied, using crushed granite, sand and gravel aggregates.

The work carried out in conjunction with The Institution on earth-pressures, pile-driving, vibrated concrete, and the action of sea water on reinforced concrete, has been described in previous Journals.¹ The research on voussoir arches carried out for the Station at the City and Guilds College by Professor Pippard has been described in the Journal.²

Tests on beams of both mild steel and high-tensile structural steel have been directed to the study of failure by crushing at the bearing, by vertical web-buckling and by shear failure. An investigation of existing road bridges has been made for the Ministry of Transport. The investigation on wind-pressures on structures has been completed, and, with the observations taken on the Severn bridge, information is available relating to wind fronts up to $\frac{1}{2}$ mile.

A series of researches has been carried out concerning the efficiency of buildings from the standpoint of the user, and a description is given

¹ See Indexes to the Journal, appearing in Vols. 3 (1935-36) and 6 (1936-37). (October, 1936 and October, 1937).

² Journal Inst. C.E., vol. 4 (1936-37), p. 281 (December, 1936), and vol. 6 (1936-37), p. 5 (June, 1937).

of the new Heating Laboratory. Tests are in progress on heat-transmission through various types of brick walls, heat-transmission through roofs, thermal transmittance of a window, the effect of moisture on the thermal resistance of insulating wall-boards, and the exclusion of solar heat. Research into ventilation has shown the value of banks of vanes or splitters in reducing the resistance at elbows in ventilating ducts. Work on acoustics has shown the importance of isolating a sound at its source. Tests have been carried out on "floating" slab floors and also on false ceilings.

Among the special investigations carried out may be mentioned the production of aggregate from clay and mud, steel-sheet structural floors and wood-cement partition slabs.

THE FIRE-TESTING STATION, ELSTREE.

The Fire-Testing Station erected by the Fire Offices Committee at Elstree was completed in 1935. By arrangement with this committee, the Fire-Testing Station is available to the Building Research Station for research on fire-resistance, for investigations for outside bodies, and for tests on proprietary structures where the Department's certificate of their fire-resistance is desired.

The essential equipment consists of three testing furnaces, together with a control room from which the temperatures are controlled and automatically recorded. In addition there is space for the construction and dismantling of test specimens, and the whole floor space is commanded by a 30-ton overhead travelling crane. The cylindrical furnace erected vertically is in two halves each mounted on a carriage which can be run back so as to allow a hose to be played on the heated specimen. This furnace is designed for the testing of columns up to 10-foot-long heated area. The column is mounted in the centre of the furnace in a special 500-ton testing machine. A panel furnace is provided for wall slabs. Wall slabs up to 10 feet square with edges either free or restrained are held vertically in a 500-ton testing machine. The furnace consists of a panel of burners likewise 10 feet square which is mounted on a carriage so as to enable it to be withdrawn from the test panel and a water-hose played on the latter. The floor furnace is capable of testing either floors up to 10 feet square or beams 10 feet long. In this case it is the test specimen which is removed before applying the hose test.

Under the British Standards Definitions (B.S.I. No. 476) specimens are classified according to their fire-resistance capacity into categories A, B, C, D, and E. The general test is to heat up the face of the specimen according to a standard heating-curve, which reaches a

final temperature of $1,200^{\circ}$ C. after 6 hours. The specimen which is subjected to $1\frac{1}{2}$ times its design load, is heated for periods of 6, 4, 2, 1 and $\frac{1}{2}$ hours for categories A, B, C, D, and E respectively. In the case of slabs and floors, the temperature on the cold side must not exceed 350° F. On completion of the test period a fire-hose is applied uniformly over the heated surface until it is cooled.

Work has been carried out on floors consisting of timber, fillerjoist, hollow clay blocks with reinforced-concrete ribs, and reinforced-concrete slabs. Panels of light-weight concrete blocks, slabs of wood fibre and cement, and brick panels have also been tested.

RESEARCH IN ENGINEERING AT KING'S COLLEGE, NEWCASTLE-UPON-TYNE, AUGUST, 1937.¹

The researches noted below are being carried out in the Departments of Mechanical, Marine and Civil Engineering, of Electrical Engineering and of Mining.

Civil Engineering.

Much work has been done on photo-elastic methods of stress-analysis. In addition to the determination of the stresses in simple frames the method has been applied to such practical problems as the analysis of the stresses in a cylinder-head casting and the stress-distribution in cases, such as angles subjected to bending, which are not amenable to mathematical treatment.

The internal stresses and strains in welded joints are being investigated. For this purpose an extensometer is not suitable as it cannot remain in situ during welding, and an optical comparator reading to $\frac{1}{200,000}$ inch has accordingly been developed. By exploring the longitudinal and lateral strains resulting from welding, and from subsequent relief of strain after cutting, the stress-distribution can be obtained. The effect of annealing on the stresses and strains is being studied.

Mechanical Engineering.

The equivalent length of a crankshaft for the calculation of torsional vibration is being studied experimentally.

A long series of researches has been made into the behaviour of piston rings, the relation between friction and cylinder-pressure and its variation with the design of ring, the amount and effect of air

¹ Under the Statutes made in accordance with the University of Durham Act, 1935, the College of Medicine and Armstrong College have been merged in King's College, Newcastle-upon-Tyne, in the University of Durham.

leakage, etc., having been investigated. Work is now held up pending the development of a suitable high-speed indicator.

The scavenging of the two-stroke oil engine is being studied, using water as the working fluid, the scavenging-efficiency being measured by the salt-solution method.

A research has been carried out with the object of investigating the effect of viscosity and pipe-dimensions on the velocity of pressure-waves in oil under pressures up to 6,000 lbs. per square inch in pipes of small bore. This is of practical significance in connexion with the oil-injection system of the diesel engine.

Marine Engineering.

The virtual increase of mass of a propeller, immersed in water, when the shaft is subjected to torsional oscillations has been ascertained in the case of a number of scale models. The interpretation of the results in terms of the prototypes is, however, difficult and inconclusive.

Electrical Engineering.

An electric miner's lamp has been developed which gives an indication of the presence of inflammable gas and, when a predetermined concentration has been reached, shuts off the light momentarily.

The variation of electrical resistance with thickness has been utilized to develop an instrument whereby the varying thickness of metal tubes and plates may be explored. By this means boiler and retort tubes may be surveyed in situ and the corrosion of ships' plates and tanks measured.

The precision measurement of very high voltages presents difficulties, and a method is being developed based upon the oscillation of a suspended ellipsoid in a uniform electrostatic field.

A fundamental research is being conducted into the relation between breakdown resistance of various gases and their molecular structure.

Mining.

Special attention is being given to the development of methods of geophysical surveying. The variation in electrical resistance of different strata is being utilized by the probe, the expanding traverse and the step methods to indicate their nature and location. Small-scale models have been used to facilitate the interpretation of field results. In connexion with magnetic surveying the use of the vertical-force magnetic variometer for the location of magnetic ores and the

correlation of underground and surface surveys by the magnetotheodolite have been studied. Work is being done in connexion with the Fuel Research Coal Survey of the Northumberland and Durham coal field.

The use of fans of air-screw form for obtaining increased efficiencies in mine ventilation has been studied.

Methods of cleaning and recovery of small coal are being investigated. By way of contrast another research is directed to the elimination of carbonaceous particles from shale so as to render it suitable for the manufacture of bricks.

The foregoing researches are being carried out under the direction of Professor C. J. Hawkes, M.Sc., Professor of Mechanical, Marine and Civil Engineering, Professor W. M. Thornton, O.B.E., D.Sc., D.Eng., Professor of Electrical Engineering, and Professor Granville Poole, B.Sc., F.G.S., Professor of Mining.

NOTES ON RESEARCH PUBLICATIONS.¹

ENGINEERING MATERIALS : PROPERTIES AND TESTING.

Timber.

Department of Scientific and Industrial Research, Forest Products Research Record No. 18 deals with the causes of stain and decay in imported timber, and *No. 21* with the growth and structure of wood.

Bricks, Cement, and Concrete.

Work done at the Building Research Station on the effects of soluble salts in clay products is described in *Trans. Ceram. Soc.*, **36**, 233.

The effect of the heat of hydration of a cement on the quality of a concrete is discussed in *Zement*, **26**, 87. In *J. Am. Concr. Inst.*, **8**, 577, the properties of cements and concretes containing fly ash are discussed. The following researches on aggregate and grading have been noted : The law of size-distribution and statistical description of particulate materials, *J. Franklin Inst.* **223**, 609 ; The effect of the grading of the aggregate on the strength and workability of concrete, *J. Inst. Mun. & County Engrs.*, **64**, 114 ; The workability of concrete and mortar, *Eng. News-Record*, **119**, 17 ; Aggregate grading in relation to concrete mix design, dealing with aggregates

¹ The figure in heavy type is the number of the Volume ; that in brackets the number of the Part ; and that in italic type the number of the Page ; in references to "Engineering Abstracts" the number of the Abstract is given.

up to 3 in. diameter, *Trans. Inst. Civ. Engrs. of Ireland*, **62**, 197. In *J. Am. Concr. Inst.*, **8**, 339, is a study of sub-aqueous concrete. In *Proc. 16th Annual Meeting (1936) U.S. Highway Research Board*, p. 193, is a Paper on the bond of vibrated concrete. The results of a research on transverse elasticity and creep of concrete are given in *Engineering*, **143**, 161. The shrinkage of concrete and the use of expanding cements are dealt with in *Annales des Ponts et Chaussées*, **107-i**, 15 (*Eng. Abs.* **75**, 28); and in *J. Am. Concr. Inst.*, **8**, 327, the effect of size on drying shrinkage is discussed. Permeability is dealt with in *Zement*, **28**, 93, and on p. 189, an improved method for its determination is described. *Bulletin No. 53, Rensselaer Polytechnic Institute*, deals with the weathering resistance of concrete; and some tests on the effect of freezing on the permeability, strength and elasticity of concrete and mortars are described in *Am. Soc. Testing Materials*, 1937 Preprint No. 55.

Metals.

The mechanical properties of carbon steels, copper, and aluminium alloys broken in tension at very high speeds are described in *J. Inst. Metals*, **61**, 263. A study of the effect of span on transverse test results for cast iron is given in *Am. Soc. Testing Materials*, 1937 Preprint No. 31. A method for detecting and locating laminations and flaws in steel plates by a study of the sand patterns formed at resonance is described in *J. Am. Acoustical Soc.*, **8**, 220. The mechanism of film-formation in corrosion processes is discussed in *Chem. & Industry*, **56**, 751.

The effect of surface condition upon the fatigue strength of aluminium wires is dealt with in *Zeitschrift Metall.*, **29**, 214. *Research No. 18* of the *British Non-Ferrous Metals Research Assoc.*, on the properties of lead and lead alloys, gives a summary of the fatigue resistance of lead and lead alloys, and in *Research No. 58* published information on the creep of non-ferrous metals and alloys is reviewed.

Other Materials.

The physical properties of typical American rocks are discussed in *Bulletin 131, Iowa Engg. Expt. Stn.* A radial flow method for the measurement of permeability of porous media is given in *Phys. Rev.*, **51**, 684. The colloidal nature of asphalt as shown by its flow properties is discussed in *J. Phys. Chem.*, **40**, 1133.

ENGINEERING MATERIALS: PRODUCTION, MANUFACTURE, AND PRESERVATION.

Research on timber includes *Department of Scientific and Industrial Research Forest Products Research Record No. 19*, Methods of kiln

operation, and in *Trans. Soc. Chem. Ind.*, **56**, 202, a new aspect of the action of timber fireproofing compounds.

The deposition of concrete treated by the vacuum process is described in *Stroitelnie Promishlennost*, **15**, (3), 44 (*Eng. Abs.* **75**, 29). The reconditioning of Portland cement deteriorated by prolonged storage by the addition of hydrochloric acid to the mixing water is described in *Cement*, **10**, 15. The manufacture of cast iron to resist high temperatures is dealt with in *Revue Univ. des Mines et de la Métallurgie*, **80**, 281.

STRUCTURES.

Mass Structures.

Geophysical exploration of foundation strata is explained in *Bauing.*, **18**, 271. The development of soil mechanics is described in *The Structural Engineer*, **15** (*New Series*), 327. A preliminary investigation into the subject of foundations in the black cotton and *Kyatti* soils of the Mandalay District, Burma, is summarised in *Proc. of the International Congress on Soil Mechanics and Foundation Engineering* 1936, **3**, 242. It is suggested, *inter alia*, that cracking of buildings is reduced by increasing the intensity of pressure on the footings; thus in the cases considered reduction of area so as to give more than 1 ton per square foot is found to be desirable. The vertical pressures beneath a spread foundation are obtained graphically in *Proc. Am. Soc. Civ. Eng.*, **63**, 669. Soil consolidation by means of a vibrator is dealt with in *Bautech.*, **15**, 219 (*Eng. Abs.* **75**, 45). A mathematical investigation of the rational design of pile foundations is given in *U.S. Department of the Interior, Bureau of Reclamation, Tech. Memo. 531. Punjab Irrigation Research Inst. Research Pubn.*, **2**, No. 16, gives the general theory of the gradient of pressure under a structure on permeable foundations, with applications to the evaluation of the gradient at exit for some standard cases, and No. 19 discusses the relative efficiency of a vertical sheet-pile under a flush floor. A mathematical solution for the predetermination of the temperature-rise in large masses of poured concrete is given in *Zement*, **26**, 158.

Framed Structures.

The solution for the effect of two isolated forces on the elastic stability of a flat rectangular plate is given in *Proc. Cambridge Phil. Soc.*, **33**, 325. In a study of relaxation methods applied to engineering problems, the deflexion of beams under transverse loading is dealt with in *Proc. Roy. Soc. Series A*, **161**, 155, and on p. 197 a solution is given for the elastic stability of a thin twisted strip. Formulas

are derived for the bending strength of thin-walled cylindrical tubes in *Report No. 9, Structural Research Lab., Roy. Tech. Coll., Copenhagen*; failure is found to be due to instability and the formation of lobes. A theory is evolved for beams resting on a yielding foundation in *Proc. Nat. Acad. Sciences, U.S.A.*, **23**, 328. The effect of shear on the frequency of transverse vibration of a loaded fixed-free bar is discussed in *Phil. Mag.*, **23**, 1129. The method of basic co-ordinates whereby it is possible to design plane frames without the use of statical formulas is explained in *Mitteilungen aus dem Institut für Baustatik an der Eidg. Technischen Hochschule, Zurich*, No. 7. Recent developments in photo-elasticity are described in *Annali dei Lavori Pubblici*, **75**, 90 (*Eng. Abs.* **75**, 3), and the photo-elastic analysis of T-tail stresses as in the pole-pieces of electric generators is discussed in *J. Franklin Inst.*, **273**, 715.

Research in reinforced concrete includes experiments concerning the strain of the reinforcement of reinforced-concrete beams due to the shrinkage of the concrete, *Beton und Eis.*, **36**, 175 (*Eng. Abs.* **75**, 52); An experimental study of bond stress, *Proc. 16th Annual Meeting (1936) U.S. Highway Research Board*, p. 96; The design of reinforced-concrete members under flexure or combined flexure and direct compression, *J. Am. Concr. Inst.*, **8**, 483; and in the same journal, p. 459, Rapid and long-time tests on reinforced-concrete knee-frames. A study of expansion-joint fillers, with particular reference to concrete roof-slabs, is given in *U.S. Nat. Bur. Stands., Tech. News Bull. (240)* 37. A discussion of general principles in connection with fire resistance of buildings is given in *The Structural Engineer*, **15**, 257.

TRANSFORMATION, TRANSMISSION, AND DISTRIBUTION OF ENERGY.

Department of Scientific and Industrial Research, Fuel Research Tech. Paper No. 45, has been published, dealing with the hydrogenation-cracking of tars, Part III: the effect of certain variables in a continuous plant. The injection of petrol in an internal-combustion engine is studied in *Comptes Rendus*, **204**, 1316 (*Eng. Abs.* **75**, 78); and the ignitability of diesel-engine fuels in *Auto. Zeit.*, **40**, 195 (*Eng. Abs.* **75**, 80). Boiler water problems are dealt with in *J. Inst. Heat. and Vent. Engrs.*, **5**, 149. In *J. Inst. Elec. Engrs.*, **80**, 567, is given an experimental investigation of the theory of eddy-currents in laminated cores of rectangular section, and on p. 647 nickel alloys of high permeability, with special reference to Mumetal, are discussed; in the same journal, Vol. **81**, p. 145, the lay-out and rupturing capacity of protective devices in motor circuits is considered; on p. 256 is a Paper on the metering of mercury-arc rectifier

supplies and outputs ; and on *p.* 277 a variable air condenser with adjustable compensation for temperature is described. The following researches in *Archiv Elek.*, **31**, have been noted : *p.* 141 (*Eng. Abs.* **75**, 23), The rupture-gradient of liquid and solid benzol ; *p.* 166 (*Eng. Abs.* **75**, 101), Rupture voltage reduction at high frequency ; *p.* 179 (*Eng. Abs.*, **75**, 98), The rupture voltage of flowing oil and the increase of the rupture field-strength by electric filtration ; *p.* 186 (*Eng. Abs.* **75**, 103), The distortion of surge-waves in short transmission-lines ; *p.* 197 (*Eng. Abs.* **75**, 102), The rupture of stratified oil-air dielectrics with impulse and alternating voltages ; *p.* 282 (*Eng. Abs.* **75**, 100), Electric rupture of various gases under high pressure ; *p.* 287, Effect of earthing- and compensating-coils upon the mutual influence of earthed three-phase systems ; *p.* 338, The problem of corona-damping of surge-waves. The dielectric strength of non-inflammable synthetic insulating oils is dealt with in *Elec. Eng.*, **56**, 671. The ageing of copper conductors traversed by electric currents is discussed in *Comptes Rendus*, **204**, 1715.

MECHANICAL PROCESSES, APPLIANCES, AND APPARATUS.

The following researches in welding have been noted : Stress-distribution in fillet welds—a review of the literature to date, *Welding J.*, **16** (5) (*Suppt.* 1) ; The welding of copper and its alloys, *J. Am. Weld. Soc.*, **16** (2) (*Welding Research Suppt.* 7) and (3) (*Suppt.* 33) (*Eng. Abs.* **75**, 113) ; The welding of cast iron, *J. Am. Weld. Soc.*, **16** (3) (*Suppt.* 2) (*Eng. Abs.* **75**, 111) ; The welding of thick aluminium sheets, *Ver. deu. Ing.*, **81**, 433 (*Eng. Abs.* **75**, 115) ; Welding stresses in vessels subjected to internal pressures, *Stahl und Eis.*, **57**, 389 (*Eng. Abs.* **75**, 114) ; Electric welding of steel bridges, giving the experience of the Department of Main Roads, N.S.W., *J. Inst. Engrs. Australia*, **9**, 173.

In the *Report of the Food Investigation Board for 1936* research into thermal conductivity, heat-transfer, refrigeration, evaporation, and control of humidity is described.

The lubrication of journal bearings in oxidizing conditions is discussed in *J. Inst. Petroleum Technologists*, **23**, 350.

SPECIALIZED ENGINEERING PRACTICE.

Transport.

In *Publication No. 4* of the Institute of the German Research Association for Soil Mechanics at the *Technische Hochschule*, Berlin, the use of dynamic foundation soil investigation and the behaviour of sand with changes in loading and movements of ground water are discussed. Soil-consolidation by vibrators is dealt with in *Bautech.*,

15, 219. The improvement of earth and worn-out gravel roads by the use of cut-backs and road oils to stabilize the soil is discussed in *Proc. 16th Annual Meeting (1936), U.S. Highway Research Board*, p. 359; and on p. 69, safe friction factors and superelevation design are dealt with in the Report of the Committee on relation of curvature to speed. In *Bull. No. 110, Permanent International Assoc. Road Congresses, 26th year*, p. 92, the lay-out and construction of roads according to the new standards recommended is described, and on p. 100 is an article on road design and road safety. A study of the friction between road surface and motor vehicles is given in *Betonstrasse*, **12** (6), 125 and (7) 139. Research on concrete roads is dealt with in *Betonstrasse*, **11**, 99. In *No. 110, Permanent International Assoc. Road Congresses, 26th year*, p. 79, is a description of American research concerning joints, and in *Eng. News-Record*, **119**, 72, a new expansion joint for concrete pavement is discussed. The mechanical properties of bituminous surfacing materials under constant stress are considered in *J. Soc. Chem. Ind.*, **56**, 146T.

Research on railways includes: A study of the development of cracks in the wheel-seats of axles within the hubs of wheels due to the effect of radial compressive stress between shrunk or forced-on wheel and axle, *J. Inst. Engrs. Australia*, **9**, 215; the spalling of the tire-surfaces of railway-wheels, *Stahl und Eis.*, **57**, 533 (*Eng. Abs.* **75**, 19); High-speed passenger trains, *J. Western Soc. Engrs.*, **42**, 47; Stresses in railway-track due to high speeds, *Rev. Gén. Chemins de Fer*, **56**, 345 (*Eng. Abs.* **75**, 131); and Lubricants and "false-brinelling" of ball and roller bearings, *Mech. Eng.*, **59**, 415 (*Eng. Abs.* **75**, 124).

The following researches on marine transport have been noted: The influence of surface roughness on ship resistance, *Schiffbau*, **38**, 135 (*Eng. Abs.* **75**, 141); The influence of form upon the frictional resistance of models towed under water, *Schiffbautech. Gesellschaft*, **38**, 177; and in the same journal, p. 260, Ship-stabilization; The resistance of a ship among waves, *Proc. Roy. Soc. Series A*, **161**, 299; Open test results of four-bladed propellers, *Het Schip.*, **19**, 84 (*Eng. Abs.* **75**, 90); Experimental results for a series of three-bladed model propellers in open water, describing work carried out at the Wm. Froude Laboratory, *Trans. Liverpool Engineering Soc.*, **58**, 214.

The following Aeronautical Research Committee Reports and Memoranda have been noted: *No. 1731*, Plane-table method of measuring take-off and landing flight-paths; *No. 1734*, Full-scale tests of Hartshorn ailerons on a Bulldog; *No. 1735*, Wind-tunnel tests on slotted flaps on a low-wing monoplane: flap angle 0 deg. to 90 deg.; *No. 1736*, Wind-tunnel tests to determine the efficiency of an airscrew working in front of a thick-section wing; *No. 1751*,

A study of the flexural axis positions for certain box sections ; *No. 1755*, Notes on stubs for seaplanes ; *No. 1756*, The distribution of stress in monocoque wings ; *No. 1757*, A general method of calculating the effect of axial constraint on torsion on different forms of two-spar, skin-covered wings ; *No. 1759*, Some applications of conformal transformation to airscrew theory ; *No. 1762*, The R.A.F. mark Va torsigraph ; *No. 1763*, A note on roughness ; *No. 1768*, Some experiments with cascades of aerofoils ; *No. 1771*, Tests of four airscrew sections in the compressed-air tunnel ; *No. 1772*, Tests of R.A.F. 34 at negative incidences and of the effect of surface roughness on R.A.F. 34 with split flap in the compressed-air tunnel ; *No. 1773*, Note on the design of corners in duct systems. Reports of the U.S. National Advisory Committee for Aeronautics include the following : *No. 585*, Span-load distribution for tapered wings with partial-span flaps ; *No. 587* (*Eng. Abs.* **75**, 77), Blower cooling of finned cylinders ; *No. 588* (*Eng. Abs.* **75**, 79), Fuel-spray and flame-formation in a compression-ignition engine employing air-flow ; *No. 589*, An analysis of lateral stability in power-off flight, with charts for use in design ; *No. 590*, Pressure-distribution measurements on an O-2H airplane in flight ; *No. 593*, Cooling of airplane engines at low air-speeds ; *No. 595*, Full-scale tests of a new type N.A.C.A. nose-slot cowl. In *Luftfahrt*, **14**, the following articles appear : *p. 168* (*Eng. Abs.* **75**, 143), Airscrews for high-speed aeroplanes ; *p. 293*, Determination of the resistance and the air-flow through built-in coolers of various types ; *p. 304*, Behaviour of static tubes at high speed ; *p. 314*, Theory of submerged aerofoils and skimming surfaces. The two-dimensional hydrodynamical theory of moving aerofoils is dealt with in *Proc. Roy. Soc.*, **161**, 406. Articles in *J. Roy. Aero. Soc.*, **41**, include : *p. 350*, Aeroplane stability and the automatic pilot ; *p. 523*, Plastic materials for aircraft construction ; *p. 595*, The formation of ice on aircraft ; *p. 609*, Note on the possibility of flight by human power ; *p. 635*, Trend of air-cooled aero engines—the next five years ; *p. 703*, Critical speeds of monoplanes.

Water-Supply and Sewage-Disposal.

Experiments with fluid friction in roughened pipes, in which the effect of non-homogeneity of the roughness is studied, are described in *Proc. Roy. Soc. Series A.* **161**, 367. In *U.S. Nat. Bur. Stand. Hydraulic Lab. Bull. Series A. Bull. V-2*, a compilation has been made of current hydraulic laboratory research in the U.S.A. The pressure-losses for fluid flow in curved pipes are studied in *U.S. Nat. Bur. Stand. J. Research*, **18**, 89. The damage caused to metal by water impact is discussed in *Schw. Bauz.* **109**, 225, (*Eng. Abs*

75, 68). *Nigeria Public Works Dept. Technical Paper No. 5* describes the method used for the estimation of flood discharges and waterways in the Northern Provinces of Nigeria. The germicidal properties of chlorine compounds for water treatment are discussed in *Iowa Engg. Expt. Station Bull. No. 132*.

The following researches on sewage-disposal have been noted: *J. Sewage Works*, **9**, 207 (*Eng. Abs.* **75**, 154), Activated carbon in sewage-sludge digestion; p. 224 (*Eng. Abs.* **75**, 151), The oxygen-demand of polluted waters; p. 285 (*Eng. Abs.* **75**, 155), Coagulation compared with chemical precipitation in the vacuum filtration of sewage-sludge; *J. Western Soc. Engineers*, Vol. **42**, 55, Activated sludge—recent discoveries.

Lighting, Heating, and Ventilation.

The Department of Scientific and Industrial Research has published *Illumination Research Technical Paper No. 20* on the use of coloured light for motor-car headlights. The interesting conclusion is reached that none of the claims made in favour of using a coloured, and in particular a yellow, headlight beam, has been substantiated. In *J. Inst. Elec. Engineers*, **80**, 636, optimum symmetrical light-distribution is discussed.

Researches into thermal conductivity include: Measurement of the thermal conductivity of insulating materials, *Zeitschrift für technische Physik*, **17**, 283, and *Soc. Glass Tech. J.* **21** (84), Abstracts 90; and a Paper on heat-transmission through walls, giving a description of the new heat-transmission laboratory at the Building Research Station, *J. Inst. Heat. and Vent. Eng.* **5**, 82.

A study of progress at the Building Research Station in ventilating research is given in *J. Inst. Heat. and Vent. Eng.* **5**, 183. The nature of noise in ventilating systems and methods for its elimination are discussed in *Heating, Piping*, **9**, 183. The velocity-distribution in fan-ducts, with particular reference to mine ventilation, is dealt with in *J. South African Inst. Engineers*, **35**, 234.

Telegraphy and Telephony.

The control of wireless signal variations is discussed in *J. Inst. Elec. Engrs.* **80**, 610; and on p. 623 is an article on control of phase-fading in long-distance radio communication.



THE LATE DR. H. H. JEFFCOTT.

SECRETARY OF THE INSTITUTION 1822-1897.

From a photograph by Elliott & Fry, Ltd.

OBITUARY.

HENRY HOMAN JEFFCOTT, B.A., B.A.I., Sc.D., the second son of William Jeffcott, Justice of the Peace, was born in County Donegal on the 6th February, 1877, and died on the 29th June, 1937, at Walton-on Thames, Surrey. From 1895 to 1899 he was educated at Trinity College, Dublin; he then proceeded for 3 years to the Engineering School at Trinity College, Dublin, where he gained high academic honours. From 1902 to 1904 he was trained as an assistant with Messrs. Siemens Brothers and Company, Ltd., at Woolwich and Stafford, and then went to the Openshaw works of Messrs. W. G. Armstrong Whitworth and Company. In 1905 he became head of the Metrology Department of the National Physical Laboratory, London, being occupied with experimental work connected with screw-threads, pipe-flanges, bolt-heads, standardization of engineers' gauges, verification of surveying apparatus for base-line measurement and the design, erection and testing of measuring machines.

In 1910 he was appointed Professor of Engineering in the Royal College of Science for Ireland, Dublin, and held this post until 1922; during the last 8 years of this period he was also Dean of the Faculty of the College. During the War he was responsible for the manufacture of munitions in the College workshops, involving the design and construction of turret lathes and the adaptation of existing lathes by novel methods. He held from 1918 to 1921 the post of Secretary of the Water Power Resources of Ireland Sub-Committee, and was also examiner in Mechanical Engineering in the University of Belfast and in the National University of Ireland. During this period also he was associated with Sir John P. Griffith, Past-President Inst. C.E., in the preparation of a hydro-electric scheme for the river Liffey. In 1922 he was appointed Secretary of the Institution of Civil Engineers, which position he held until his death.

Dr. Jeffcott wrote many papers on engineering and scientific subjects for the Transactions of learned societies upon such matters as whirling of shafts, vibration of beams, elastic deformation, screws and threads, electrical transmission lines, hydro-electric investigations, heat-engines, surveying instruments, etc., and in addition he was the patentee of several inventions, the best-known of which is his direct-reading tacheometer. He always placed


himself with unfailing readiness and courtesy at the disposal of members and of visitors to The Institution, and his death will be keenly felt by all those with whom he came in contact. A memorial service was held at St. Margaret's, Westminster, on Monday, 5 July, which was attended by many members of The Institution and by numerous representatives of other bodies.

He was a Member of the Institution of Civil Engineers, the Institution of Mechanical Engineers, and the Royal Irish Academy. He married Louisa, daughter of George Lang, who survives him and by whom he had one son who died in infancy.

NOTE.

The Institution as a body is not responsible either for the statements made, or for the opinions expressed, in the Papers published.

COMBINED NAME-INDEX
AND
COMBINED SUBJECT-INDEX
FOR
Volumes 4, 5 and 6, 1936-37
Journals, November, 1936, to October, 1937



COMBINED NAME-INDEX

FOR

Volumes 4, 5 and 6, 1936-37.

November, 1936, to October, 1937, Journals.

- 4 refers to Volume 4, 1936-37, containing November and December, 1936 and January, 1937, Journals.
5 refers to Volume 5, 1936-37, containing February, March and April, 1937, Journals.
6 refers to Volume 6, 1936-37, containing June and October, 1937, Journals.

Adams, Haddon C., 6, 22 (June).
Adams, W. F., 4, 121 (Nov.).
Addison, Herbert, 6, 561 (Oct.).
Alford, J. S., 6, 451, 473 (Oct.).
Allard, William, 6, 119 (June).
Anderson, Dr. David, 5, 761 (Apr.).
Anderson, R. A. T., 5, 596 (Apr.).
Andrews, E. S., 5, 345 (Mar.).
Ashbridge, Sir Noel, 5, 349, 394 (Mar.).
Ashforth, G. E., 4, 198 (Dec.).
Atkins, M. R., 5, 598 (Apr.).

Baker, Prof. J. F., 6, 297 (Oct.).
Balsom, E. V., 5, 598 (Apr.).
Bardet, Gaston, 4, 255 (Dec.).
Barnes, A. A., 6, 525 (Oct.).
Barron, S. N., 4, 204 (Dec.).
Bateman, E. H., 6, 545 (Oct.).
Bateson, Ernest, 4, 419 (Jan.); 5, 146 (Feb.).
Benedicks, Dr. Carl, 6, 549 (Oct.).
Bennett, G. T., 4, 200 (Dec.).
Binnie, W. J. E., 4, 253 (Dec.); 6, 114 (June), 452 (Oct.).
Borer, Oscar, 4, 247 (Dec.); 5, 309 (Mar.); 6, 419 (Oct.).
Bragg, Sir William H., 6, 181 (June).
Braine, C. D. C., 5, 593 (Apr.).
Bressey, Sir Charles H., 5, 763 (Apr.).
Broomfield, R. E., 6, 440 (Oct.).
Brown, J. G., 5, 687, 768 (Apr.); 6, 520 (Oct.).
Brown, R. D., 6, 519 (Oct.).
Brown, R. D., Jun., 4, 483 (Jan.).
Buckton, E. J., 4, 454 (Jan.).
Bush, W. E., 6, 473 (Oct.).

Calvert, Dr. H. T., 5, 587 (Apr.).
Carpmael, Raymond, 4, 423, 465 (Jan.); 5, 765 (Apr.).
Chalmers, Robert, 4, 457 (Jan.).
Chamney, R. M., 5, 391 (Mar.).
Chapman, Harry, 6, 129 (June).
Charles, Lt.-Gen. Sir Ronald, 5, 59 (Feb.).
Chettoe, C. S., 6, 18 (June).
Chitty, Letitia, 4, 281 (Dec.); 6, 24 (June).
Clark, R. G., 6, 345 (Oct.).
Clayton, A. J. H., 4, 206 (Dec.).
Codrington, W. M., 4, 416 (Jan.).
Cole, R. S., 5, 313 (Mar.).
Cook, F. C., 4, 161, 218 (Dec.); 5, 766 (Apr.); 6, 71 (June).
Cooling, L. F., 4, 135 (Nov.).
Couper, J. D. C., 6, 214 (June).
Cowan, P. J., 6, 215 (June).
Cox, S. W., 5, 588 (Apr.).
Coyne, A., 5, 401 (Mar.).
Craddock, D. A., 5, 392 (Mar.).
Criswell, Henry, 6, 72 (June).
Crousaz, Eng. Rear-Adml. A. G., 5, 669 (Apr.).
Cunningham, Dr. Brysson, 4, 459 (Jan.).

Dalrymple-Hay, Sir Harley, 4, 16 (Nov.).
Davey, Dr. Norman, 5, 74 (Feb.); 6, 6 (June).
Davies, Powys, 5, 59 (Feb.).
Davy, C. H., 5, 678 (Apr.).
Dawe, J. N., 4, 461 (Jan.).
Daymond, J. R., 6, 268 (June).

- Dean, A. J., 5, 287 (Mar.); 6, 437 (Oct.).
 Deane, H. J., 5, 345 (Mar.).
 Deschamps, Joseph, 5, 764 (Apr.).
 Dipper, L. C., 6, 501 (Oct.).
 Dixon, J. R., 5, 763 (Apr.).
 Dixon, Prof. S. M., 6, 81, 156 (June), 541 (Oct.).
 Doak, W. J., 6, 365 (Oct.).
 Donkin, S. B., 5, 384 (Mar.); 6, 71, 181 (June).
 Dorey, Dr. S. F., 5, 621, 667, 681 (Apr.); 6, 515 (Oct.).
 Dowson, Robert, 6, 263 (June).
 Du-Plat-Taylor, F. M. G., 4, 17 (Nov.), 456 (Jan.).
 Duckham, F. W., 4, 207 (Dec.).
 Durant, N. J., 5, 143 (Feb.).
 Durley, T. C., 5, 344 (Mar.).
- Eddy, *The late* H. P., 6, 474 (Oct.).
 Edwards, David, 4, 197 (Dec.).
 Engel, Dr. F. V. A. E., 6, 476 (Oct.).
 Everall, W. T., 6, 402 (Oct.).
- Faber, Dr. Oscar, 5, 342 (Mar.).
 Faltus, Dr. Frank, 6, 502 (Oct.).
 Fereday, H. J., 5, 140 (Feb.); 6, 366 (Oct.).
 Ferguson, Robert, 4, 51 (Nov.); 6, 338 (Oct.).
 Fergusson, H. B., 6, 503 (Oct.).
 FitzGibbon, Gerald, 6, 81, 156 (June), 541 (Oct.).
 Flanagan, J. W., 5, 601 (Apr.).
 Fordham, A. A., 4, 131 (Nov.).
 Frank, T. P., 5, 574 (Apr.); 6, 76 (June).
- Gales, Sir Robert, 6, 325, 367 (Oct.).
 Gardner, A. C., 6, 346 (Oct.).
 Garner, F. H., 5, 776 (Apr.).
 Gates, H. B., 6, 341, 371, 381 (Oct.).
 Gedyo, N. G., 4, 451 (Jan.).
 Gibb, Sir Alexander, 4, 2, 4, 17 (Nov.), 253 (Dec.), 448 (Jan.); 5, 49 (Feb.), 337, 384 (Mar.), 760 (Apr.); 6, 5, 7, 215 (June).
 Gibb, H. M., 5, 76 (Feb.).
 Glanville, Dr. W. H., 5, 56 (Feb.), 338 (Mar.).
 Glasspoole, Dr. John, 6, 133 (June).
 Gold, E., 6, 148 (June).
 Goodlet, B. L., 4, 475 (Jan.).
 Gorringer, H. M., 5, 432 (Mar.).
 Gough, G. S., 6, 247 (June), 548 (Oct.).
 Gourley, H. J. F., 5, 52 (Feb.); 6, 150, 214 (June), 453 (Oct.).
 Graham, D. C., 5, 604 (Apr.).
 Greet, E. H., 5, 148 (Feb.).
- Gribble, Conrad, 5, 138 (Feb.).
 Griffith, W. M., 6, 528 (Oct.).
 Griffiths, G. J., 4, 252 (Dec.), 453 (Jan.).
 Grisley, Frederick, 5, 393 (Mar.).
 Grove, Frank, 6, 423 (Oct.).
 Gullan, A. G., 6, 382 (Oct.).
 Gurney, W. E. R., 6, 565 (Oct.).
- Hadfield, Sir Robert A., 6, 558 (Oct.).
 Haigh, Prof. B. P., 5, 673 (Apr.).
 Halcrow, W. T., 5, 49 (Feb.), 305 (Mar.); 6, 75 (June).
 Hamlin, Dr. E. J., 6, 441 (Oct.).
 Handman, F. W. A., 4, 325 (Jan.); 6, 372 (Oct.).
 Harris, Dr. Herbert, 6, 505 (Oct.).
 Harvey, B. L., 4, 21 (Nov.); 6, 333 (Oct.).
 Hatfield, Dr. W. H., 5, 671 (Apr.).
 Headland, Henry, 6, 357, 507 (Oct.).
 Henderson, Hon. Philip, 4, 422 (Jan.).
 Hetherington, R. G., 5, 577 (Apr.).
 Hibbert, Frank, 6, 127 (June).
 Hill, K. J. C., 5, 307 (Mar.).
 Hillier, W. H., 5, 606 (Apr.).
 Hindley, Sir Clement, 5, 138 (Feb.); 6, 117, 202 (June).
 Hindmarsh, R. F., 4, 462 (Jan.).
 Hodgson, G. H., 4, 208 (Dec.); 6, 74 (June).
 Hogan, Dr. M. A., 6, 81, 114, 156 (June), 541 (Oct.).
 Hogg, Charles, 5, 608 (Apr.).
 Holmstrom, Dr. J. E., 4, 208 (Dec.).
 Hood, William, 4, 133 (Nov.).
 Howorth, Ben, 6, 151 (June).
 Howorth, G. E., 4, 369 (Jan.); 6, 378 (Oct.).
 Hughes, R. V., 4, 211 (Dec.).
 Humphreys, C. L. H., 6, 28, 70, 78 (June), 524 (Oct.).
 Humphreys, Sir George, 5, 570 (Apr.).
 Humphreys, G. H., 4, 195 (Dec.).
 Hunter, J. K., 5, 71 (Feb.).
 Huntsman, B. W., 5, 243, 305, 315 (Mar.); 6, 430 (Oct.).
 Hurcomb, Sir Cyril, 4, 192 (Dec.).
 Husbands, H. W. S., 4, 211 (Dec.).
- Inglis, C. C., 6, 329 (Oct.).
 Inglis, Prof. C. E., 4, 414 (Jan.); 6, 7 (June).
- Jasper, T. M., 6, 512 (Oct.).
 Johnston, D. B., 4, 307 (Dec.).
- Kirkpatrick, Sir Cyril, 4, 245 (Dec.); 6, 215 (June).
 Kramer, J. B., 5, 764 (Apr.).

- La Touche, J. N. D., 6, 406 (Oct.).
 Lacey, Gerald, 6, 534 (Oct.).
 Lacey, J. M., 6, 152 (June), 424, 454 (Oct.).
 Lapworth, C. F., 6, 145 (June).
 Larke, Sir William, 5, 668 (Apr.).
 Latham, Ernest, 4, 462 (Jan.).
 Lea, Prof. F. C., 4, 93 (Nov.); 5, 55 (Feb.); 6, 343 (Oct.).
 Lea, Dr. F. M., 5, 217 (Feb.); 6, 275, 278 (June).
 Lee, Sir George, 5, 385 (Mar.).
 Legget, R. F., 6, 569 (Oct.).
 Leitch, W. O., 6, 332, 425 (Oct.).
 Lillie, G. E., 6, 457 (Oct.).
 Lloyd, David, 6, 535 (Oct.).
 Lloyd, H. G., 5, 79 (Feb.), 767 (Apr.).
 Lowe-Brown, Dr. W. L., 5, 71 (Feb.), 346 (Mar.); 6, 214 (June).
 McClean, W. N., 5, 68 (Feb.); 6, 139 (June).
 McLuckie, W. N., 6, 572 (Oct.).
 Main, S. A., 6, 558 (Oct.).
 Makins, Thomas, 6, 425 (Oct.).
 Manning, G. P., 6, 441 (Oct.).
 Manning H. D., 5, 589 (Apr.).
 Marks, J. R., 6, 442 (Oct.).
 Marsh, C. M., 6, 336 (Oct.).
 Martin, A. J., 5, 595 (Apr.).
 Maybury, Sir Henry, 4, 2 (Nov.), 191 (Dec.).
 Meares, J. W., 6, 385 (Oct.).
 Mitchell, James, 6, 446, 513 (Oct.).
 Monkhouse, E. W., 6, 215 (June).
 Moon, Ramsay, 5, 152 (Feb.).
 Moran, T. W., 6, 385, 521 (Oct.).
 Morgan, Sir Charles, 4, 2 (Nov.).
 Morgan, H. D., 5, 63 (Feb.).
 Morgan, W. H., 5, 586 (Apr.).
 Morris, Arnold, 5, 576 (Apr.).
 Morum, S. W. F., 4, 484 (Jan.).
 Naylor, A. H., 5, 3, 49, 80 (Feb.); 6, 398 (Oct.).
 Needham, E. S., 5, 150 (Feb.).
 Nichols, H. J., 4, 213 (Dec.), 417 (Jan.); 5, 91, 155 (Feb.); 6, 340, 342, 410 (Oct.).
 Osborne, A. A., 4, 214 (Dec.); 6, 482 (Oct.).
 Payne, H. F., 6, 483 (Oct.).
 Peel, Cecil, 6, 348 (Oct.).
 Pearse, Langdon, 6, 484 (Oct.).
 Pippard, Prof. A. J. S., 4, 79 (Nov.), 281 (Dec.); 5, 24 (June), 341 (Oct.).
 Pullin, V. E., 6, 513 (Oct.).
 Purchas, A. W., 4, 215 (Dec.).
 Radice, W. A., 6, 332 (Oct.).
 Reeson, J. N., 6, 214 (June).
 Reeve, Dr. Lewis, 5, 680 (Apr.).
 Richards, B. D., 4, 464 (Jan.); 5, 67 (Feb.), 405 (Mar.); 6, 470 (Oct.).
 Richards, J. C., 5, 196 (Feb.).
 Risdon, P. J., 6, 371 (Oct.).
 Roberts, C. H., 6, 135 (June).
 Robinson, P. J., 6, 463 (Oct.).
 Royal-Dawson, Prof. F. G., 4, 216 (Dec.).
 Saner, J. A., 4, 246 (Dec.); 5, 767 (Apr.).
 Savage, J. L., 6, 161 (June).
 Savile, Sir Leopold, 5, 761 (Apr.).
 Schaper, Dr. G., 6, 203 (June).
 Schuster, L. W., 5, 674 (Apr.).
 Scott, F. W., 6, 425 (Oct.).
 Slade, F. W., 4, 469 (Jan.).
 Southwell, Prof. R. V., 6, 9 (June).
 Sparkes, S. R., 4, 79 (Nov.); 6, 341 (Oct.).
 Stanford, F. O., 6, 155 (June).
 Stanger, R. H. H., 5, 62 (Feb.), 337 (Mar.).
 Stewart, D. A., 5, 318, 336, 346 (Mar.); 6, 448 (Oct.).
 Stradling, Dr. R. E., 6, 202 (June).
 Strong, C. E., 5, 387 (Mar.).
 Stuart, J. M. B., 5, 313 (Apr.).
 Swift, Prof. H. W., 5, 161 (Feb.).
 Swinden, T., 5, 778 (Apr.).
 Temple, F. C., 5, 572, 780 (Apr.).
 Thornton, D. L., 5, 154 (Feb.).
 Thrupp, E. C., 6, 490 (Oct.).
 Toms, A. H., 6, 406 (Oct.).
 Townend, C. B., 5, 579 (Apr.).
 Tranter, Eric, 4, 281 (Dec.); 6, 24 (June).
 Tripp, H. A., 4, 194 (Dec.).
 Tudsbury, M. T., 5, 389 (Mar.).
 Turner, Leslie, 5, 312 (Mar.).
 Walker, E. G., 6, 77 (June).
 Walker, J. H., 6, 389 (Oct.).
 Walker, Ronald, 6, 395 (Oct.).
 Walmsley, Dr. Thomas, 5, 390 (Mar.).
 Walters, R. C. S., 6, 155 (June).
 Warlow, W. P., 6, 491 (Oct.).
 Watson, D. M., 5, 463, 610 (Apr.); 6, 496 (Oct.).
 Watson, John D., 4, 1, 2, (Nov.); 5, 569 (Apr.).
 Webb, E. N., 4, 259 (Dec.); 6, 363 (Oct.).
 Weinrich, A. O., 6, 514 (Oct.).
 Wentholt, Dr. L. R., 4, 221 (Dec.); 6, 351 (Oct.).

- | | |
|---|---|
| Wentworth-Sheilds, F. E., 4, 448
(Jan.). | Williamson, James, 5, 65 (Feb.). |
| Whitehead, H. C., 5, 583 (Apr.). | Wilmot, H. F., 6, 523, 541 (Oct.). |
| Wileman, R. F., 6, 148 (June). | Wilson, C. A., 4, 250 (Dec.). |
| Wilkinson, G. W., 6, 492 (Oct.). | Wilson, J. S., 5, 59 (Feb.); 6, 20
(June). |
| Williams, C. G., 5, 771 (Apr.). | Wilson, M. F.-G., 4, 450 (Jan.). |
| Williams, G. B., 6, 395, 536 (Oct.). | |
-

COMBINED SUBJECT-INDEX

FOR

Volumes 4, 5 and 6, 1936-37.

November, 1936, to October, 1937, Journals.

4 refers to Volume 4, 1936-37, containing November and December, 1936, and January, 1937, Journals.

5 refers to Volume 5, 1936-37, containing February, March and April, 1937, Journals.

6 refers to Volume 6, 1936-37, containing June and October, 1937, Journals.

Address, Presidential, **4**, **4**, (Nov.).

Address, Sir Alexander Gibb's, to the British Association, **6**, 579, (Oct.).

Address to His Majesty King George VI, **6**, **1**, (June).

Annual General Meeting, **6**, 213, (June).

Arches.—"The Mechanics of the Voussoir Arch," Prof. A. J. S. Pippard, Eric Tranter, and Letitia Chitty, **4**, 281, (Dec.). Introduction, 281; review of accepted basis of design, 282; experimental apparatus, 283; calibration of apparatus, 286; experiments on two-pinned arch when span is kept constant, 286; experiments on two-pinned arch with abutments spread or contracted, 289; analytical explanation, 293; ultimate failure of two-pinned arch, 295; experiments on a fixed-end arch, 297; experiments on a fixed-end arch with abutments spread or contracted, 299; multiple loads on an arch, 301; summary and conclusion, 302; appendix, 304. *Discussion*, **6**, **5**, (June).

Associate, Election of an, **4**, 324, (Jan.).

Associate Members, Election of, **4**, 322, (Dec.); **5**, 89, (Feb.), 317, (Mar.), 619, (Apr.); **6**, 27, (June).

Automobile Engineering.—Symposium on Research in relation to the Motor Vehicle, **5**, 771, (Apr.). Section I, the motor vehicle (C. G. Williams), 771; section II, fuels and lubricants (F. H. Garner), 776; section III, materials, with special reference to steel (T. Swinden), 778.

Battersea Polytechnic Institute, Research Work in Engineering at, **4**, 490, (Jan.).

Bearings.—"Fluctuating Loads in Sleeve Bearings," Prof. H. W. Swift, **5**, 161, (Feb.). Introduction, 161; no rotation of shaft, radial movement of centre, 162; no rotation of shaft, rotary movement of centre, 173; shaft and load rotating, 176; general case of journal-movement, 178.

Bridges.—"Kincardine-on-Forth Bridge," J. G. Brown, **5**, 687, (Apr.). History, 687; site of bridge, 691; bores at site, 692; general description of bridge, 693; setting-out, 694; temporary bridge, 695; permanent timber jetty at main swing-span pier, 697; bridge piers, 699; concrete aggregates and mixtures, 713; swing-span, 724; wedges and locking bolts, 732; turning machinery, 736; control cabin and operation of swing-span, 741; portals and safety-gates, 746; power-consumption in moving bridge, 748; paint, 748; connecting roads, 749; expenditure, 750; conclusion, 750; appendices, 752. *Discussion*, 760. *Correspondence*, **6**, 519, (Oct.).

—"The Lower Zambezi Bridge," F. W. A. Handman, **4**, 325, (Jan.). Introduction, 325; object of the bridge, 326; river Zambezi, 328; geology of district, 328; site of bridge, 329; physiography of river at site, 332; hydrography of river at site, 334; the bridge, 336; main features of design, 336;

- well-sinking, 340; load on foundations, 347; steelwork, 347; viaduct, 349; footway, 353; railway track, 354; concrete, 354; setting-out, 356; painting, 358; connecting railways, 363; costs, 367; conclusion, 367. *Discussion*, 414. *Correspondence*, 6, 365, (Oct.).
- "The Construction of the Lower Zambezi Bridge," G. E. Howorth, 4, 369, (Jan.). Introduction, 369; preliminary arrangements at site, 369; personnel, 370; camp arrangements, 370; labour, 372; communications and construction of south connecting railway, 373; stone-supply, 374; survey for length, 377; general working methods and plant provisions, 378; projected sinking progress, 379; commencement of plant-deliveries and construction of barges and steamers, 380; constructional work, 381; sinking-effort and resistances, 399; viaduct pile-driving, 404; steelwork-erection, 405; stone-pitching around piers, 409; conclusion, 409; appendix, 411. *Discussion*, 414. *Correspondence*, 6, 365, (Oct.).
- "New German Bridges," G. Schaper, 6, 203, (June.)
- "Pre-Stressing Bridge Girders," H. J. Nichols, 5, 91, (Feb.). Introduction, 91; design, 93; instruments, 96; procedure, 99; primary stresses, 109; deformation stresses, 112; secondary stresses, 121; conclusions, 123; proposed modifications for pre-stressing, 124; acknowledgments, 129; appendix, 130. *Discussion*, 138. *Correspondence*, 6, 402, (Oct.).
- "Regirdering of Bridges on the Great Indian Peninsula Railway," William Hood, 4, 133, (Nov.).
- British Electrical and Allied Industries Research Association, The, 5, 785, (Apr.).
- Buildings.**—"An All-Welded Building in the United States of America," D. B. Johnston, 4, 307, (Dec.).
- Building Research Board, Report of the, for the Year 1935, 5, 230, (Feb.).
- Building Research Board, Report of the, for the Year 1936, 6, 582, (Oct.).
- Canals.**—"Newry Ship-Canal Improvement Scheme," Robert Ferguson, 4, 51, (Nov.). Historical, 51; introduction, 54; improvement scheme (1930), 58; description of works, 59; additional works, 72; conclusion, 74; appendices, 74. *Correspondence*, 6, 336, (Oct.).
- "Ship-Canals Utilized for Drainage," L. R. Wentholt, 4, 221, (Dec.). Introduction, 221; general remarks on ship-canals utilized for drainage, 225; permissible velocity of current in a ship-canal, 227; inflow structure for the Bolksbeek, 230; spillway at lock near Zutphen, 234; small inlet-structures, 243. *Discussion*, 245. *Correspondence*, 6, 345, (Oct.).
- Cement.**—Special Cements for Mass-Concrete Structures and their Specification, 5, 217, (Feb.), F. M. Lea.
- Measurements of Free Shrinkage and on Shrinkage-Cracking, 6, 272, (June).
- Comparison of Methods for Measuring the Heat of Hydration of Cements (F. M. Lea), 6, 275, (June.)
- The Testing of Pozzolanic Cements (F. M. Lea), 6, 278, (June).
- City and Guilds (Engineering) College, The, Research Work in Engineering at, 4, 148, (Nov.).
- Concrete.**—"Fundamental Research on the Application of Vibration to the Pre-Casting of Concrete," D. A. Stewart, 5, 318, (Mar.). Theoretical considerations, 318; description of apparatus, 321; tests, 325; phenomena observed during tests, 329; practical considerations of the effects of vibration on concrete, 332. *Discussion*, 336. *Correspondence*, 6, 440, (Oct.).
- Investigation on the Vibration of Concrete. Interim Report No. 1. Preliminary Tests. 5, 436, (Mar.).
- Corrosion.**—"Corrosion of Iron and Steel," Sir Robert Hadfield, Bart., and S. A. Main, *Late Correspondence*, 6, 549, (Oct.).
- See also Iron and Steel Institute.
- Council, Election of the, 6, 213, (June).
- Council, Report of the, 1936-37, 6, 216, (June). Coronation of King George VI, 216; patronage, 216; Ordinary Meetings, 216; Informal Meetings, 217; Lectures, 218; Joint Meetings, 218; Students' Meetings and Visits, 219;

- Local Associations, 219; research, 221; Sea-Action Committee, 223; Factories Bill, 223; Architects' Registration, 224; arbitration, 224; legislation affecting The Institution, 224; proposed L.C.C. Building By-Laws, 224; engineering and the public, 224; Engineering Congress, Glasgow, 1938, 225; "Engineering Abstracts," 225; co-operation, 225; nominations and appointments, 225; Ewing Medal, 228; Dugald Clerk Lecture, 228; scholarships, 228; Charles Hawkesley Prize, 228; building, 229; accounts, 229; library, 230; Tait room, 230; gifts, 230; Smeatonian Society, 231; use of building, 231; Annual Dinner, 231; Conversazione, 232; elections, transfers, and admissions, 232; examinations, 232; the Roll, 232; deaths, 233; erasure, 235; resignations, 235; appendix, 236.
- Cranes.**—"Moving a Tower Crane in connexion with the Building of the Q.S.S. 'Queen Mary,'" R. D. Brown, Jun., 4, 483, (Jan.).
- Crystal Structure.**—*James Forrest Lecture*: "The Crystal and the Engineer," Sir William Bragg, 6, 181, (June).
- Dams.**—"The Boulder Dam," J. L. Savage, 6, 161, (June). Chronological history, 161. Preparatory features, 163. Six Companies' plant and equipment, 163. Aggregate and mixing plants, 164. Main features of project: diversion-tunnels, 165; spillways, 168; dam, 170; intake-towers, 173; penstocks and outlet-conduits, 174; power plant, 177.
- "The Construction of Large Modern Water Dams," A. Coyne, 5, 401, (Mar.).
- Deaths, announcements of, 4, 1, (Nov.).
- Department of Scientific and Industrial Research, Report for the Year 1935-36, 5, 451, (Mar.).
- Deterioration of Structures in Sea-Water, Sixteenth (Interim) Report of the Institution Committee upon the, 5, 782, (Apr.).
- Docks. *See* Harbours and Docks.
- Drainage. *See* Reclamation and Drainage.
- Earthquake Effects on Rivers. *See* Rivers.
- Forest Products Research Board, Report of the, for the Year 1935, 4, 153, (Nov.). Forrest Lecture, 1937, The James. *See* Crystal Structure.
- Framed Structures.**—*Institution Lecture to Students*: "Modern Methods of Structural Design," Prof. J. F. Baker, 6, 297, (Oct.).
- "The Open-Frame Girder," G. S. Gough, 6, 247, (June). Introduction, 247; general method of analysis, 247; notation, 248; general equations for mid-panel moments, 249; girder of infinite length, 250; girder of finite length, 254; values of r , 256; girder with graduated verticals: approximate methods, 257; conclusion, 259; appendix, 260. *Correspondence*, 6, 545, (Oct.).
- "Simple Experimental Solutions of Certain Structural Design Problems," Prof. A. J. S. Pippard and S. R. Sparkes, 4, 79, (Nov.). Introduction, 79; theory of method employed, 80; experimental procedure, 81; examples, 81; conclusions, 90; addendum, 91. *Correspondence*, 6, 340, (Oct.).
- "Stress-Determination for a Three-Dimensional Rigid-Jointed Framework by the Method of Systematic Relaxation of Constraints," J. C. Richards, 5, 196. Foreword, 196; introduction, 202; particulars of structure, 204; the problem, 204; conclusions, 211.
- See also* Bridges—"Pre-Stressing Bridge Girders," H. J. Nichols.
- Fuel Research Board, Report of the, for the Year ended 31 March, 1936, 4, 315, (Dec.).
- Harbours and Docks.**—"The Maintenance of Waterways to Harbours and Docks," Raymond Carpmal, 4, 423, (Jan.). Introduction, 423; causes of siltation, 424; methods employed to maintain waterways, 431; short historical survey of dredging craft, 434; types of dredging craft, 437; organization (engineering), 440; statistics of dock- and channel-dredging, 440; methods of working employed, 441; modernization and centralization

- of the Great Western Railway fleet of dredgers, 442; appendix, 447. *Discussion*, 448.
- Honorary Members, Election of, 4, 1, (Nov.), 5, 461, (Apr.), 6, 3, (June).
- Hydraulics.**—"Experiments on the Flow of Water in Pipe-Bends," Herbert Addison, 6, 561, (Oct.).
- Induction of the President, 4, 1, (Nov.).
- Institution Lecture to Students, 1936-37. *See* Framed Structures.
- Iron and Steel Institute, Fourth Report of the Corrosion Committee of the, 4, 314, (Dec.).
- Jetties and Wharves.**—"Jetty Repairs on the River Thames," H. M. Gorringe, 5, 432, (Mar.).
- "Some Canadian Wharf-Structures of Steel Sheet-Piling," R. F. Legget, 6, 569, (Oct.).
- King's College, London University, Research Work in Engineering at, 4, 312, (Dec.).
- King's College, Newcastle-upon-Tyne, Research in Engineering at, 6, 585, (Oct.).
- Medals and Premiums Awarded, Session 1935-36, 4, 18, (Nov.).
- Members, Election of, 4, 322, (Jan.); 5, 89, (Feb.), 317, (Mar.), 619, (Apr.).
- Members, Transfers to the Class of, 4, 321, (Jan.); 5, 1, (Feb.); 241, (Mar.), 461, (Apr.); 6, 3, (June).
- Mud-Runs.**—"The Treatment of Mud-Runs in Bolivia," S. W. F. Morum: *Author's Reply to Discussion and Correspondence*, 4, 484, (Jan.). [For Paper, Discussion, and Correspondence, *see* 1, 426 (Jan. 1936) and 564* (Oct. 1936).]
- National Physical Laboratory, Report of the, for the Year 1936, 6, 283, (June).
- Obituary.**—Sir Brodie Henderson, 5, 239, (Feb.); Sir John Aspinall, 5, 795, (Apr.); Elihu Thomson, 6, 295, (June); Dr. H. H. Jeffcott, 6, 595, (Oct.).
- Original Communications, Additional, received between 1 April, 1935, and 31 August, 1937, 6, 575, (Oct.).
- Pelton Wheels.—*See* Water-Power.
- Publications, Notes on Research.—*See* Research.
- Queen Mary College (University of London), Research Work in Engineering at, 6, 281, (June).
- Radio-Telephony.**—"Modern Developments in Broadcasting Transmission and Television," Sir Noel Ashbridge, 5, 349, (Mar.). Introduction, 349; the home service, 351; the overseas or Empire service, 368; television, 373. *Discussion*, 384.
- Railways and Rail Transport.**—"The Diversion of the Main Line between Mottram and Dinting, London and North-Eastern Railway," F. W. Slade, 4, 469, (Jan.). Introduction, 469; earthwork and culverts, 470.
- "A Proposed Formula for Use in Traffic Surveys, Particularly Applicable to the Construction of Branch-Line Railways in India and Similar Countries," W. E. R. Gurney, 6, 565, (Oct.).
- Rainfall and Run-Off.**—"The Estimation of Run-Off from Areas Subjected to Rainstorms," J. R. Daymond, 6, 268, (June).
- "Flood-Hydrographs," B. D. Richards, 5, 405, (Mar.). Part I: introduction, 405; methods of flood-estimation, 406; flood-hydrographs, 415; large catchment-areas, 419; check of result obtained from formulas by actual flood-records, 421; special cases in which the formulas do not apply, 421; conclusion, 421. Part II: determination of reservoir lag-effect, 422; appendix, 430. *Correspondence*, 6, 451, (Oct.).

- "The Flow of the River Severn, 1921-36," Prof. S. M. Dixon, Gerald FitzGibbon, and M. A. Hogan, 6, 81, (June). Introduction, 81; description of catchment, 82; selection of gauge-points and gauging-section, 84; methods of discharge-measurement, 85; accuracy of discharge-measurements, 89; characteristics of gauging-section, 90; stage-discharge curve, 90; calculation of daily discharges, 93; comparison of different gauges, 94; description of typical hydrographs, 95; floods, 98; duration-curves, 99; variations in discharge, 101; rainfall, 101; relation between rainfall and run-off, 105; acknowledgments, 108; appendixes, 110. *Discussion*, 114. *Correspondence*, 525, (Oct.).
- Reclamation and Drainage.**—"The Lake Copais, Boeotia, Greece: Its Drainage and Development," A. J. Dean, 5, 287, (Mar.). Introduction, 287; ancient drainage, 289; drainage under the French company, 289; work of the British company, 290; exterior drainage, 291; interior drainage and development, 293; drainage-improvement works, 294; results and benefits, 300; position to-day, 301; appendix, 303. *Discussion*, 305. *Correspondence*, 6, 419, (Oct.).
- "The Salonika Plain Reclamation-Works," B. W. Huntsman, 5, 243, (Mar.). Description of the country, 243; the contract and its objects, 246; design of works, 247; construction, 259; results and conclusions, 266; appendixes, 277. *Discussion*, 305. *Correspondence*, 6, 419, (Oct.).
- Research.**—Engineering Research, 4, 135, (Nov.), 310, (Dec.), 488, (Jan.); 5, 217, (Feb.), 435, (Mar.), 782, (Apr.); 6, 272, (June), 579, (Oct.).
- Institution Research Committee, The, 4, 135, (Nov.), 310, (Dec.), 488, (Jan.); 5, 217, (Feb.), 435, (Mar.), 783, (Apr.); 6, 272, (June), 581, (Oct.).
- Notes on Research Publications, 4, 154, (Nov.), 315, (Dec.), 492, (Jan.); 5, 232, (Feb.), 453, (Mar.), 787, (Apr.); 6, 288, (June), 587, (Oct.).
- Rivers.**—"The North Bihar Group of the Rivers and Waterways of the Gangetic Plain before and after the Earthquake of the 15th January, 1934," F. C. Temple, 5, 780, (Apr.).
- *See also Rainfall and Run-Off.*
- River Training.**—"The Restoration of the Breach in the Right Guide Bank of the Hardinge Bridge," B. L. Harvey, 4, 21, (Nov.). Introduction, 21; river Ganges, 23; Damukdia guide bank, 25; causes of breach of right guide bank, 26; breach, 29; scheme for safety of bridge, 33; construction of mole and backwater bund, 36; other works carried out, 40; medical arrangements, 44; cost, 44; flood season 1934, 44; restoration of breach, 45; flood season 1935, 47; conclusion, 48; acknowledgments, 49; staff, 50; appendix, 50. *Correspondence*, 6, 325, (Oct.).
- Road Research Board, Report of the, for the Year ended 31st March, 1936, 6, 285, (June).
- Roads and Road Transport.**—"The Reconstruction of the Chester-Holyhead Road near Penmaenmawr, North Wales," C. L. H. Humphreys, 6, 28, (June). Introduction, 28. Penmaenbach diversion: historical and general notes, 29; early surveys for diversion-schemes, 30; main sections of diversion, 31; notes on design, 35; construction of main works, 35; special points of interest, 39. Penycip diversion: historical and general notes, 42; recent traffic-difficulties on old road, 43; surveys for present diversion-scheme, 44; main sections of diversion, 45; some special supporting works, 59; tests on foundations, 65; tests on concrete, 66; Viaduct Bay, 67; conclusion, 67; appendix, 69. *Discussion*, 70. *Correspondence*, 521, (Oct.).
- "Road Design and Road Safety," F. C. Cook, 4, 161, (Dec.). Introduction, 161; analyses of accidents, 162; design of roads, 168; road intersections, 177; road surfaces, 179; by-passes, 182; existing roads, 182; street-lighting, 185; accident maps, 185; road vehicles, 188; conclusions, 189. *Discussion*, 191.
- "Roads and Road Transport in Tanganyika Territory," W. H. McLuckie, 6, 572, (Oct.).
- "Road Traffic considered as a Random Series," W. F. Adams, 4, 121, (Nov.). Introduction, 121; general considerations, 122; method of using

- curves, 124; examples, 125; observations on results of example 3, 127; conclusion, 129.
- "A Study of the Underground Road Crossings of Paris," Gaston Bardet, 4, 255, (Dec.).
- Sea-Action.—*See* Deterioration of Structures in Sea-Water.
- Sewerage and Sewage-Disposal.—"West Middlesex Main Drainage," D. M. Watson, 5, 463, (Apr.). Introduction, 463; history, 463; main sewerage, 468; effluent-conduits and outfalls, 492; Mogden purification-works, 498; Perry Oaks sludge-disposal works, 549; cost, 554; appendixes, 558. *Discussion*, 569. *Correspondence*, 6, 473, (Oct.).
- Soil Mechanics.—"The Active and Passive Pressures of Sea-Sand Behind a Vertical Wall," A. A. Fordham, 4, 131, (Nov.).
- Report on the First International Conference on Soil Mechanics and Foundation Engineering, L. F. Cooling, 4, 135, (Nov.).
- Special Lecture.—*See* Dams—"The Boulder Dam," J. L. Savage.
- Strength of Materials.—"Repeated Stresses on Structural Elements," Prof. F. C. Lea, 4, 93, (Nov.). Introduction, 93; experiments on mild-steel "black" plates, 95; comparison of results of repeated-stress tests with theoretical investigations and photo-elastic tests, 104; failure of riveted specimens under repeated stresses, and effect of tightness of grip of cover-plates, 107; wire for suspension-bridges, and repeated-stress tests on cold-drawn wires, 111; repeated-stress tests of weld-metal and welded joints, 117. *Correspondence*, 6, 341, (Oct.).
- Students, Admission of, 4, 321, (Jan.); 5, 1, (Feb.), 241, (Mar.), 461, (Apr.); 6, 3, (June).
- Television. *See* Radio-Telephony.
- Thermodynamics.—"The Indicator-Diagram and its Interpretation," Robert Dowson, 6, 263, (June).
- Transformers.—"The Impedance of Transformers Connected in Cascade," B. L. Goodlet, 4, 475, (Jan.). Introduction, 475; cascade of two units, 476; cascade of three units, 478; appendix, 480.
- Victoria University, Manchester, Research Work in Engineering at, 5, 450, (Mar.).
- Water Pollution Research Board, Report of the, for the Year ended 30th June, 1936; 5, 784, (Apr.).
- Water-Power.—"Efficiency Tests of Large Modern Pelton Wheels," E. N. Webb, 4, 259, (Dec.). Introduction, 259; loading the sets, 261; measuring the load, 263; measurement of water-supply, 264; programme for tests, 267; computation of quantity, Q , 268; efficiency computations, 271; discussion of efficiencies, 275; flow of water in supply-pipe, 277; cognate experience, 280. *Correspondence*, 6, 357, (Oct.).
- "The Second-Stage Development of the Lochaber Water-Power Scheme," A. H. Naylor, 5, 3, (Feb.). Introduction, 3; second-stage development, general considerations of design, 5; detailed considerations of design, 7; construction, 21; study of internal temperature and formation of cracks in Laggan dam, 32; deflexion of Laggan dam, 41; conclusion, 42; appendixes, 43. *Discussion*, 49. *Correspondence*, 6, 381, (Oct.).
- Welding.—"Welded Joints in Pressure-Vessels," S. F. Dorey, 5, 621, (Apr.). Introduction, 621; design, 624; workmanship, 626; material, 628; welded joints, 637; joint-efficiencies, 640; procedure control and testing of welded joints, 646; heat-treatment, 655; X-ray examination, 660; conclusion, 664; acknowledgments, 666. *Discussion*, 667. *Correspondence*, 6, 501, (Oct.).
- Wharves. *See* Jetties and Wharves.
- Woolwich Polytechnic, Research Work in Engineering at, 5, 229, (Feb.).